

LilyPond

Snippets

The music typesetter

The LilyPond development team

This document shows a selected set of LilyPond snippets from the [LilyPond Snippet Repository](#) (LSR). It is in the public domain.

We would like to address many thanks to Sebastiano Vigna for maintaining LSR web site and database, and the University of Milano for hosting LSR.

Please note that this document is not an exact subset of LSR: some snippets come from ‘`input/new`’ LilyPond sources directory, and snippets from LSR are converted through `convertly`, as LSR is based on a stable LilyPond version, and this document is for version 2.18.2.

Snippets are grouped by tags; tags listed in the table of contents match a section of LilyPond notation manual. Snippets may have several tags, and not all LSR tags may appear in this document.

In the HTML version of this document, you can click on the file name or figure for each example to see the corresponding input file.

For more information about how this manual fits with the other documentation, or to read this manual in other formats, see [Section “Manuals” in General Information](#).

If you are missing any manuals, the complete documentation can be found at <http://www.lilypond.org/>.

This document has been placed in the public domain.

For LilyPond version 2.18.2

Table of Contents

Pitches	1
Adding ambitus per voice.....	1
Adding an ottava marking to a single voice.....	1
Altering the length of beamed stems	2
Ambitus with multiple voices	2
Ambitus.....	3
Applying note head styles depending on the step of the scale	3
Automatically changing the stem direction of the middle note based on the melody	4
Changing the ambitus gap	5
Changing the interval of lines on the stave	6
Clefs can be transposed by arbitrary amounts	6
Coloring notes depending on their pitch	7
Creating a sequence of notes on various pitches.....	8
Forcing a clef symbol to be displayed.....	8
Generating random notes	9
Hiding accidentals on tied notes at the start of a new system	9
Keep change clefs full sized	9
Makam example	10
Non-traditional key signatures	10
Numbers as easy note heads	11
Orchestra choir and piano template	12
Ottava text.....	15
Preventing extra naturals from being automatically added.....	16
Preventing natural signs from being printed when the key signature changes	16
Quoting another voice with transposition	16
Separating key cancellations from key signature changes.....	17
Transposing pitches with minimum accidentals ("Smart" transpose)	18
Tweaking clef properties	19
Using autochange with more than one voice	21
Rhythms	22
Adding beams slurs ties etc. when using tuplet and non-tuplet rhythms	22
Adding drum parts	22
Adjusting grace note spacing	23
Aligning bar numbers.....	23
Alternative breve notes	24
Automatic beam subdivisions	24
Automatically change durations.....	25
Avoiding collisions with chord fingerings	26
Beam endings in Score context.....	26
Beam grouping in 7/8 time	27
Beams across line breaks	27
Changing beam knee gap	28
Changing form of multi-measure rests	28
Changing the number of augmentation dots per note	28
Changing the tempo without a metronome mark	29
Changing the tuplet number	29
Changing time signatures inside a polymetric section using \scaleDurations	30

Chant or psalms notation	30
Compound time signatures	31
Conducting signs measure grouping signs	31
Consistently left aligned bar numbers	32
Controlling tuplet bracket visibility	33
Creating metronome marks in markup mode	34
Engraving ties manually	34
Engraving tremolos with floating beams	34
Entering several tuplets using only one \tuplet command	35
Flat flags and beam nibs	36
Forcing rehearsal marks to start from a given letter or number	37
Generating custom flags	37
Guitar strum rhythms	39
Heavily customized polymetric time signatures	40
Making an object invisible with the 'transparent property	41
Making slurs with complex dash structure	41
Manually controlling beam positions	42
Merging multi-measure rests in a polyphonic part	42
Modifying tuplet bracket length	43
Moving dotted notes in polyphony	43
Multi-measure rest markup	44
Non-default tuplet numbers	44
Partcombine and autoBeamOff	45
Permitting line breaks within beamed tuplets	46
Positioning grace note beams at the height of normal note beams	46
Positioning grace notes with floating space	47
Positioning multi-measure rests	47
Preventing final mark from removing final tuplet	48
Printing bar numbers at regular intervals	49
Printing bar numbers inside boxes or circles	50
Printing metronome and rehearsal marks below the staff	50
Printing music with different time signatures	51
Printing the bar number for the first measure	54
Redefining grace note global defaults	54
Removing bar numbers from a score	55
Removing connecting bar lines on StaffGroup PianoStaff or GrandStaff	55
Rest styles	56
Reverting default beam endings	57
Rhythmic slashes	57
Skips in lyric mode (2)	58
Skips in lyric mode	58
Stemlets	59
Strict beat beaming	59
Subdividing beams	59
Three-sided box	60
Time signature printing only the numerator as a number (instead of the fraction)	61
Tweaking grace layout within music	61
Using alternative flag styles	62
Using grace note slashes with normal heads	63
Using ties with arpeggios	63

Expressive marks	64
Adding beams slurs ties etc. when using tuplet and non-tuplet rhythms	64
Adding parentheses around an expressive mark or chordal note	64
Adding timing marks to long glissandi	64
Adjusting the shape of falls and doits	65
Alternative breve notes	65
Asymmetric slurs	66
Breathing signs	66
Broken Crescendo Hairpin	67
Caesura ("railtracks") with fermata	68
Center text below hairpin dynamics	68
Changing \flageolet mark size	70
Changing text and spanner styles for text dynamics	70
Changing the appearance of a slur from solid to dotted or dashed	70
Changing the breath mark symbol	71
Changing the number of augmentation dots per note	71
Combining dynamics with markup texts	71
Contemporary glissando	72
Controlling spanner visibility after a line break	72
Controlling the vertical ordering of scripts	73
Creating a delayed turn	73
Creating arpeggios across notes in different voices	74
Creating cross-staff arpeggios in a piano staff	74
Creating cross-staff arpeggios in other contexts	75
Creating double-digit fingerings	75
Creating "real" parenthesized dynamics	76
Creating simultaneous rehearsal marks	76
Creating slurs across voices	77
Creating text spanners	78
Double glissando	78
Dynamics custom text spanner postfix	79
Dynamics text spanner postfix	80
Glissandi can skip grobs	80
Hairpins with different line styles	80
Hiding the extender line for text dynamics	81
Horizontally aligning custom dynamics (e.g. "sempre pp" "piu f" "subito p")	81
How to print two rehearsal marks above and below the same barline (method 1)	84
How to print two rehearsal marks above and below the same barline (method 2)	85
Inserting a caesura	86
Laissez vibrer ties	86
Line arrows	87
Making slurs with complex dash structure	87
Modifying default values for articulation shorthand notation	88
Moving slur positions vertically	88
Positioning arpeggios	89
Positioning text markups inside slurs	89
Printing hairpins in various styles	90
Printing hairpins using al niente notation	90
Printing metronome and rehearsal marks below the staff	91
Setting hairpin behavior at bar lines	91
Setting the minimum length of hairpins	91
Showing the same articulation above and below a note or chord	92
Snap-pizzicato or Bartok pizzicato	92
Using a tick as the breath mark symbol	93

Using arpeggioBracket to make divisi more visible	93
Using double slurs for legato chords	94
Using the whiteout property	94
Vertical line as a baroque articulation mark	95
Vertically aligning dynamics across multiple notes	95
Repeats	96
Adding volta brackets to additional staves	96
Centered measure numbers	96
Cross-staff tremolos	97
Engraving tremolos with floating beams	98
Isolated percent repeats	98
Measure counter	99
Numbering groups of measures	99
Percent repeat count visibility	100
Percent repeat counter	101
Positioning segno and coda (with line break)	101
Printing a repeat sign at the beginning of a piece	103
Setting the double repeat default for <code>volte</code>	104
Shortening volta brackets	104
Volta below chords	105
Volta multi staff	105
Volta text markup using <code>repeatCommands</code>	106
Simultaneous notes	107
Additional voices to avoid collisions	107
Changing a single note's size in a chord	107
Changing partcombine texts	108
Clusters	108
Combining two parts on the same staff	109
Displaying complex chords	110
Double glissando	110
Forcing horizontal shift of notes	111
Making an object invisible with the ' <code>transparent</code> property	111
Moving dotted notes in polyphony	112
Suppressing warnings for clashing note columns	112
Staff notation	114
Adding ambitus per voice	114
Adding an extra staff at a line break	114
Adding an extra staff	115
Adding indicators to staves which get split after a break	116
Adding orchestral cues to a vocal score	118
Adding timing marks to long glissandi	119
Alternative bar numbering	120
Centered measure numbers	121
Changing the number of lines in a staff	122
Changing the staff size	123
Creating blank staves	123
Creating double-digit fingerings	125
Cross staff stems	125
Display bracket with only one staff in a system	126
Extending glissandi across repeats	126

Forcing measure width to adapt to MetronomeMark's width	128
Glissandi can skip grobs	128
How to print two rehearsal marks above and below the same barline (method 1)	128
How to print two rehearsal marks above and below the same barline (method 2)	129
Incipit	130
Inserting score fragments above a staff as markups	136
Letter tablature formatting	137
Making glissandi breakable	137
Making some staff lines thicker than the others	138
Measure counter	138
Mensurstriche layout (bar lines between the staves)	139
Nesting staves	139
Non-traditional key signatures	140
Numbering groups of measures	140
Orchestra choir and piano template	142
Putting lyrics inside the staff	145
Quoting another voice with transposition	146
Quoting another voice	146
Removing the first empty line	147
Setting system separators	148
Tick bar lines	151
Time signature in parentheses - method 3	151
Time signature in parentheses	151
Tweaking clef properties	151
Use square bracket at the start of a staff group	153
Using autochange with more than one voice	153
Vertical aligned StaffGroups without connecting SystemStartBar	154
Volta below chords	162
Volta multi staff	163
Editorial annotations	164
Adding fingerings to a score	164
Adding links to objects	164
Allowing fingerings to be printed inside the staff	165
Alternative bar numbering	166
Analysis brackets above the staff	167
Applying note head styles depending on the step of the scale	167
Avoiding collisions with chord fingerings	168
Blanking staff lines using the \whiteout command	168
Changing a single note's size in a chord	169
Changing the appearance of a slur from solid to dotted or dashed	169
Coloring notes depending on their pitch	169
Controlling the placement of chord fingerings	170
Creating a delayed turn	171
Creating blank staves	171
Creating double-digit fingerings	173
Default direction of stems on the center line of the staff	173
Drawing boxes around grobs	173
Drawing circles around note heads	174
Drawing circles around various objects	174
Embedding native PostScript in a \markup block	175
Grid lines: changing their appearance	175
Grid lines: emphasizing rhythms and notes synchronization	176
Hammer on and pull off using chords	177

Hammer on and pull off using voices	178
Hammer on and pull off	178
How to print two rehearsal marks above and below the same barline (method 1)	178
How to print two rehearsal marks above and below the same barline (method 2)	179
Making some staff lines thicker than the others	180
Marking notes of spoken parts with a cross on the stem	180
Measure counter	181
Numbering groups of measures	181
Positioning fingering indications precisely	183
Positioning text markups inside slurs	183
Printing text from right to left	183
String number extender lines	184
Using PostScript to generate special note head shapes	184
Using the whiteout property	185
Text	186
Adding the current date to a score	186
Adjusting lyrics vertical spacing	186
Aligning and centering instrument names	187
Aligning objects created with the \mark command	188
Aligning syllables with melisma	189
Blanking staff lines using the \whiteout command	189
Center text below hairpin dynamics	190
Centering markup on note heads automatically	191
Changing the default text font family	192
Combining dynamics with markup texts	193
Combining two parts on the same staff	193
Creating "real" parenthesized dynamics	195
Creating simultaneous rehearsal marks	195
Creating text spanners	196
Demonstrating all headers	197
Embedding native PostScript in a \markup block	198
Formatting lyrics syllables	198
How to put ties between syllables in lyrics	199
Lyrics alignment	199
Markup lines	199
Multi-measure rest markup	201
Ottava text	202
Outputting the version number	202
Piano template with centered lyrics	202
Printing marks at the end of a line	203
Printing marks on every staff	204
Printing text from right to left	204
Putting lyrics inside the staff	205
Stand-alone two-column markup	205
String number extender lines	206
Three-sided box	206
UTF-8	207
Vocal ensemble template with lyrics aligned below and above the staves	209
Volta text markup using repeatCommands	210

Vocal music	211
Adding ambitus per voice.....	211
Adding indicators to staves which get split after a break	211
Adding orchestral cues to a vocal score	213
Adjusting lyrics vertical spacing	215
Aligning syllables with melisma.....	215
Ambitus with multiple voices	216
Ambitus	216
Ancient notation template – modern transcription of gregorian music.....	217
Anglican psalm template	218
Changing stanza fonts	221
Chant or psalms notation.....	221
Forcing hyphens to be shown	222
Formatting lyrics syllables.....	222
How to put ties between syllables in lyrics	223
Hymn template	223
Lyrics alignment	225
Marking notes of spoken parts with a cross on the stem	226
Obtaining 2.12 lyrics spacing in newer versions.....	226
Orchestra choir and piano template	229
Piano template with melody and lyrics	232
Putting lyrics inside the staff	233
SATB Choir template - four staves	234
Single staff template with notes lyrics and chords	235
Single staff template with notes lyrics chords and frets	236
Single staff template with notes and lyrics	237
Skips in lyric mode (2)	238
Skips in lyric mode	238
Using arpeggioBracket to make divisi more visible	238
Vertically aligning ossias and lyrics	239
Vertically centered common lyrics	240
Vocal ensemble template with automatic piano reduction.....	241
Vocal ensemble template with lyrics aligned below and above the staves	243
Vocal ensemble template with verse and refrain	244
Vocal ensemble template	246
Chords	249
Adding a figured bass above or below the notes	249
Adding bar lines to ChordNames context	249
Avoiding collisions with chord fingerings	250
Bar chords notation for Guitar (with Text Spanner).....	250
Changing chord separator	251
Changing the chord names to German or semi-German notation.....	252
Changing the positions of figured bass alterations	252
Chord name exceptions	253
chord name major7	253
Clusters	254
Controlling the placement of chord fingerings	254
Cross-staff chords - beaming problems workaround	255
Displaying complex chords.....	255
Manually break figured bass extenders for only some numbers	256
Showing chords at changes	256
Simple lead sheet.....	257

Single staff template with notes lyrics and chords	257
Single staff template with notes lyrics chords and frets	258
Single staff template with notes and chords	259
Vertically centering paired figured bass extenders	259
Volta below chords	260
Keyboards	262
Accordion-discant symbols.....	262
Accordion register symbols	265
Changing the text for sustain markings	266
Clusters	266
Controlling the placement of chord fingerings	267
Creating slurs across voices	267
Cross-staff chords - beaming problems workaround	268
Cross-staff tremolos	269
Fine-tuning pedal brackets	269
Indicating cross-staff chords with arpeggio bracket	270
Jazz combo template	270
Laissez vibrer ties	276
Piano template (simple)	277
Piano template with centered lyrics	277
Piano template with melody and lyrics	278
Using autochange with more than one voice	279
Vocal ensemble template with automatic piano reduction.....	280
Percussion	283
Adding drum parts	283
Heavily customized polymetric time signatures	283
Jazz combo template	284
Percussion beaters	290
Printing music with different time signatures	293
Fretted strings	297
Adding fingerings to a score	297
Adding fingerings to tablatures	297
Allowing fingerings to be printed inside the staff	298
Bar chords notation for Guitar (with Text Spanner).....	298
Changing fret orientations	299
Chord glissando in tablature	300
ChordChanges for FretBoards	300
Controlling the placement of chord fingerings	301
Customizing fretboard fret diagrams	302
Customizing markup fret diagrams	303
Defining predefined fretboards for other instruments	304
Faking a hammer in tablatures	306
Fingerings string indications and right-hand fingerings	307
Flamenco notation	307
Fret diagrams explained and developed	312
Fretboards alternate tables	318
Fretted-string harmonics in tablature	320
Guitar slides	321
Guitar strum rhythms	322
Hammer on and pull off using chords	323

Hammer on and pull off using voices	324
Hammer on and pull off	324
How to change fret diagram position	324
Jazz combo template	325
Laissez vibrer ties	331
Letter tablature formatting	332
Open string harmonics in tablature	332
Placement of right-hand fingerings	334
Polyphony in tablature	334
Slides in tablature	335
Stem and beam behavior in tablature	336
String number extender lines	336
Unfretted strings.....	338
Changing \flageolet mark size	338
Creating slurs across voices	338
Dotted harmonics	339
Snap-pizzicato or Bartok pizzicato	339
String quartet template (simple)	339
String quartet template with separate parts	341
Winds.....	344
Changing the size of woodwind diagrams	344
Fingering symbols for wind instruments	344
Flute slap notation	345
Graphical and text woodwind diagrams	346
Recorder fingering chart	346
Woodwind diagrams key lists	347
Woodwind diagrams listing	348
Ancient notation.....	351
Adding a figured bass above or below the notes	351
Ancient fonts	351
Ancient notation template – modern transcription of gregorian music	356
Ancient notation template – modern transcription of mensural music	357
Ancient time signatures	362
Chant or psalms notation	362
Custodes	363
Incipit	364
Mensurstriche layout (bar lines between the staves)	369
Rest styles	370
Transcription of Ancient music with incipit	371
Vertical line as a baroque articulation mark	377
World music.....	378
Arabic improvisation	378
Makam example	378
Printing text from right to left	378

Contexts and engravers	380
Adding a figured bass above or below the notes	380
Adding an extra staff at a line break	380
Adding an extra staff	381
Automatically changing the stem direction of the middle note based on the melody	382
Centered measure numbers	382
Centering markup on note heads automatically	383
Changing MIDI output to one channel per voice	384
Changing time signatures inside a polymetric section using \scaleDurations	385
Chant or psalms notation	386
Creating blank staves	387
Cross staff stems	388
Defining an engraver in Scheme: ambitus engraver	389
Displaying a whole GrandStaff system if only one of its staves is alive	395
Engravers one-by-one	397
Mensurstriche layout (bar lines between the staves)	402
Nesting staves	403
Numbering groups of measures	403
Removing bar numbers from a score	404
Use square bracket at the start of a staff group	405
Vocal ensemble template with lyrics aligned below and above the staves	405
Vocal ensemble template with verse and refrain	407
Tweaks and overrides	410
Adding an ottava marking to a single voice	410
Adding links to objects	410
Adding timing marks to long glissandi	412
Adjusting grace note spacing	413
Altering the length of beamed stems	413
Alternative bar numbering	414
Analysis brackets above the staff	415
Asymmetric slurs	415
Avoiding collisions with chord fingerings	415
Caesura ("railtracks") with fermata	416
Centering markup on note heads automatically	416
Changing a single note's size in a chord	417
Changing form of multi-measure rests	418
Changing properties for individual grobs	418
Changing text and spanner styles for text dynamics	419
Changing the default text font family	419
Changing the staff size	420
Changing the tempo without a metronome mark	420
Changing the text for sustain markings	421
Controlling spanner visibility after a line break	421
Controlling the vertical ordering of scripts	422
Controlling tuplet bracket visibility	422
Creating a delayed turn	423
Creating double-digit fingerings	424
Creating simultaneous rehearsal marks	424
Creating text spanners	425
Cross-staff chords - beaming problems workaround	425
Cross staff stems	426
Custodes	427

Customizing fretboard fret diagrams	428
Customizing markup fret diagrams	429
Display bracket with only one staff in a system	430
Displaying grob ancestry	431
Dotted harmonics	433
Drawing boxes around grobs	433
Drawing circles around various objects	434
Dynamics custom text spanner postfix	434
Dynamics text spanner postfix	435
Extending glissandi across repeats	435
Fine-tuning pedal brackets	436
Forcing horizontal shift of notes	437
Fret diagrams explained and developed	437
Generating custom flags	444
Glissandi can skip grobs	445
Hairpins with different line styles	445
Horizontally aligning custom dynamics (e.g. "sempre pp" "piu f" "subito p")	446
How to change fret diagram position	449
How to print two rehearsal marks above and below the same barline (method 1)	450
How to print two rehearsal marks above and below the same barline (method 2)	451
Inserting a caesura	452
Keep change clefs full sized	452
Line arrows	453
Making an object invisible with the 'transparent' property	454
Making glissandi breakable	454
Manually controlling beam positions	455
Mensurstriche layout (bar lines between the staves)	455
Moving dotted notes in polyphony	456
Moving slur positions vertically	456
Nesting staves	457
Overriding articulations of distinct type	458
Percent repeat count visibility	459
Positioning arpeggios	460
Positioning multi-measure rests	460
Positioning text markups inside slurs	461
Printing a repeat sign at the beginning of a piece	461
Printing bar numbers inside boxes or circles	462
Printing metronome and rehearsal marks below the staff	462
Printing note names with and without an octave marker	463
Proportional strict notespacing	463
Removing connecting bar lines on StaffGroup PianoStaff or GrandStaff	464
Removing the first empty line	465
Rest styles	466
Rhythmic slashes	467
Separating key cancellations from key signature changes	468
Setting hairpin behavior at bar lines	468
Setting system separators	468
Showing the same articulation above and below a note or chord	471
String number extender lines	471
Suppressing warnings for clashing note columns	472
Time signature in parentheses - method 3	472
Time signature in parentheses	473
Time signature printing only the numerator as a number (instead of the fraction)	473
Transcription of Ancient music with incipit	473

Tweaking clef properties	479
Tweaking grace layout within music	481
Using alternative flag styles	481
Using ly:grob-object to access grobs with \tweak	482
Using PostScript to generate special note head shapes	483
Using the \tweak command to tweak individual grobs	484
Vertically aligned dynamics and textscripts	484
Vertically aligning ossias and lyrics	485
Vertically centering paired figured bass extenders	486
Paper and layout	487
Aligning and centering instrument names	487
Book parts	488
Changing the staff size	492
Clip systems	493
Creating blank staves	496
Demonstrating all headers	497
Setting system separators	498
Table of contents	500
Vertical aligned StaffGroups without connecting SystemStartBar	501
Titles	510
Adding the current date to a score	510
Aligning and centering instrument names	510
Demonstrating all headers	512
Outputting the version number	513
Spacing	514
Adjusting lyrics vertical spacing	514
Allowing fingerings to be printed inside the staff	514
Page label	515
Proportional strict notespacing	517
Vertically aligned dynamics and textscripts	518
Vertically aligning ossias and lyrics	518
MIDI	520
Changing MIDI output to one channel per voice	520
Changing the tempo without a metronome mark	521
Demo MidiInstruments	521
Templates	525
Ancient notation template – modern transcription of gregorian music	525
Ancient notation template – modern transcription of mensural music	526
Anglican psalm template	531
Hymn template	534
Jazz combo template	536
Orchestra choir and piano template	542
Piano template (simple)	545
Piano template with centered lyrics	546
Piano template with melody and lyrics	547
SATB Choir template - four staves	548
Score for diatonic accordion	550

Single staff template with notes lyrics and chords	554
Single staff template with notes lyrics chords and frets	555
Single staff template with notes and chords	556
Single staff template with notes and lyrics	557
Single staff template with only notes.....	557
String quartet template (simple).....	558
String quartet template with separate parts.....	559
Vocal ensemble template with automatic piano reduction.....	561
Vocal ensemble template with lyrics aligned below and above the staves	564
Vocal ensemble template with verse and refrain	565
Vocal ensemble template	567

Pitches

Section “Pitches” in *Notation Reference*

Adding ambitus per voice

Ambitus can be added per voice. In this case, the ambitus must be moved manually to prevent collisions.

```
\new Staff <<
  \new Voice \with {
    \consists "Ambitus_engraver"
  } \relative c'' {
    \override Ambitus.X-offset = #2.0
    \voiceOne
    c4 a d e
    f1
  }
  \new Voice \with {
    \consists "Ambitus_engraver"
  } \relative c' {
    \voiceTwo
    es4 f g as
    b1
  }
>>
```




Adding an ottava marking to a single voice

If you have more than one voice on the staff, setting octavation in one voice will transpose the position of notes in all voices for the duration of the ottava bracket. If the ottavation is only intended to apply to one voice, the middleCPosition and ottava bracket may be set explicitly. In this snippet, the bass clef usually has middleCPosition set to 6, six positions above the center line, so in the 8va portion middleCPosition is 7 positions (one octave) higher still.

```
{
  \clef bass
  << { <g d'>1~ q2 <c' e'> }
  \\
  {
    r2.
    \set Staff.ottavation = #"8vb"
    \once \override Staff.OttavaBracket.direction = #DOWN
    \set Voice.middleCPosition = #(+ 6 7)
    <b,,, b,,,>4 ~ |
    q2
    \unset Staff.ottavation
    \unset Voice.middleCPosition
    <c e>2
  }
```

```
>>
}




A musical staff in bass clef and common time. It contains two 16th notes. The first 16th note has a standard stem length. The second 16th note has a stem length that is shorter than the first, indicated by the instruction 8vb below it.


```

Altering the length of beamed stems

Stem lengths on beamed notes can be varied by overriding the `beamed-lengths` property of the `details` of the `Stem`. If a single value is used as an argument, the length applies to all stems. When multiple arguments are used, the first applies to eighth notes, the second to sixteenth notes and so on. The final argument also applies to all notes shorter than the note length of the final argument. Non-integer arguments may also be used.

```
\relative c' {
    \override Stem.details.beamed-lengths = #'(2)
    a8[ a] a16[ a] a32[ a]
    \override Stem.details.beamed-lengths = #'(8 10 12)
    a8[ a] a16[ a] a32[ a] r8
    \override Stem.details.beamed-lengths = #'(8)
    a8[ a]
    \override Stem.details.beamed-lengths = #'(8.5)
    a8[ a]
    \revert Stem.details
    a8[ a] a16[ a] a32[ a] r16
}
```



Ambitus with multiple voices

Adding the `Ambitus_engraver` to the `Staff` context creates a single ambitus per staff, even in the case of staves with multiple voices.

```
\new Staff \with {
    \consists "Ambitus_engraver"
}
<<
\new Voice \relative c' {
    \voiceOne
    c4 a d e
    f1
}
\new Voice \relative c' {
    \voiceTwo
```

```

es4 f g as
b1
}
>>

```



Ambitus

Ambitus indicate pitch ranges for voices.

Accidentals only show up if they are not part of the key signature. `AmbitusNoteHead` grobs also have ledger lines.

```

\layout {
  \context {
    \Voice
    \consists "Ambitus_engraver"
  }
}

<<
  \new Staff {
    \relative c' {
      \time 2/4
      c4 f'
    }
  }
  \new Staff {
    \relative c' {
      \time 2/4
      \key d \major
      cis4 as'
    }
  }
>>

```



Applying note head styles depending on the step of the scale

The `shapeNoteStyles` property can be used to define various note head styles for each step of the scale (as set by the key signature or the `tonic` property). This property requires a set of symbols, which can be purely arbitrary (geometrical expressions such as `triangle`, `cross`, and `xcircle` are allowed) or based on old American engraving tradition (some latin note names are also allowed).


That said, to imitate old American song books, there are several predefined note head styles available through shortcut commands such as `\aikenHeads` or `\sacredHarpHeads`.

This example shows different ways to obtain shape note heads, and demonstrates the ability to transpose a melody without losing the correspondence between harmonic functions and note head styles.

```
fragment = {
    \key c \major
    c2 d
    e2 f
    g2 a
    b2 c
}

\new Staff {
    \transpose c d
    \relative c' {
        \set shapeNoteStyles = ##(do re mi fa
                                #f la ti)
        \fragment
    }
    \break

    \relative c' {
        \set shapeNoteStyles = ##(cross triangle fa #f
                                mensural xcircle diamond)
        \fragment
    }
}
```



Automatically changing the stem direction of the middle note based on the melody

LilyPond can alter the stem direction of the middle note on a staff so that it follows the melody, by adding the `Melody_engraver` to the `Voice` context and overriding the `neutral-direction` of Stem.

```
\relative c'' {
    \time 3/4
    \autoBeamOff
    a8 b g f b g |
    c b d c b c
}
```

```
\layout {
  \context {
    \Voice
    \consists "Melody_engraver"
    \override Stem.neutral-direction = #'()
  }
}
```



Changing the ambitus gap

It is possible to change the default gap between the ambitus noteheads and the line joining them.

```
\layout {
  \context {
    \Voice
    \consists "Ambitus_engraver"
  }
}

\new Staff {
  \time 2/4
  % Default setting
  c'4 g''
}

\new Staff {
  \time 2/4
  \override AmbitusLine.gap = #0
  c'4 g''
}

\new Staff {
  \time 2/4
  \override AmbitusLine.gap = #1
  c'4 g''
}

\new Staff {
  \time 2/4
  \override AmbitusLine.gap = #1.5
  c'4 g''
}
```





Changing the interval of lines on the stave

`staffLineLayoutFunction` is used to change the position of notes. This snippet shows setting its value to `#ly:pitch-semitones` in order to produce a chromatic scale with the distance between each space and line of the stave equal to one semitone.

```
scale = \relative c' {
    a4 ais b c
    cis4 d dis e
    f4 fis g gis
    a1
}

\new Staff \with {
    \remove "Accidental_engraver"
    staffLineLayoutFunction = #ly:pitch-semitones
}
{
    <<
        \scale
        \context NoteNames {
            \set printOctaveNames = ##f
            \scale
        }
    >>
}
```



Clefs can be transposed by arbitrary amounts

Clefs can be transposed by arbitrary amounts, not just by octaves.

```
\relative c' {
    \clef treble
    c4 c c c
    \clef "treble_8"
    c4 c c c
    \clef "treble_5"
    c4 c c c
```

```
\clef "treble^3"
c4 c c c
}
```



Coloring notes depending on their pitch

It is possible to color note heads depending on their pitch and/or their names: the function used in this example even makes it possible to distinguish enharmonics.

```
%Association list of pitches to colors.
```

```
#(define color-mapping
  (list
    (cons (ly:make-pitch 0 0 NATURAL) (x11-color 'red))
    (cons (ly:make-pitch 0 0 SHARP) (x11-color 'green))
    (cons (ly:make-pitch 0 1 FLAT) (x11-color 'green))
    (cons (ly:make-pitch 0 2 NATURAL) (x11-color 'red))
    (cons (ly:make-pitch 0 2 SHARP) (x11-color 'green))
    (cons (ly:make-pitch 0 3 FLAT) (x11-color 'red))
    (cons (ly:make-pitch 0 3 NATURAL) (x11-color 'green))
    (cons (ly:make-pitch 0 4 SHARP) (x11-color 'red))
    (cons (ly:make-pitch 0 5 NATURAL) (x11-color 'green))
    (cons (ly:make-pitch 0 5 FLAT) (x11-color 'red))
    (cons (ly:make-pitch 0 6 SHARP) (x11-color 'red))
    (cons (ly:make-pitch 0 1 NATURAL) (x11-color 'blue))
    (cons (ly:make-pitch 0 3 SHARP) (x11-color 'blue))
    (cons (ly:make-pitch 0 4 FLAT) (x11-color 'blue))
    (cons (ly:make-pitch 0 5 SHARP) (x11-color 'blue))
    (cons (ly:make-pitch 0 6 FLAT) (x11-color 'blue))))
```

```
%Compare pitch and alteration (not octave).
```


```
#(define (pitch>equals? p1 p2)
  (and
    (= (ly:pitch-alteration p1) (ly:pitch-alteration p2))
    (= (ly:pitch-notename p1) (ly:pitch-notename p2))))
```

```
#(define (pitch-to-color pitch)
  (let ((color (assoc pitch color-mapping pitch>equals?)))
    (if color
        (cdr color))))
```

```
#(define (color-notehead grob)
  (pitch-to-color
    (ly:event-property (event-cause grob) 'pitch)))
```

```
\score {
  \new Staff \relative c' {
    \override NoteHead.color = #color-notehead
    c8 b d dis ees f g aes
  }
}
```

}



Creating a sequence of notes on various pitches

In music that contains many occurrences of the same sequence of notes at different pitches, the following music function may prove useful. It takes a note, of which only the pitch is used. This example creates the rhythm used throughout Mars, from Gustav Holst's The Planets.

```
rhythm =
#(define-music-function (parser location p) (ly:pitch?)
  "Make the rhythm in Mars (the Planets) at the given pitch"
  #{ \tuplet 3/2 { $p 8 $p $p } $p 4 $p $p 8 $p $p 4 #})

\new Staff {
  \time 5/4
  \rhythm c'
  \rhythm c''
  \rhythm g
}
```



Forcing a clef symbol to be displayed

When a clef sign has already been displayed and it has not been changed to a different clef, then repeating the \clef command will be ignored by LilyPond, since it is not a change of clef. It is possible to force the clef to be redisplayed using the command \set Staff.forceClef = ##t.

```
\relative c' {
  \clef treble
  c1
  \clef treble
  c1
  \set Staff.forceClef = ##t
  c1
  \clef treble
  c1
}
```



Generating random notes

This Scheme-based snippet generates 24 random notes (or as many as required), based on the current time (or any randomish number specified instead, in order to obtain the same random notes each time): i.e., to get different random note patterns, just change this number.



```
\score {
{
  $(let ((random-state (seed->random-state (current-time))))
    (make-sequential-music
      (map (lambda (x)
        (let ((idx (random 12 random-state)))
          (make-event-chord
            (list
              (make-music 'NoteEvent
                'duration (ly:make-duration 2 0 1/1)
                'pitch (ly:make-pitch
                  (quotient idx 7)
                  (remainder idx 7)
                  0))))))
        (make-list 24)))))
}
}
```



Hiding accidentals on tied notes at the start of a new system

This shows how to hide accidentals on tied notes at the start of a new system.

```
\relative c' {
  \override Accidental.hide-tied-accidental-after-break = ##t
  cis1~ cis~
  \break
  cis
}
```



Keep change clefs full sized

When a clef is changed, the clef sign displayed is smaller than the initial clef. This can be overridden with `full-size-change`.

```
\relative c' {
  \clef "treble"
  c1
```

```
\clef "bass"
c1
\clef "treble"
c1
\override Staff.Clef.full-size-change = ##t
\clef "bass"
c1
\clef "treble"
c1
\revert Staff.Clef.full-size-change
\clef "bass"
c1
\clef "treble"
c1
}
}
```



Makam example

Makam is a type of melody from Turkey using 1/9th-tone microtonal alterations. Consult the initialization file ‘ly/makam.ly’ for details of pitch names and alterations.

```
% Initialize makam settings
\include "makam.ly"

\relative c' {
  \set Staff.keySignature = #`((6 . ,(- KOMA)) (3 . ,BAKIYE))
  c4 cc db fk
  gbm4 gfc gfb efk
  fk4 db cc c
}
```



Non-traditional key signatures

The commonly used `\key` command sets the `keySignature` property, in the `Staff` context.

To create non-standard key signatures, set this property directly. The format of this command is a list:

```
\set Staff.keySignature = #`((octave . step) . alter) ((octave . step) . alter)
...
where, for each element in the list, octave specifies the octave (0 being the octave from middle C to the B above), step specifies the note within the octave (0 means C and 6 means B), and alter is ,SHARP ,FLAT ,DOUBLE-SHARP etc. (Note the leading comma.) The accidentals in the key signature will appear in the reverse order to that in which they are specified.
```

Alternatively, for each item in the list, using the more concise format `(step . alter)` specifies that the same alteration should hold in all octaves.

For microtonal scales where a “sharp” is not 100 cents, `alter` refers to the alteration as a proportion of a 200-cent whole tone.

Here is an example of a possible key signature for generating a whole-tone scale:

```
\relative c' {
  \set Staff.keySignature = #`(((0 . 6) . ,FLAT)
                           ((0 . 5) . ,FLAT)
                           ((0 . 3) . ,SHARP))

  c4 d e fis
  aes4 bes c2
}
```



Numbers as easy note heads

Easy notation note heads use the `note-names` property of the `NoteHead` object to determine what appears inside the note head. By overriding this property, it is possible to print numbers representing the scale-degree.

A simple engraver can be created to do this for every note head object it sees.

```
#(define Ez_numbers_engraver
  (make-engraver
    (acknowledgers
      ((note-head-interface engraver grob source-engraver)
       (let* ((context (ly:translator-context engraver))
              (tonic-pitch (ly:context-property context 'tonic))
              (tonic-name (ly:pitch-notename tonic-pitch))
              (grob-pitch
                (ly:event-property (event-cause grob) 'pitch))
              (grob-name (ly:pitch-notename grob-pitch))
              (delta (modulo (- grob-name tonic-name) 7)))
              (note-names
                (make-vector 7 (number->string (1+ delta))))))
         (ly:grob-set-property! grob 'note-names note-names)))))




#(set-global-staff-size 26)

\layout {
  ragged-right = ##t
  \context {
    \Voice
    \consists \Ez_numbers_engraver
  }
}

\relative c' {
  \easyHeadsOn
  c4 d e f
  g4 a b c \break
```

```
\key a \major
a,4 b cis d
e4 fis gis a \break

\key d \dorian
d,4 e f g
a4 b c d
}
```



Orchestra choir and piano template

This template demonstrates the use of nested `StaffGroup` and `GrandStaff` contexts to subgroup instruments of the same type together, and a way to use `\transpose` so that variables hold music for transposing instruments at concert pitch.

```
#(set-global-staff-size 17)
\paper {
    indent = 3.0\cm % space for instrumentName
    short-indent = 1.5\cm % space for shortInstrumentName
}

fluteMusic = \relative c' { \key g \major g'1 b }
% Pitches as written on a manuscript for Clarinet in A
% are transposed to concert pitch.
clarinetMusic = \transpose c' a
\relative c'' { \key bes \major bes1 d }
trumpetMusic = \relative c { \key g \major g''1 b }
% Key signature is often omitted for horns
hornMusic = \transpose c' f
\relative c { d'1 fis }
percussionMusic = \relative c { \key g \major g1 b }
sopranoMusic = \relative c'' { \key g \major g'1 b }
sopranoLyrics = \lyricmode { Lyr -- ics }
altoIMusic = \relative c' { \key g \major g'1 b }
altoIIMusic = \relative c' { \key g \major g'1 b }
altoILyrics = \sopranoLyrics
altoIIILyrics = \lyricmode { Ah -- ah }
```

```

tenorMusic = \relative c' { \clef "treble_8" \key g \major g1 b }
tenorLyrics = \sopranoLyrics
pianoRHMusic = \relative c { \key g \major g''1 b }
pianoLHMusic = \relative c { \clef bass \key g \major g1 b }
violinIMusic = \relative c' { \key g \major g'1 b }
violinIIMusic = \relative c' { \key g \major g'1 b }
violaMusic = \relative c { \clef alto \key g \major g'1 b }
celloMusic = \relative c { \clef bass \key g \major g1 b }
bassMusic = \relative c { \clef "bass_8" \key g \major g,1 b }

\score {
<<
  \new StaffGroup = "StaffGroup_woodwinds" <<
    \new Staff = "Staff_flute" {
      \set Staff.instrumentName = #"Flute"
      % shortInstrumentName, midiInstrument, etc.
      % may be set here as well
      \fluteMusic
    }
    \new Staff = "Staff_clarinet" {
      \set Staff.instrumentName =
      \markup { \concat { "Clarinet in B" \flat } }
      % Declare that written Middle C in the music
      % to follow sounds a concert B flat, for
      % output using sounded pitches such as MIDI.
      \transposition bes
      % Print music for a B-flat clarinet
      \transpose bes c' \clarinetMusic
    }
  >>
  \new StaffGroup = "StaffGroup_brass" <<
    \new Staff = "Staff_hornI" {
      \set Staff.instrumentName = #"Horn in F"
      \transposition f
      \transpose f c' \hornMusic
    }
    \new Staff = "Staff_trumpet" {
      \set Staff.instrumentName = #"Trumpet in C"
      \trumpetMusic
    }
  >>
  \new RhythmicStaff = "RhythmicStaff_percussion" <<
    \set RhythmicStaff.instrumentName = #"Percussion"
    \percussionMusic
  >>
  \new PianoStaff <<
    \set PianoStaff.instrumentName = #"Piano"
    \new Staff { \pianoRHMusic }
    \new Staff { \pianoLHMusic }
  >>
  \new ChoirStaff = "ChoirStaff_choir" <<
    \new Staff = "Staff_soprano" {

```

```
\set Staff.instrumentName = #"Soprano"
\new Voice = "soprano"
\sopranoMusic
}
\new Lyrics \lyricsto "soprano" { \sopranoLyrics }
\new GrandStaff = "GrandStaff_altos"
\with { \accepts Lyrics } <<
  \new Staff = "Staff_altoI"  {
    \set Staff.instrumentName = #"Alto I"
    \new Voice = "altoI"
    \altoIMusic
  }
  \new Lyrics \lyricsto "altoI" { \altoILyrics }
  \new Staff = "Staff_altoII" {
    \set Staff.instrumentName = #"Alto II"
    \new Voice = "altoII"
    \altoIIMusic
  }
  \new Lyrics \lyricsto "altoII" { \altoIIILyrics }
>>
\new Staff = "Staff_tenor" {
  \set Staff.instrumentName = #"Tenor"
  \new Voice = "tenor"
  \tenorMusic
}
\new Lyrics \lyricsto "tenor" { \tenorLyrics }
>>
\new StaffGroup = "StaffGroup_strings" <<
  \new GrandStaff = "GrandStaff_violins" <<
    \new Staff = "Staff_violinI" {
      \set Staff.instrumentName = #"Violin I"
      \violinIMusic
    }
    \new Staff = "Staff_violinII" {
      \set Staff.instrumentName = #"Violin II"
      \violinIIMusic
    }
  >>
  \new Staff = "Staff_viola" {
    \set Staff.instrumentName = #"Viola"
    \violaMusic
  }
  \new Staff = "Staff_cello" {
    \set Staff.instrumentName = #"Cello"
    \celloMusic
  }
  \new Staff = "Staff_bass" {
    \set Staff.instrumentName = #"Double Bass"
    \bassMusic
  }
>>
>>
```

```
\layout { }
```

Flute

Clarinet in B_b

Horn in F

Trumpet in C

Percussion

Piano

Soprano

Alto I

Alto II

Tenor

Violin I

Violin II

Viola

Cello

Double Bass 8

Ottava text

Internally, `\ottava` sets the properties `ottavation` (for example, to `8va` or `8vb`) and `middleCPosition`. To override the text of the bracket, set `ottavation` after invoking `\ottava`.

```
{
  \ottava #1
  \set Staff.ottavation = #"8"
  c''1
  \ottava #0
  c'1
  \ottava #1
  \set Staff.ottavation = #"Text"
  c''1
}
```

Preventing extra naturals from being automatically added

In accordance with traditional typesetting rules, a natural sign is printed before a sharp or flat if a previous double sharp or flat on the same note is canceled. To change this behavior to contemporary practice, set the `extraNatural` property to `f` in the `Staff` context.

```
\relative c' {
  aeses4 aes ais a
  \set Staff.extraNatural = ##f
  aeses4 aes ais a
}
```

Preventing natural signs from being printed when the key signature changes

When the key signature changes, natural signs are automatically printed to cancel any accidentals from previous key signatures. This may be prevented by setting to `f` the `printKeyCancellation` property in the `Staff` context.

```
\relative c' {
  \key d \major
  a4 b cis d
  \key g \minor
  a4 bes c d
  \set Staff.printKeyCancellation = ##f
  \key d \major
  a4 b cis d
  \key g \minor
  a4 bes c d
}
```

Quoting another voice with transposition

Quotations take into account the transposition of both source and target. In this example, all instruments play sounding middle C; the target is an instrument in F. The target part may be transposed using `\transpose`. In this case, the quoted pitches will stay unchanged.

```
\addQuote clarinet {
  \transposition bes
  \repeat unfold 8 { d'16 d' d'8 }
}

\addQuote sax {
  \transposition es'
  \repeat unfold 16 { a8 }
```

```

}

quoteTest = {
    % french horn
    \transposition f
    g'4
    << \quoteDuring #"clarinet" { \skip 4 } s4^"clar." >>
    << \quoteDuring #"sax" { \skip 4 } s4^"sax." >>
    g'4
}

{
    \set Staff.instrumentName =
        \markup {
            \center-column { Horn \line { in F } }
        }
    \quoteTest
    \transpose c' d' << \quoteTest s4_ "up a tone" >>
}

```



Separating key cancellations from key signature changes

By default, the accidentals used for key cancellations are placed adjacent to those for key signature changes. This behavior can be changed by overriding the `'break-align-orders` property of the `BreakAlignment` grob.

The value of `'break-align-orders` is a vector of length 3, with quoted lists of breakable items as elements. This example only modifies the second list, moving `key-cancellation` before `staff-bar`; by modifying the second list, break alignment behavior only changes in the middle of a system, not at the beginning or the end.

```

\new Staff {
    \override Score.BreakAlignment.break-align-orders =
        #((left-edge ambitus breathing-sign clef staff-bar
            key-cancellation key-signature time-signature custos)

        (left-edge ambitus breathing-sign clef key-cancellation
            staff-bar key-signature time-signature custos)

        (left-edge ambitus breathing-sign clef key-cancellation
            key-signature staff-bar time-signature custos))

    \key des \major
    c'1
    \bar "|"
    \key bes \major
    c'1
}

```



Transposing pitches with minimum accidentals ("Smart" transpose)

This example uses some Scheme code to enforce enharmonic modifications for notes in order to have the minimum number of accidentals. In this case, the following rules apply:

Double accidentals should be removed

B sharp -> C

E sharp -> F

C flat -> B

F flat -> E

In this manner, the most natural enharmonic notes are chosen.

```
#(define (naturalize-pitch p)
  (let ((o (ly:pitch-octave p))
        (a (* 4 (ly:pitch-alteration p))))
    ;; alteration, a, in quarter tone steps,
    ;; for historical reasons
    (n (ly:pitch-notename p)))
  (cond
    ((and (> a 1) (or (eq? n 6) (eq? n 2)))
     (set! a (- a 2))
     (set! n (+ n 1)))
    ((and (< a -1) (or (eq? n 0) (eq? n 3)))
     (set! a (+ a 2))
     (set! n (- n 1))))
    (cond
      ((> a 2) (set! a (- a 4)) (set! n (+ n 1)))
      ((< a -2) (set! a (+ a 4)) (set! n (- n 1))))
      (if (< n 0) (begin (set! o (- o 1)) (set! n (+ n 7))))
          (if (> n 6) (begin (set! o (+ o 1)) (set! n (- n 7))))
              (ly:make-pitch o n (/ a 4)))))

#(define (naturalize music)
  (let ((es (ly:music-property music 'elements))
        (e (ly:music-property music 'element))
        (p (ly:music-property music 'pitch)))
    (if (pair? es)
        (ly:music-set-property!
         music 'elements
         (map (lambda (x) (naturalize x)) es)))
    (if (ly:music? e)
        (ly:music-set-property!
         music 'element
         (naturalize e)))
    (if (ly:pitch? p)
        (begin
          (set! p (naturalize-pitch p))
          (ly:music-set-property! music 'pitch p)))
    music))
```

```

naturalizeMusic =
#(define-music-function (parser location m)
  (ly:music?)
  (naturalize m))

music = \relative c' { c4 d e g }

\score {
  \new Staff {
    \transpose c ais { \music }
    \naturalizeMusic \transpose c ais { \music }
    \transpose c deses { \music }
    \naturalizeMusic \transpose c deses { \music }
  }
  \layout { }
}

```



Tweaking clef properties

The command `\clef "treble_8"` is equivalent to setting `clefGlyph`, `clefPosition` (which controls the vertical position of the clef), `middleCPosition` and `clefTransposition`. A clef is printed when any of the properties except `middleCPosition` are changed.

Note that changing the glyph, the position of the clef, or the octavation does not in itself change the position of subsequent notes on the staff: the position of middle C must also be specified to do this. In order to get key signatures on the correct staff lines, `middleCClefPosition` must also be set. The positional parameters are relative to the staff center line, positive numbers displacing upwards, counting one for each line and space. The `clefTransposition` value would normally be set to 7, -7, 15 or -15, but other values are valid.

When a clef change takes place at a line break the new clef symbol is printed at both the end of the previous line and the beginning of the new line by default. If the warning clef at the end of the previous line is not required it can be suppressed by setting the `Staff` property `explicitClefVisibility` to the value `end-of-line-invisible`. The default behavior can be recovered with `\unset Staff.explicitClefVisibility`.

The following examples show the possibilities when setting these properties manually. On the first line, the manual changes preserve the standard relative positioning of clefs and notes, whereas on the second line, they do not.

```

\layout { ragged-right = ##t }
{
  % The default treble clef
  \key f \major
  c'1
  % The standard bass clef
  \set Staff.clefGlyph = #"clefs.F"
  \set Staff.clefPosition = #2
  \set Staff.middleCPosition = #6
  \set Staff.middleCClefPosition = #6
  \key g \major

```

```

c'1
% The baritone clef
\set Staff.clefGlyph = #"clefs.C"
\set Staff.clefPosition = #4
\set Staff.middleCPosition = #4
\set Staff.middleCClefPosition = #4
\key f \major
c'1
% The standard choral tenor clef
\set Staff.clefGlyph = #"clefs.G"
\set Staff.clefPosition = #-2
\set Staff.clefTransposition = #-7
\set Staff.middleCPosition = #1
\set Staff.middleCClefPosition = #1
\key f \major
c'1
% A non-standard clef
\set Staff.clefPosition = #0
\set Staff.clefTransposition = #0
\set Staff.middleCPosition = #-4
\set Staff.middleCClefPosition = #-4
\key g \major
c'1 \break

% The following clef changes do not preserve
% the normal relationship between notes, key signatures
% and clefs:

\set Staff.clefGlyph = #"clefs.F"
\set Staff.clefPosition = #2
c'1
\set Staff.clefGlyph = #"clefs.G"
c'1
\set Staff.clefGlyph = #"clefs.C"
c'1
\set Staff.clefTransposition = #7
c'1
\set Staff.clefTransposition = #0
\set Staff.clefPosition = #0
c'1

% Return to the normal clef:

\set Staff.middleCPosition = #0
c'1
}

```





Using autochange with more than one voice

Using autochange with more than one voice.

```
\score
{
    \new PianoStaff
    <<
        \new Staff = "up" {
            <<
                \set Timing.beamExceptions = #'()
                \set Timing.beatStructure = #'(4)
                \new Voice {
                    \voiceOne
                    \autochange
                    \relative c' {
                        g8 a b c d e f g
                        g,,8 a b c d e f g
                    }
                }

                \new Voice {
                    \voiceTwo
                    \autochange
                    \relative c' {
                        g8 a b c d e f g
                        g,,8 a b c d e f g
                    }
                }
            >>
        }
    >>
}

\new Staff = "down" {
    \clef bass
}
>>
```

Rhythms

Section “Rhythms” in *Notation Reference*

Adding beams slurs ties etc. when using tuplet and non-tuplet rhythms

LilyPond syntax can involve many unusual placements for parentheses, brackets etc., which might sometimes have to be interleaved. For example, when entering a manual beam, the left square bracket has to be placed after the starting note and its duration, not before. Similarly, the right square bracket should directly follow the note which is to be at the end of the requested beaming, even if this note happens to be inside a tuplet section. This snippet demonstrates how to combine manual beaming, manual slurs, ties and phrasing slurs with tuplet sections (enclosed within curly braces).

```
{
  r16[ g16 \tuplet 3/2 { r16 e'8} ]
  g16( a \tuplet 3/2 { b d e') }
  g8[( a \tuplet 3/2 { b d') e'] ~ }
  \time 2/4
  \tuplet 5/4 { e'32\(( a b d' e' } a'4.\)
}
```



Adding drum parts

Using the powerful pre-configured tools such as the `\drummode` function and the `DrumStaff` context, inputting drum parts is quite easy: drums are placed at their own staff positions (with a special clef symbol) and have note heads according to the drum. Attaching an extra symbol to the drum or restricting the number of lines is possible.

```
drh = \drummode { cymc4.^"crash" hhc16^"h.h." hh hhc8 hho hhc8 hh16 hh hhc4 r4 r2 }
drl = \drummode { bd4 sn8 bd bd4 << bd ss >> bd8 tommh tommh bd toml toml bd tomfh16 tomfh
timb = \drummode { timh4 ssh timl8 ssh r timh r4 ssh8 timl r4 cb8 cb }
```

```
\score {
  <<
  \new DrumStaff \with {
    drumStyleTable = #timbales-style
    \override StaffSymbol.line-count = #2
    \override BarLine.bar-extent = #'(-1 . 1)
  } <<
  \set Staff.instrumentName = #"timbales"
  \timb
  >>
  \new DrumStaff <<
  \set Staff.instrumentName = #"drums"
  \new DrumVoice { \stemUp \drh }
  \new DrumVoice { \stemDown \drl }
  >>
```

```
>>
\layout { }
\midi {
    \tempo 4 = 120
}
}
```

timbales

drums

Adjusting grace note spacing

The space given to grace notes can be adjusted using the `spacing-increment` property of `Score.GraceSpacing`.

```
graceNotes = {
    \grace { c4 c8 c16 c32 }
    c8
}


\relative c' {
    c8
    \graceNotes
    \override Score.GraceSpacing.spacing-increment = #2.0
    \graceNotes
    \revert Score.GraceSpacing.spacing-increment
    \graceNotes
}
```

Aligning bar numbers

Bar numbers by default are right-aligned to their parent object. This is usually the left edge of a line or, if numbers are printed within a line, the left hand side of a bar line. The numbers may also be positioned directly over the bar line or left-aligned to the bar line.

```
\relative c' {
    \set Score.currentBarNumber = #111
    \override Score.BarNumber.break-visibility = #all-visible
    % Increase the size of the bar number by 2
    \override Score.BarNumber.font-size = #2
    % Print a bar number every second measure
    \set Score.barNumberVisibility = #(every-nth-bar-number-visible 2)
    c1 | c1
    % Center-align bar numbers
    \override Score.BarNumber.self-alignment-X = #CENTER
    c1 | c1
```

```
% Left-align bar numbers
\override Score.BarNumber.self-alignment-X = #LEFT
c1 | c1
}
```



Alternative breve notes

Breve notes are also available with two vertical lines on each side of the notehead instead of one line and in baroque style.

```
\relative c' {
  \time 4/2
  c\brevet |
  \override Staff.NoteHead.style = #'altdefault
  b\brevet
  \override Staff.NoteHead.style = #'baroque
  b\brevet
  \revert Staff.NoteHead.style
  a\brevet
}
```



Automatic beam subdivisions

Beams can be subdivided automatically. By setting the property `subdivideBeams`, beams are subdivided at beat positions (as specified in `baseMoment`).

```
\new Staff {
  \relative c' {
    <<
    {
      \voiceOne
      \set subdivideBeams = ##t
      b32[ a g f c' b a g
      b32^"subdivide beams" a g f c' b a g]
    }
    \new Voice {
      \voiceTwo
      b32_"default"[ a g f c' b a g
      b32 a g f c' b a g]
    }
  >>
  \oneVoice
  \set baseMoment = #(ly:make-moment 1/8)
  \set beatStructure = #'(2 2 2 2)
  b32^"baseMoment 1 8"[ a g f c' b a g]
  \set baseMoment = #(ly:make-moment 1/16)
```

```
\set beatStructure = #'(4 4 4 4)
b32^"baseMoment 1 16"[ a g f c' b a g]
}
}
```

Automatically change durations

`<code>shiftDurations</code>` can be used to change the note lengths of a piece of music. It takes two arguments - the scaling factor as a power of two, and the number of dots to be added as a positive integer.

```
\paper { indent = 0 }

music = \relative c' { a1 b2 c4 d8 r }

\score {
  \new Voice {
    \time 4/2
    \music
    \time 4/4
    \shiftDurations #1 #0 { \music }
    \time 2/4
    \shiftDurations #2 #0 { \music }
    \time 4/1
    \shiftDurations #-1 #0 { \music }
    \time 8/1
    \shiftDurations #-2 #0 { \music }
    \time 6/2
    \shiftDurations #0 #1 { \music }
    \time 7/2
    \shiftDurations #0 #2 { \music }
  }
}
```


Avoiding collisions with chord fingerings

Fingerings and string numbers applied to individual notes will automatically avoid beams and stems, but this is not true by default for fingerings and string numbers applied to the individual notes of chords. The following example shows how this default behavior can be overridden.

```
\relative c' {
    \set fingeringOrientations = #'(up)
    \set stringNumberOrientations = #'(up)
    \set strokeFingerOrientations = #'(up)

    % Default behavior
    r8
    <f c'-5>8
    <f c'\5>8
    <f c'-\rightHandFinger #2 >8

    % Corrected to avoid collisions
    r8
    \override Fingering.add-stem-support = ##t
    <f c'-5>8
    \override StringNumber.add-stem-support = ##t
    <f c'\5>8
    \override StrokeFinger.add-stem-support = ##t
    <f c'-\rightHandFinger #2 >8
}
```




Beam endings in Score context

Beam-ending rules specified in the `Score` context apply to all staves, but can be modified at both `Staff` and `Voice` levels:

```
\relative c'' {
    \time 5/4
    % Set default beaming for all staves
    \set Score.baseMoment = #(ly:make-moment 1/8)
    \set Score.beatStructure = #'(3 4 3)
    <<
        \new Staff {
            c8 c c c c c c c c
        }
        \new Staff {
            % Modify beaming for just this staff
            \set Staff.beatStructure = #'(6 4)
            c8 c c c c c c c c
        }
        \new Staff {
            % Inherit beaming from Score context
            <<
```

```
{
    \voiceOne
    c8 c c c c c c c c
}
% Modify beaming for this voice only
\new Voice {
    \voiceTwo
    \set Voice.beatStructure = #'(6 4)
    a8 a a a a a a a a
}
>>
}
>>
}
```



Beam grouping in 7/8 time

There are no default automatic beam groupings specified for 7/8 time, so if automatic beams are required the grouping must be specified using `<code>beatStructure</code>`. For example, to group all beams 2-3-2 in 7/8 time, specify beam endings at 2/8 and 5/8:

```
\relative c' {
    \time 7/8
    % rhythm 2-3-2
    a8 a a a a a a
    \set Score.beatStructure = #'(2 3 2)
    a8 a a a a a a
}
```



Beams across line breaks

Line breaks are normally forbidden when beams cross bar lines. This behavior can be changed as shown:

```
\relative c' {
    \override Beam.breakable = ##t
    c8 c[ c] c[ c] c[ c] c[ \break
    c8] c[ c] c[ c] c[ c] c
}
```

The first staff shows a continuous beam connecting five eighth notes. The second staff shows a beam with a break (knee) between the third and fourth notes.

Changing beam knee gap

Kneed beams are inserted automatically when a large gap is detected between the note heads. This behavior can be tuned through the `auto-knee-gap` property. A kneeed beam is drawn if the gap is larger than the value of `auto-knee-gap` plus the width of the beam object (which depends on the duration of the notes and the slope of the beam). By default `auto-knee-gap` is set to 5.5 staff spaces.

```
{
    f8 f''8 f8 f''8
    \override Beam.auto-knee-gap = #6
    f8 f''8 f8 f''8
}
```

A staff of musical notation showing a beam with a knee between the third and fourth notes, as specified in the code above.

Changing form of multi-measure rests

If there are ten or fewer measures of rests, a series of longa and breve rests (called in German “Kirchenpausen” - church rests) is printed within the staff; otherwise a simple line is shown. This default number of ten may be changed by overriding the `expand-limit` property.

```
\relative c' {
    \compressFullBarRests
    R1*2 | R1*5 | R1*9
    \override MultiMeasureRest.expand-limit = #3
    R1*2 | R1*5 | R1*9
}
```

A staff of musical notation showing multi-measure rests. The rests are labeled with numbers: 2, 5, 9, 2, 5, 9. The first two rests are longa (two vertical dashes), the next two are breve (one vertical dash), and the last two are longa again.

Changing the number of augmentation dots per note

The number of augmentation dots on a single note can be changed independently of the dots placed after the note.

```
\relative c' {
    c4.. a16 r2 |
    \override Dots.dot-count = #4
    c4.. a16 r2 |
    \override Dots.dot-count = #0
    c4.. a16 r2 |
    \revert Dots.dot-count
    c4.. a16 r2 |
```

```
}
```



Changing the tempo without a metronome mark

To change the tempo in MIDI output without printing anything, make the metronome mark invisible.

```
\score {
    \new Staff \relative c' {
        \tempo 4 = 160
        c4 e g b
        c4 b d c
        \set Score.tempoHideNote = ##t
        \tempo 4 = 96
        d,4 fis a cis
        d4 cis e d
    }
    \layout { }
    \midi { }
}
```



Changing the tuplet number

By default, only the numerator of the tuplet number is printed over the tuplet bracket. Alternatively, num:den of the tuplet number may be printed, or the tuplet number may be suppressed altogether.

```
\relative c'' {
    \tuplet 3/2 { c8 c c }
    \tuplet 3/2 { c8 c c }
    \override TupletNumber.text = #tuplet-number::calc-fraction-text
    \tuplet 3/2 { c8 c c }
    \omit TupletNumber
    \tuplet 3/2 { c8 c c }
}
```



Changing time signatures inside a polymetric section using \scaleDurations

```
\layout {
  \context {
    \Score
    \remove "Timing_translator"
    \remove "Default_bar_line_engraver"
  }
  \context {
    \Staff
    \consists "Timing_translator"
    \consists "Default_bar_line_engraver"
  }
}

<<
\new Staff {
  \scaleDurations 8/5 {
    \time 6/8
    \set Timing.measureLength = #(ly:make-moment 6/5)
    b8 b b b b b
    \time 2/4
    \set Timing.measureLength = #(ly:make-moment 4/5)
    b4 b
  }
}
\new Staff {
  \clef bass
  \time 2/4
  c2 d e f
}
>>
```



Chant or psalms notation

This form of notation is used for the chant of the Psalms, where verses aren't always the same length.

```
stemOff = \hide Staff.Stem
stemOn  = \undo \stemOff

\score {
  \new Staff \with { \remove "Time_signature_engraver" }
  {
    \key g \minor
    \cadenzaOn
```

```
\stemOff a'\breve bes'4 g'4
\stemOn a'2 \bar "||"
\stemOff a'\breve g'4 a'4
\stemOn f'2 \bar "||"
\stemOff a'\breve ^\markup { \italic flexe }
\stemOn g'2 \bar "||"
}
}
```



Compound time signatures

Odd 20th century time signatures (such as `"5/8"`) can often be played as compound time signatures (e.g. `"3/8 + 2/8"`), which combine two or more unequal metrics. LilyPond can make such music quite easy to read and play, by explicitly printing the compound time signatures and adapting the automatic beaming behavior.

```
\relative c' {
  \compoundMeter #'((2 8) (3 8))
  c8 d e fis gis
  c8 fis, gis e d
  c8 d e4 gis8
}
```



Conducting signs measure grouping signs


Beat grouping within a measure is controlled by the context property `beatStructure`. Values of `beatStructure` are established for many time signatures in ‘scm/time-signature-settings.scm’. Values of `beatStructure` can be changed or set with `\set`. Alternatively, `\time` can be used to both set the time signature and establish the beat structure. For this, you specify the internal grouping of beats in a measure as a list of numbers (in Scheme syntax) before the time signature.

`\time` applies to the `Timing` context, so it will not reset values of `beatStructure` or `baseMoment` that are set in other lower-level contexts, such as `Voice`.

If the `Measure_grouping_engraver` is included in one of the display contexts, measure grouping signs will be created. Such signs ease reading rhythmically complex modern music. In the example, the 9/8 measure is grouped in two different patterns using the two different methods, while the 5/8 measure is grouped according to the default setting in ‘scm/time-signature-settings.scm’:

```
\score {
  \new Voice \relative c' {
    \time 9/8
    g8 g d d g g a( bes g) |
    \set Timing.beatStructure = #'(2 2 2 3)
    g8 g d d g g a( bes g) |
  }
```

```
\time #'(4 5) 9/8
g8 g d d g g a( bes g) |
\time 5/8
a4. g4 |
}
\layout {
  \context {
    \Staff
    \consists "Measure_grouping_engraver"
  }
}
}
```



Consistently left aligned bar numbers

When left aligning bar numbers, overlapping problems may occur with Staves brackets. The snippet solves this by keeping right aligned the first bar number following line breaks.

```
consistentlyLeftAlignedBarNumbers = {
  \override Score.BarNumber.break-visibility = #end-of-line-invisible
  \override Score.BarNumber.self-alignment-X =
    #(lambda (grob)
      (let ((break-dir (ly:item-break-dir grob)))
        (if (= break-dir RIGHT) RIGHT LEFT)))
}

\new ChoirStaff <-
  \new Staff {
    \relative c' {
      \set Score.barNumberVisibility = #(every-nth-bar-number-visible 3)
      \bar ""
      \consistentlyLeftAlignedBarNumbers

      \set Score.currentBarNumber = #112
      \repeat unfold 8 { R1 }
      \break
      \repeat unfold 9 { R1 }
      \break
      \repeat unfold 7 { R1 }
    }
  }
  \new Staff {
    \relative c' {
      \repeat unfold 24 { R1 }
    }
  }
>>
```

```
\layout {
  indent = #0
  ragged-right = ##t
  ragged-last = ##t
}
```

The image shows three staves of musical notation. The top staff has two measures, both starting with a 'c' and ending with a fermata. Measure 114 consists of a triplet of eighth notes (beamless). Measure 117 consists of a sextuplet of sixteenth notes (beamed in groups of three). The middle staff has two measures, both starting with a 'c'. Measure 120 consists of a triplet of eighth notes (beamless). Measure 123 consists of a septuplet of sixteenth notes (beamed in groups of three). The bottom staff has three measures, all starting with a 'c'. Measure 129 consists of a triplet of eighth notes (beamless). Measure 132 consists of a septuplet of sixteenth notes (beamed in groups of three). Measure 135 consists of a triplet of eighth notes (beamless).

Controlling tuplet bracket visibility

The default behavior of tuplet-bracket visibility is to print a bracket unless there is a beam of the same length as the tuplet. To control the visibility of tuplet brackets, set the property 'bracket-visibility' to either `#t` (always print a bracket), `#f` (never print a bracket) or `#'if-no-beam` (only print a bracket if there is no beam).

```
music = \relative c' {
  \tuplet 3/2 { c16[ d e } f8]
  \tuplet 3/2 { c8 d e }
  \tuplet 3/2 { c4 d e }
}

\new Voice {
  \relative c' {
    << \music s4^"default" >>
    \override TupletBracket.bracket-visibility = #'if-no-beam
    << \music s4^"'if-no-beam" >>
    \override TupletBracket.bracket-visibility = ##t
    << \music s4^"#t" >>
    \override TupletBracket.bracket-visibility = ##f
    << \music s4^"#f" >>
  }
}
```

The top staff is in common time (C) and the bottom staff is in 3/4 time (3). Both staves have a treble clef (G) and a key signature of one sharp (F#).

Creating metronome marks in markup mode

New metronome marks can be created in markup mode, but they will not change the tempo in MIDI output.

```
\relative c' {
  \tempo \markup {
    \concat {
      (
      \smaller \general-align #Y #DOWN \note #"16." #1
      " = "
      \smaller \general-align #Y #DOWN \note #"8" #1
    )
  }
}
c1
c4 c' c,2
}
```

Engraving ties manually

Ties may be engraved manually by changing the `tie-configuration` property of the `TieColumn` object. The first number indicates the distance from the center of the staff in half staff-spaces, and the second number indicates the direction (1 = up, -1 = down).

```
\relative c' {
  <c e g>2~ <c e g>
  \override TieColumn.tie-configuration =
    #'((0.0 . 1) (-2.0 . 1) (-4.0 . 1))
  <c e g>2~ <c e g>
}
```

Engraving tremolos with floating beams

If a tremolo's total duration is less than a quarter-note, or exactly a half-note, or between a half-note and a whole-note, it is normally typeset with all beams touching the stems. Certain engraving styles typeset some of these beams as centered floating beams that do not touch the stems. The number of floating beams in this type of tremolo is controlled with the '`gap-count`

property of the `Beam` object, and the size of the gaps between beams and stems is set with the `'gap` property.

```
\relative c' {
    \repeat tremolo 8 { a32 f }
    \override Beam.gap-count = #1
    \repeat tremolo 8 { a32 f }
    \override Beam.gap-count = #2
    \repeat tremolo 8 { a32 f }
    \override Beam.gap-count = #3
    \repeat tremolo 8 { a32 f }

    \override Beam.gap-count = #3
    \override Beam.gap = #1.33
    \repeat tremolo 8 { a32 f }
    \override Beam.gap = #1
    \repeat tremolo 8 { a32 f }
    \override Beam.gap = #0.67
    \repeat tremolo 8 { a32 f }
    \override Beam.gap = #0.33
    \repeat tremolo 8 { a32 f }
}
```



Entering several tuplets using only one `\tuplet` command

The property `tupletSpannerDuration` sets how long each of the tuplets contained within the brackets after `\tuplet` should last. Many consecutive tuplets can then be placed within a single `\tuplet` expression, thus saving typing.

There are several ways to set `tupletSpannerDuration`. The command `\tupletSpan` sets it to a given duration, and clears it when instead of a duration `\default` is specified. Another way is to use an optional argument with `\tuplet`.

```
\relative c' {
    \time 2/4
    \tupletSpan 4
    \tuplet 3/2 { c8^"\tupletSpan 4" c c c c c }
    \tupletSpan \default
    \tuplet 3/2 { c8^"\tupletSpan \default" c c c c c }
    \tuplet 3/2 4 { c8^"\tuplet 3/2 4 {...}" c c c c c }
}
```

Flat flags and beam nibs

Flat flags on lone notes and beam nibs at the ends of beamed figures are both possible with a combination of `stemLeftBeamCount`, `stemRightBeamCount` and paired [] beam indicators.

For right-pointing flat flags on lone notes, use paired [] beam indicators and set `stemLeftBeamCount` to zero (see Example 1).


For left-pointing flat flags, set `stemRightBeamCount` instead (Example 2).

For right-pointing nibs at the end of a run of beamed notes, set `stemRightBeamCount` to a positive value. And for left-pointing nibs at the start of a run of beamed notes, set `stemLeftBeamCount` instead (Example 3).

Sometimes it may make sense for a lone note surrounded by rests to carry both a left- and right-pointing flat flag. Do this with paired [] beam indicators alone (Example 4).

(Note that `\set stemLeftBeamCount` is always equivalent to `\once \set`. In other words, the beam count settings are not “sticky”, so the pair of flat flags attached to the lone `c'16[]` in the last example have nothing to do with the `\set` two notes prior.)



```
\score {
  <<
  % Example 1
  \new RhythmicStaff {
    \set stemLeftBeamCount = #0
    c16[]
    r8.
  }
  % Example 2
  \new RhythmicStaff {
    r8.
    \set stemRightBeamCount = #0
    c16[]
  }
  % Example 3
  \new RhythmicStaff {
    c16 c
    \set stemRightBeamCount = #2
    c16 r r
    \set stemLeftBeamCount = #2
    c16 c c
  }
  % Example 4
  \new RhythmicStaff {
    c16 c
    \set stemRightBeamCount = #2
    c16 r
    c16[]
    r16
    \set stemLeftBeamCount = #2
    c16 c
  }
>>
}
```



Forcing rehearsal marks to start from a given letter or number

This snippet demonstrates how to obtain automatic ordered rehearsal marks, but from the letter or number desired.

```
\relative c' {
    c1 \mark \default
    c1 \mark \default
    c1 \mark \default
    c1 \mark #14
    c1 \mark \default
    c1 \mark \default
    c1 \mark \default
    c1 \mark \default
    \break
    \set Score.markFormatter = #format-mark-numbers
    c1 \mark #1
    c1 \mark \default
    c1 \mark \default
    c1 \mark \default
    c1 \mark #14
    c1 \mark \default
    c1 \mark \default
    c1 \mark \default
    c1 \mark \default
}
```



Generating custom flags

The `stencil` property of the Flag grob can be set to a custom scheme function to generate the glyph for the flag.

```
#(define-public (weight-flag grob)
```

```

(let* ((stem-grob (ly:grob-parent grob X))
      (log (- (ly:grob-property stem-grob 'duration-log) 2)))
      (is-up? (eqv? (ly:grob-property stem-grob 'direction) UP))
      (yext (if is-up? (cons (* log -0.8) 0) (cons 0 (* log 0.8))))
      (flag-stencil (make-filled-box-stencil '(-0.4 . 0.4) yext))
      (stroke-style (ly:grob-property grob 'stroke-style))
      (stroke-stencil (if (equal? stroke-style "grace")
                           (make-line-stencil 0.2 -0.9 -0.4 0.9 -0.4)
                           empty-stencil)))
  (ly:stencil-add flag-stencil stroke-stencil)))

% Create a flag stencil by looking up the glyph from the font
(define (inverted-flag grob)
  (let* ((stem-grob (ly:grob-parent grob X))
         (dir (if (eqv? (ly:grob-property stem-grob 'direction) UP) "d" "u"))
         (flag (retrieve-glyph-flag "" dir "" grob))
         (line-thickness (ly:staff-symbol-line-thickness grob))
         (stem-thickness (ly:grob-property stem-grob 'thickness))
         (stem-width (* line-thickness stem-thickness))
         (stroke-style (ly:grob-property grob 'stroke-style))
         (stencil (if (null? stroke-style)
                      flag
                      (add-stroke-glyph flag stem-grob dir stroke-style "")))
         (rotated-flag (ly:stencil-rotate-absolute stencil 180 0 0)))
    (ly:stencil-translate rotated-flag (cons (- (/ stem-width 2)) 0)))))

snippetexamplenotes = { \autoBeamOff c'8 d'16 c'32 d'64 \acciaccatura {c'8} d'64 }■

{
\override Score.RehearsalMark.self-alignment-X = #LEFT
\time 1/4
\mark "Normal flags"
\snippetexamplenotes

\mark "Custom flag: inverted"
\override Flag.stencil = #inverted-flag
\snippetexamplenotes

\mark "Custom flag: weight"
\override Flag.stencil = #weight-flag
\snippetexamplenotes

\mark "Revert to normal"
\revert Flag.stencil
\snippetexamplenotes
}

```



Guitar strum rhythms

For guitar music, it is possible to show strum rhythms, along with melody notes, chord names and fret diagrams.

```
\include "predefined-guitar-fretboards.ly"
<<
\new ChordNames {
  \chordmode {
    c1 | f | g | c
  }
}
\new FretBoards {
  \chordmode {
    c1 | f | g | c
  }
}
\new Voice \with {
  \consists "Pitch_squash_engraver"
} {
  \relative c' {
    \improvisationOn
    c4 c8 c c4 c8 c
    f4 f8 f f4 f8 f
    g4 g8 g g4 g8 g
    c4 c8 c c4 c8 c
  }
}
\new Voice = "melody" {
  \relative c' {
    c2 e4 e4
    f2. r4
    g2. a4
    e4 c2.
  }
}
\new Lyrics {
  \lyricsto "melody" {
    This is my song.
    I like to sing.
  }
}
>>
```


The diagram shows four guitar chord diagrams labeled C, F, G, and C. Below each chord is its corresponding tablature. Above the chords are four measures of music for a soprano voice. The first measure consists of eighth-note chords: C (x, o, o), F (134211), G (21 ooo), and C (x, o, o). The second measure also consists of eighth-note chords: C (32 1), F (134211), G (21 3), and C (x, o, o). The lyrics "This is my song." and "I like to sing." are written below the staff.

Heavily customized polymetric time signatures

Though the polymetric time signature shown was not the most essential item here, it has been included to show the beat of this piece (which is the template of a real Balkan song!).

```
melody = \relative c' {
    \set Staff.instrumentName = #"Bb Sop."
    \key g \major
    \compoundMeter #'((3 8) (2 8) (2 8) (3 8) (2 8) (2 8)
                      (2 8) (2 8) (3 8) (2 8) (2 8))
    c8 c c d4 c8 c b c b a4 g fis8 e d c b' c d e4-^ fis8 g \break
    c,4. d4 c4 d4. c4 d c2 d4. e4-^ d4
    c4. d4 c4 d4. c4 d c2 d4. e4-^ d4 \break
    c4. d4 c4 d4. c4 d c2 d4. e4-^ d4
    c4. d4 c4 d4. c4 d c2 d4. e4-^ d4 \break
}

drum = \new DrumStaff \drummode {
    \bar ".|:" bd4. ^\markup { Drums } sn4 bd \bar ";" sn4.
    bd4 sn \bar ";" bd sn bd4. sn4 bd \bar ":|. "
}
```



Musical score for drums starting at measure 25. The score consists of two staves. The top staff shows a treble clef, a key signature of one sharp, and a common time signature. It features vertical bar lines and three dots above the staff, indicating a repeating pattern. The bottom staff is labeled "Drums" and shows a common time signature with a 25 over 8 time extension. It has vertical bar lines and includes a measure number 25. The notes are represented by vertical stems with dots at the top, indicating a rhythmic value of eighth note followed by sixteenth note.

Making an object invisible with the 'transparent' property

Setting the `transparent` property will cause an object to be printed in “invisible ink”: the object is not printed, but all its other behavior is retained. The object still takes up space, it takes part in collisions, and slurs, ties and beams can be attached to it.

This snippet demonstrates how to connect different voices using ties. Normally, ties only connect two notes in the same voice. By introducing a tie in a different voice, and blanking the first up-stem in that voice, the tie appears to cross voices.

```
\relative c' {
    \time 2/4
    <<
    {
        \once \hide Stem
        \once \override Stem.length = #8
        b8 ~ b\noBeam
        \once \hide Stem
        \once \override Stem.length = #8
        g8 ~ g\noBeam
    }
    \\
    {
        b8 g g e
    }
    >>
}
```

Making slurs with complex dash structure

Slurs can be made with complex dash patterns by defining the `dash-definition` property. `dash-definition` is a list of `dash-elements`. A `dash-element` is a list of parameters defining the dash behavior for a segment of the slur.

The slur is defined in terms of the bezier parameter t which ranges from 0 at the left end of the slur to 1 at the right end of the slur. **dash-element** is a list (**start-t stop-t dash-fraction dash-period**). The region of the slur from **start-t** to **stop-t** will have a fraction **dash-fraction** of each **dash-period** black. **dash-period** is defined in terms of staff spaces. **dash-fraction** is set to 1 for a solid slur.

```
\once \override
  Slur.dash-definition = #'((0 0.25 1 1)
                            (0.3 0.7 0.4 0.75)
                            (0.75 1.0 1 1))
c4( d e f)
}
```



Manually controlling beam positions

Beam positions may be controlled manually, by overriding the `positions` setting of the Beam grob.

```
\relative c' {
  \time 2/4
  % from upper staff-line (position 2) to center (position 0)
  \override Beam.positions = #'(2 . 0)
  c8 c
  % from center to one above center (position 1)
  \override Beam.positions = #'(0 . 1)
  c8 c
}
```



Merging multi-measure rests in a polyphonic part


When using multi-measure rests in a polyphonic staff, the rests will be placed differently depending on the voice they belong to. However they can be printed on the same staff line, using the following setting.

```
normalPos = \revert MultiMeasureRest.direction
```

```
{
  <<
  {
    c''1
    R1
    c''1
    \normalPos
    R1
  }
  \\
  {
    c'1
    R1
    c'1
    \normalPos
    R1
  }
```

```

}
>>
}
```




Modifying tuplet bracket length

Tuplet brackets can be made to run to prefatory matter or the next note. Default tuplet brackets end at the right edge of the final note of the tuplet; full-length tuplet brackets extend farther to the right, either to cover all the non-rhythmic notation up to the following note, or to cover only the whitespace before the next item of notation, be that a clef, time signature, key signature, or another note. The example shows how to switch tuplets to full length mode and how to modify what material they cover.

```

\new RhythmicStaff {
    % Set tuplets to be extendable...
    \set tupletFullLength = ##t
    % ...to cover all items up to the next note
    \set tupletFullLengthNote = ##t
    \time 2/4
    \tuplet 3/2 { c4 c c }
    % ...or to cover just whitespace
    \set tupletFullLengthNote = ##f
    \time 4/4
    \tuplet 5/4 { c4 c1 }
    \time 3/4
    c2.
}
```



Moving dotted notes in polyphony

When a dotted note in the upper voice is moved to avoid a collision with a note in another voice, the default is to move the upper note to the right. This behaviour can be over-ridden by using the `prefer-dotted-right` property of `NoteCollision`.

```

\new Staff \relative c' <<
    { f2. f4
        \override Staff.NoteCollision.prefer-dotted-right = ##f
        f2. f4
        \override Staff.NoteCollision.prefer-dotted-right = ##t
        f2. f4
    }
    \\
    { e4 e e e e e e e e e }
>>
```



Multi-measure rest markup

Markups attached to a multi-measure rest will be centered above or below it. Long markups attached to multi-measure rests do not cause the measure to expand. To expand a multi-measure rest to fit the markup, use an empty chord with an attached markup before the multi-measure rest.

Text attached to a spacer rest in this way is left-aligned to the position where the note would be placed in the measure, but if the measure length is determined by the length of the text, the text will appear to be centered.

```
\relative c' {
    \compressFullBarRests
    \textLengthOn
    <>^markup { [MAJOR GENERAL] }
    R1*19
    <>_markup { \italic { Cue: ... it is yours } }
    <>^markup { A }
    R1*30^markup { [MABEL] }
    \textLengthOff
    c4^markup { CHORUS } d f c
}
```

Non-default tuplet numbers


LilyPond also provides formatting functions to print tuplet numbers different than the actual fraction, as well as to append a note value to the tuplet number or tuplet fraction.

```
\relative c'' {
    \once \override TupletNumber.text =
        #(tuplet-number::non-default-tuplet-denominator-text 7)
    \tuplet 3/2 { c4. c4. c4. c4. }
    \once \override TupletNumber.text =
        #(tuplet-number::non-default-tuplet-fraction-text 12 7)
    \tuplet 3/2 { c4. c4. c4. c4. }
    \once \override TupletNumber.text =
        #(tuplet-number::append-note-wrapper
            (tuplet-number::non-default-tuplet-fraction-text 12 7) "8")
    \tuplet 3/2 { c4. c4. c4. c4. }

    \once \override TupletNumber.text =
        #(tuplet-number::append-note-wrapper
            tuplet-number::calc-denominator-text "4")
    \tuplet 3/2 { c8 c8 c8 c8 c8 c8 }
    \once \override TupletNumber.text =
        #(tuplet-number::append-note-wrapper
            tuplet-number::calc-fraction-text "4")
```

```
\tuplet 3/2 { c8 c8 c8 c8 c8 c8 }

\once \override TupletNumber.text =
  #(tuplet-number::fraction-with-notes "4." "8")
\tuplet 3/2 { c4. c4. c4. c4. }
\once \override TupletNumber.text =
  #(tuplet-number::non-default-fraction-with-notes 12 "8" 4 "4")
\tuplet 3/2 { c4. c4. c4. c4. }
}
```



Partcombine and autoBeamOff

The function of `\autoBeamOff` when used with `\partcombine` can be difficult to understand.

It may be preferable to use

```
\set Staff.autoBeaming = ##f
```

instead, to ensure that autobeamng will be turned off for the entire staff.

`\partcombine` apparently works with 3 voices – stem up single, stem down single, stem up combined.

An `\autoBeamOff` call in the first argument to `\partcombine` will apply to the voice that is active at the time the call is processed, either stem up single or stem up combined. An `\autoBeamOff` call in the second argument will apply to the voice that is stem down single.

In order to use `\autoBeamOff` to stop all autobeamng when used with `\partcombine`, it will be necessary to use three calls to `\autoBeamOff`.

```
{
  %\set Staff.autoBeaming = ##f % turns off all autobeamng
  \partcombine
  {
    \autoBeamOff % applies to split up stems
    \repeat unfold 4 a'16
    %\autoBeamOff % applies to combined up stems
    \repeat unfold 4 a'8
    \repeat unfold 4 a'16
  }
  {
    \autoBeamOff % applies to down stems
    \repeat unfold 4 f'8
    \repeat unfold 8 f'16 |
  }
}
```



Permitting line breaks within beamed tuplets

This artificial example shows how both manual and automatic line breaks may be permitted to within a beamed tuplet. Note that such off-beat tuplets have to be beamed manually.

```
\layout {
  \context {
    \Voice
      % Permit line breaks within tuplets
      \remove "Forbid_line_break_engraver"
      % Allow beams to be broken at line breaks
      \override Beam.breakable = ##t
  }
}

\relative c' {
  a8
  \repeat unfold 5 { \tuplet 3/2 { c[ b a] } }
  % Insert a manual line break within a tuplet
  \tuplet 3/2 { c[ b \bar{ } \break a] }
  \repeat unfold 5 { \tuplet 3/2 { c[ b a] } }
  c8
}
```



Positioning grace note beams at the height of normal note beams

When notes are placed on ledger lines, their beams are usually centred on the stave. Grace notes beams are shorter and grace notes on ledger lines may well have beams outside the stave. You can override this beaming for grace notes.


```
\relative c {
  f8[ e]
  \grace {
    f8[ e]
    \override Stem.no-stem-extend = ##f
    f8[ e]
    \revert Stem.no-stem-extend
  }
  f8[ e]
}
```



Positioning grace notes with floating space

Setting the property 'strict-grace-spacing' makes the musical columns for grace notes 'floating', i.e., decoupled from the non-grace notes: first the normal notes are spaced, then the (musical columns of the) graces are put left of the musical columns for the main notes.

```
\relative c' {
  <<
    \override Score.SpacingSpanner.strict-grace-spacing = ##t
    \new Staff \new Voice {
      \afterGrace c4 { c16[ c8 c16] }
      c8[ \grace { b16 d } c8]
      c4 r
    }
    \new Staff {
      c16 c c c c c c c4 r
    }
  >>
}
```



Positioning multi-measure rests

Unlike ordinary rests, there is no predefined command to change the staff position of a multi-measure rest symbol of either form by attaching it to a note. However, in polyphonic music multi-measure rests in odd-numbered and even-numbered voices are vertically separated. The positioning of multi-measure rests can be controlled as follows:

```
\relative c' {
  % Multi-measure rests by default are set under the fourth line
  R1
  % They can be moved using an override
  \override MultiMeasureRest.staff-position = #-2
  R1
  \override MultiMeasureRest.staff-position = #0
  R1
  \override MultiMeasureRest.staff-position = #2
  R1
  \override MultiMeasureRest.staff-position = #3
  R1
  \override MultiMeasureRest.staff-position = #6
  R1
  \revert MultiMeasureRest.staff-position
  \break

  % In two Voices, odd-numbered voices are under the top line
  << { R1 } \\ { a1 } >>
  % Even-numbered voices are under the bottom line
```



```

<< { a1 } \\ { R1 } >>
% Multi-measure rests in both voices remain separate
<< { R1 } \\ { R1 } >>

% Separating multi-measure rests in more than two voices
% requires an override
<< { R1 } \\ { R1 } \\
  \once \override MultiMeasureRest.staff-position = #0
  { R1 }
>>

% Using compressed bars in multiple voices requires another override
% in all voices to avoid multiple instances being printed
\compressFullBarRests
<<
  \revert MultiMeasureRest.direction
  { R1*3 }
  \\
  \revert MultiMeasureRest.direction
  { R1*3 }
>>
}

```



Preventing final mark from removing final tuplet

The addition of a final mark can result in the loss of a final tuplet marking. This can be overcome by setting `TupletBracket #'full-length-to-extent` to false.

```
\markup \vspace #1 %% workaround for LSR-problem
```

```



\new Staff {
  \set tupletFullLength = ##t
  \time 1/8
  \tuplet 3/2 { c'16 c'16 c'16 }
  \tuplet 3/2 { c'16 c'16 c'16 }
  \tuplet 3/2 { c'16 c'16 c'16 }
  \override Score.RehearsalMark.break-visibility = ##(##t ##t ##t)
  \override Score.RehearsalMark.direction = #DOWN
  \override Score.RehearsalMark.self-alignment-X = #RIGHT
% due to issue 2362 the following line is commented
%   \mark "Composed Feb 2007 - Feb 2008"
% and a shorter mark is used.
  \mark "1234"
}

```

```
\new Staff {
    \set tupletFullLength = ##t

    \override TupletBracket.full-length-to-extent = ##f

    \time 1/8
    \tuplet 3/2 { c'16 c'16 c'16 }
    \tuplet 3/2 { c'16 c'16 c'16 }
    \tuplet 3/2 { c'16 c'16 c'16 }
    \override Score.RehearsalMark.break-visibility = ##(##t ##t ##t)
    \override Score.RehearsalMark.direction = #DOWN
    \override Score.RehearsalMark.self-alignment-X = #RIGHT
% due to issue 2362 the following line is commented
%   \mark "Composed Feb 2007 - Feb 2008"
% and a shorter mark is used.
    \mark "1234"
}
```




Printing bar numbers at regular intervals

Bar numbers can be printed at regular intervals by setting the property `barNumberVisibility`. Here the bar numbers are printed every two measures except at the end of the line.

```
\relative c' {
    \override Score.BarNumber.break-visibility = #end-of-line-invisible
    \set Score.currentBarNumber = #11
    % Permit first bar number to be printed
    \bar ""
    % Print a bar number every second measure
    \set Score.barNumberVisibility = #(every-nth-bar-number-visible 2)
    c1 | c | c | c | c
    \break
    c1 | c | c | c | c
}
```





Printing bar numbers inside boxes or circles

Bar numbers can also be printed inside boxes or circles.

```
\relative c' {
    % Prevent bar numbers at the end of a line and permit them elsewhere
    \override Score.BarNumber.break-visibility = #end-of-line-invisible
    \set Score.barNumberVisibility = #(every-nth-bar-number-visible 4)

    % Increase the size of the bar number by 2
    \override Score.BarNumber.font-size = #2

    % Draw a box round the following bar number(s)
    \override Score.BarNumber.stencil
        = #(make-stencil-boxer 0.1 0.25 ly:text-interface::print)
    \repeat unfold 5 { c1 }

    % Draw a circle round the following bar number(s)
    \override Score.BarNumber.stencil
        = #(make-stencil-circler 0.1 0.25 ly:text-interface::print)
    \repeat unfold 4 { c1 } \bar "|."
}
```




Printing metronome and rehearsal marks below the staff

By default, metronome and rehearsal marks are printed above the staff. To place them below the staff simply set the `direction` property of `MetronomeMark` or `RehearsalMark` appropriately.

```
\layout { ragged-right = ##f }

{
    % Metronome marks below the staff
    \override Score.MetronomeMark.direction = #DOWN
    \tempo 8. = 120
    c'''1

    % Rehearsal marks below the staff
    \override Score.RehearsalMark.direction = #DOWN
    \mark \default
    c'''1
}
```



Printing music with different time signatures

In the following snippet, two parts have a completely different time signature, yet remain synchronized. The bar lines can no longer be printed at the `Score` level; to allow independent bar lines in each part, the `Default_barline_engraver` and `Timing_translator` are moved from the `Score` context to the `Staff` context.

If bar numbers are required, the `Bar_number_engraver` should also be moved, since it relies on properties set by the `Timing_translator`; a `\with` block can be used to add bar numbers to the relevant staff.

```
\paper {
    indent = #0
    ragged-right = ##t
}

global = { \time 3/4 { s2.*3 } \bar "" \break { s2.*3 } }

\layout {
    \context {
        \Score
        \remove "Timing_translator"
        \remove "Default_bar_line_engraver"
        \remove "Bar_number_engraver"
        \override SpacingSpanner.uniform-stretching = ##t
        \override SpacingSpanner.strict-note-spacing = ##t
        proportionalNotationDuration = #(ly:make-moment 1/64)
    }
    \context {
        \Staff
        \consists "Timing_translator"
        \consists "Default_bar_line_engraver"
    }
    \context {
        \Voice
        \remove "Forbid_line_break_engraver"
        tupletFullLength = ##t
    }
}

Bassklarinette = \new Staff \with {
    \consists "Bar_number_engraver"
    barNumberVisibility = #(every-nth-bar-number-visible 2)
    \override BarNumber.break-visibility = #end-of-line-invisible
} <<
\global {
    \bar "|"
    \clef treble
    \time 3/8
    d''4.

    \bar "|"
    \time 3/4
    r8 des''2( c''8)
```

```
\bar "|"
\time 7/8
r4. ees''2 ~

\bar "|"
\time 2/4
\tupletUp
\tuplet 3/2 { ees''4 r4 d''4 ~ }

\bar "|"
\time 3/8
\tupletUp
\tuplet 4/3 { d''4 r4 }

\bar "|"
\time 2/4
e''2

\bar "|"
\time 3/8
es''4.

\bar "|"
\time 3/4
r8 d''2 r8
\bar "|"
}
>>

Perkussion = \new StaffGroup <-
\new Staff <-
\global {
\bar "|"
\clef percussion
\time 3/4
r4 c'2 ~

\bar "|"
c'2.

\bar "|"
R2.

\bar "|"
r2 g'4 ~

\bar "|"
g'2. ~

\bar "|"
g'2.
```

```

        }
>>
\new Staff <<
  \global {
    \bar "|"
    \clef percussion
    \time 3/4
    R2.

    \bar "|"
    g'2. ~

    \bar "|"
    g'2.

    \bar "|"
    r4 g'2 ~

    \bar "|"
    g'2 r4

    \bar "|"
    g'2.
  }
>>
>>

\score {
  <<
    \Bassklarinette
    \Perkussion
  >>
}

```

The musical score is composed of two staves. The top staff is for Bassclarinet, indicated by a bass clef. It starts with a quarter note followed by a dotted half note. The bottom staff is for Percussion, indicated by a common clef. It starts with a dotted half note. Both staves switch to 4/4 time. The Bassclarinet has a long sustained note with a fermata, followed by a eighth note. The Percussion staff has a eighth note followed by a sustained note.

The image contains two musical staves. The top staff starts with a treble clef and a measure containing three eighth notes. It then changes to a 3/8 time signature with a single eighth note. This is followed by a 4/4 time signature with a rest, a 6/8 time signature with a single eighth note, and a 3/8 time signature with a single eighth note. The bottom staff starts with a treble clef and a 3/4 time signature with a single eighth note. It then changes to a 3/4 time signature with a rest, and finally to a 3/4 time signature with a single eighth note.

Printing the bar number for the first measure

By default, the first bar number in a score is suppressed if it is less than or equal to '1'. By setting `barNumberVisibility` to `#all-bar-numbers-visible`, any bar number can be printed for the first measure and all subsequent measures. Note that an empty bar line must be inserted before the first note for this to work.

```
\relative c' {
  \set Score.barNumberVisibility = #all-bar-numbers-visible
  \bar ""
  c1 | d | e | f \break
  g1 | e | d | c
}
```

The image shows two musical staves. The first staff is labeled with a '1' above the staff and contains a single note. The second staff is labeled with a '5' above the staff and contains a single note.

Redefining grace note global defaults

The global defaults for grace notes are stored in the identifiers `startGraceMusic`, `stopGraceMusic`, `startAcciaccaturaMusic`, `stopAcciaccaturaMusic`, `startAppoggiaturaMusic` and `stopAppoggiaturaMusic`, which are defined in the file `ly/grace-init.ly`. By redefining them other effects may be obtained.

```
startAcciaccaturaMusic = {
  <>(
  \override Flag.stroke-style = #"grace"
  \slurDashed
}
```

```

stopAcciaccaturaMusic = {
    \revert Flag.stroke-style
    \slurSolid
    <>
}
}

\relative c' {
    \acciaccatura d8 c1
}

```



Removing bar numbers from a score


Bar numbers can be removed entirely by removing the `Bar_number_engraver` from the `Score` context.

```

\layout {
    \context {
        \Score
        \remove "Bar_number_engraver"
    }
}

\relative c' {
    c4 c c c \break
    c4 c c c
}

```



Removing connecting bar lines on StaffGroup PianoStaff or GrandStaff


By default, bar lines in StaffGroup, PianoStaff, or GrandStaff groups are connected between the staves. This behaviour can be overridden on a staff-by-staff basis.

```

\relative c' {
    \new StaffGroup <<
        \new Staff {
            e1 | e
            \once \override Staff.BarLine.allow-span-bar = ##f
            e1 | e | e
        }
        \new Staff {
            c1 | c | c
        }
    >>
}

```

```
\once \override Staff.BarLine.allow-span-bar = ##f
c1 | c
}
\new Staff {
  a1 | a | a | a | a
}
>>
}
```



Rest styles

Rests may be used in various styles.

```
\layout {
  indent = 0
  \context {
    \Staff
    \remove "Time_signature_engraver"
  }
}

\new Staff \relative c {
  \cadenzaOn
  \override Staff.Rest.style = #'mensural
  r\maxima^\markup \typewriter { mensural }
  r\longa r\breve r1 r2 r4 r8 r16 s32 s64 s128 s128
  \bar ""

  \override Staff.Rest.style = #'neomensural
  r\maxima^\markup \typewriter { neomensural }
  r\longa r\breve r1 r2 r4 r8 r16 s32 s64 s128 s128
  \bar ""

  \override Staff.Rest.style = #'classical
  r\maxima^\markup \typewriter { classical }
  r\longa r\breve r1 r2 r4 r8 r16 r32 r64 r128 s128
  \bar ""

  \override Staff.Rest.style = #'default
  r\maxima^\markup \typewriter { default }
  r\longa r\breve r1 r2 r4 r8 r16 r32 r64 r128 s128
}
```

The image displays four staves of musical notation, each with a different beam ending style:

- mensural:** Shows a sequence of eighth notes grouped by vertical bar lines.
- neomensural:** Shows a sequence of eighth notes grouped by horizontal bar lines.
- classical:** Shows a sequence of eighth notes grouped by vertical bar lines, with some notes beamed together by horizontal lines.
- default:** Shows a sequence of eighth notes grouped by vertical bar lines, with complex horizontal beamings connecting notes across measure boundaries.

Reverting default beam endings

To typeset beams grouped 3-4-3-2 in 12/8 it is necessary first to override the default beam endings in 12/8, and then to set up the new beaming endings:

```
\relative c' {
    \time 12/8

    % Default beaming
    a8 a a a a a a a a a a a

    % Set new values for beam endings
    \set Score.beatStructure = #'(3 4 3 2)
    a8 a a a a a a a a a a
}
```

A single staff of music in 12/8 time, showing a sequence of eighth notes grouped by vertical bar lines, representing the default beaming behavior.

Rhythmic slashes

In “simple” lead-sheets, sometimes no actual notes are written, instead only “rhythmic patterns” and chords above the measures are notated giving the structure of a song. Such a feature is for example useful while creating/transcribing the structure of a song and also when sharing lead sheets with guitarists or jazz musicians. The standard support for this using `\repeat percent` is unsuitable here since the first beat has to be an ordinary note or rest. This example shows two solutions to this problem, by redefining ordinary rests to be printed as slashes. (If the duration of each beat is not a quarter note, replace the `r4` in the definitions with a rest of the appropriate duration).

```
% Macro to print single slash
rs = {
    \once \override Rest.stencil = #ly:percent-repeat-item-interface::beat-slash
    \once \override Rest.thickness = #0.48
    \once \override Rest.slope = #1.7
    r4
}
```

```
% Function to print a specified number of slashes
comp = #(define-music-function (parser location count) (integer?))
#{{
  \override Rest.stencil = #ly:percent-repeat-item-interface::beat-slash
  \override Rest.thickness = #0.48
  \override Rest.slope = #1.7
  \repeat unfold $count { r4 }
  \revert Rest.stencil
#}
}

\score {
  \relative c' {
    c4 d e f |
    \rs \rs \rs \rs |
    \comp #4 |
  }
}
```



Skips in lyric mode (2)

Although **s** skips cannot be used in `\lyricmode` (it is taken to be a literal “s”, not a space), double quotes (") or underscores (_) are available. So for example:


```
<<
  \relative c'' { a4 b c d }
  \new Lyrics \lyricmode { a4 "" _ gap }
>>
```



Skips in lyric mode

The **s** syntax for skips is only available in note mode and chord mode. In other situations, for example, when entering lyrics, using the `\skip` command is recommended.

```
<<
  \relative c'' { a1 | a }
  \new Lyrics \lyricmode { \skip 1 bla1 }
>>
```



Stemlets

In some notational conventions beams are allowed to extend over rests. Depending on preference, these beams may drop 'stemlets' to help the eye appreciate the rhythm better, and in some modern music the rest itself is omitted and only the stemlet remains.

This snippet shows a progression from traditional notation, to beams over the rest, to stemlets over the rest, to stemlets alone. Stemlets are generated by overriding the 'stemlet-length' property of `Staff.Stem`, while rests are hidden by setting '`transparent = ##t`'.


Some `\markup` elements are included in the source to highlight the different notations.

```
\paper { ragged-right = ##f }

{
  c'16^\markup { traditional } d' r f'
  g'16[^\markup { beams over rests } f' r d']

  % N.B. use Score.Stem to set for the whole score.
  \override Staff.Stem.stemlet-length = #0.75

  c'16[^\markup { stemlets over rests } d' r f']
  g'16[^\markup { stemlets and no rests } f'
    \once \hide Rest
    r16 d']
}
```



Strict beat beaming

Beamlets can be set to point in the direction of the beat to which they belong. The first beam avoids sticking out flags (the default); the second beam strictly follows the beat.

```
\relative c' {
  \time 6/8
  a8. a16 a a
  \set strictBeatBeaming = ##t
  a8. a16 a a
}
```



Subdividing beams

The beams of consecutive 16th (or shorter) notes are, by default, not subdivided. That is, the three (or more) beams stretch unbroken over entire groups of notes. This behavior can be modified to subdivide the beams into sub-groups by setting the property `subdivideBeams`. When set, multiple beams will be subdivided at intervals defined by the current value of `baseMoment` by reducing the multiple beams to just one beam between the sub-groups. Note that `baseMoment` defaults to one over the denominator of the current time signature if not set explicitly. It must

be set to a fraction giving the duration of the beam sub-group using the `ly:make-moment` function, as shown in this snippet. Also, when `baseMoment` is changed, `beatStructure` should also be changed to match the new `baseMoment`:

```
\relative c' {
  c32[ c c c c c c]
  \set subdivideBeams = ##t
  c32[ c c c c c c]

  % Set beam sub-group length to an eighth note
  \set baseMoment = #(ly:make-moment 1/8)
  \set beatStructure = #'(2 2 2)
  c32[ c c c c c c]

  % Set beam sub-group length to a sixteenth note
  \set baseMoment = #(ly:make-moment 1/16)
  \set beatStructure = #'(4 4 4 4)
  c32[ c c c c c c]
}
```



Three-sided box

This example shows how to add a markup command to get a three sided box around some text (or other markup).

```
% New command to add a three sided box, with sides north, west and south
% Based on the box-stencil command defined in scm/stencil.scm
% Note that ";" is used to comment a line in Scheme
#(define-public (NWS-box-stencil stencil thickness padding)
  "Add a box around STENCIL, producing a new stencil."
  (let* ((x-ext (interval-widen (ly:stencil-extent stencil X) padding))
         (y-ext (interval-widen (ly:stencil-extent stencil Y) padding))
         (y-rule (make-filled-box-stencil (cons 0 thickness) y-ext))
         (x-rule (make-filled-box-stencil
                   (interval-widen x-ext thickness) (cons 0 thickness))))
    ;; (set! stencil (ly:stencil-combine-at-edge stencil X 1 y-rule padding))
    (set! stencil (ly:stencil-combine-at-edge stencil X LEFT y-rule padding))
    (set! stencil (ly:stencil-combine-at-edge stencil Y UP x-rule 0.0))
    (set! stencil (ly:stencil-combine-at-edge stencil Y DOWN x-rule 0.0))
    stencil))

% The corresponding markup command, based on the \box command defined
% in scm/define-markup-commands.scm
#(define-markup-command (NWS-box layout props arg) (markup?))
  "Draw a box round @var{arg}. Looks at @code{thickness},
@code{box-padding} and @code{font-size} properties to determine line
thickness and padding around the markup."
  (let* ((th (chain-assoc-get 'thickness props 0.1))
         (size (chain-assoc-get 'font-size props 0)))
    (pad (* (magstep size)
```


```

  (chain-assoc-get 'box-padding props 0.2)))
  (m (interpret-markup layout props arg)))
(NWS-box-stencil m th pad))

% Test it:

\relative c' {
  c1^\markup { \NWS-box ABCD }
  c1^\markup { \NWS-box \note #"4" #1.0 }
}

```



Time signature printing only the numerator as a number (instead of the fraction)

Sometimes, a time signature should not print the whole fraction (e.g. $\frac{7}{4}$), but only the numerator (7 in this case). This can be easily done by using `\override Staff.TimeSignature.style = #'single-digit` to change the style permanently. By using `\revert Staff.TimeSignature.style`, this setting can be reversed. To apply the single-digit style to only one time signature, use the `\override` command and prefix it with a `\once`.

```

\relative c'' {
  \time 3/4
  c4 c c
  % Change the style permanently
  \override Staff.TimeSignature.style = #'single-digit
  \time 2/4
  c4 c
  \time 3/4
  c4 c c
  % Revert to default style:
  \revert Staff.TimeSignature.style
  \time 2/4
  c4 c
  % single-digit style only for the next time signature
  \once \override Staff.TimeSignature.style = #'single-digit
  \time 5/4
  c4 c c c c
  \time 2/4
  c4 c
}

```



Tweaking grace layout within music

The layout of grace expressions can be changed throughout the music using the functions `add-grace-property` and `remove-grace-property`. The following example undefines the `Stem`

direction for this grace, so that stems do not always point up, and changes the default note heads to crosses.

```
\relative c' {
  \new Staff {
    $(remove-grace-property 'Voice 'Stem 'direction)
    $(add-grace-property 'Voice 'NoteHead 'style 'cross)
    \new Voice {
      \acciaccatura { f16 } g4
      \grace { d16 e } f4
      \appoggiatura { f,,32 g a } e2
    }
  }
}
```



Using alternative flag styles

Alternative styles of flag on eighth and shorter notes can be displayed by overriding the `stencil` property of `Flag`. Valid values are `modern-straight-flag` and `old-straight-flag`.


```
testnotes = {
  \autoBeamOff
  c8 d16 c32 d64 \acciaccatura { c8 } d64 r4
}

\relative c' {
  \time 2/4
  \testnotes

  \override Flag.stencil = #modern-straight-flag
  \testnotes

  \override Flag.stencil = #old-straight-flag
  \testnotes

  \revert Flag.stencil
  \testnotes
}
```



Using grace note slashes with normal heads

The slash through the stem found in acciaccaturas can be applied in other situations.

```
\relative c' {
    \override Flag.stroke-style = #"grace"
    c8( d2) e8( f4)
}
```



Using ties with arpeggios

Ties are sometimes used to write out arpeggios. In this case, two tied notes need not be consecutive. This can be achieved by setting the `tieWaitForNote` property to `#t`. The same feature is also useful, for example, to tie a tremolo to a chord, but in principle, it can also be used for ordinary consecutive notes.

```
\relative c' {
    \set tieWaitForNote = ##t
    \grace { c16[ ~ e ~ g] ~ } <c, e g>2
    \repeat tremolo 8 { c32 ~ c' ~ } <c c,>1
    e8 ~ c ~ a ~ f ~ <e' c a f>2
    \tieUp
    c8 ~ a
    \tieDown
    \tieDotted
    g8 ~ c g2
}
```



Expressive marks

Section “Expressive marks” in *Notation Reference*

Adding beams slurs ties etc. when using tuplet and non-tuplet rhythms

LilyPond syntax can involve many unusual placements for parentheses, brackets etc., which might sometimes have to be interleaved. For example, when entering a manual beam, the left square bracket has to be placed after the starting note and its duration, not before. Similarly, the right square bracket should directly follow the note which is to be at the end of the requested beaming, even if this note happens to be inside a tuplet section. This snippet demonstrates how to combine manual beaming, manual slurs, ties and phrasing slurs with tuplet sections (enclosed within curly braces).

```
{
r16[ g16 \tuplet 3/2 { r16 e'8} ]
g16( a \tuplet 3/2 { b d e') }
g8[( a \tuplet 3/2 { b d') e'] ~ }
\time 2/4
\tuplet 5/4 { e'32\(\( a b d' e' \) a'4.\)
}
```



Adding parentheses around an expressive mark or chordal note

The `\parenthesize` function is a special tweak that encloses objects in parentheses. The associated grob is `ParenthesesItem`.

```
\relative c' {
  c2-\parenthesize
  \override ParenthesesItem.padding = #0.1
  \override ParenthesesItem.font-size = #-4
  <d \parenthesize f a>2
}
```



Adding timing marks to long glissandi

Skipped beats in very long glissandi are sometimes indicated by timing marks, often consisting of stems without noteheads. Such stems can also be used to carry intermediate expression markings.

If the stems do not align well with the glissando, they may need to be repositioned slightly.

```
glissandoSkipOn = {
  \override NoteColumn.glissando-skip = ##t
  \hide NoteHead
```

```
\override NoteHead.no-ledgers = ##t
}

glissandoSkipOff = {
  \revert NoteColumn.glissando-skip
  \undo \hide NoteHead
  \revert NoteHead.no-ledgers
}

\relative c' {
  r8 f8\glissando
  \glissandoSkipOn
  f4 g a a8\noBeam
  \glissandoSkipOff
  a8

  r8 f8\glissando
  \glissandoSkipOn
  g4 a8
  \glissandoSkipOff
  a8 |

  r4 f\glissando \l
  \glissandoSkipOn
  a4\f \r
  \glissandoSkipOff
  b8!\r |
}
```



Adjusting the shape of falls and doits

The `shortest-duration-space` property may be tweaked to adjust the shape of falls and doits.

```
\relative c' {
  \override Score.Spacer.shortest-duration-space = #4.0
  c2-\bendAfter #5
  c2-\bendAfter #-4.75
  c2-\bendAfter #8.5
  c2-\bendAfter #-6
}
```



Alternative breve notes

Breve notes are also available with two vertical lines on each side of the notehead instead of one line and in baroque style.

```
\relative c'' {
    \time 4/2
    c\brevet
    \override Staff.NoteHead.style = #'altdefault
    b\brevet
    \override Staff.NoteHead.style = #'baroque
    b\brevet
    \revert Staff.NoteHead.style
    a\brevet
}
```



Asymmetric slurs

Slurs can be made asymmetric to match an asymmetric pattern of notes better.

```
slurNotes = { d,8( a' d f a f' d, a) }
```

```
\relative c' {
    \stemDown
    \slurUp
    \slurNotes
    \once \override Slur.eccentricity = #3.0
    \slurNotes
}
```



Breathing signs

Breathing signs are available in different tastes: commas (default), ticks, vees and “railroad tracks” (caesura).

```
\new Staff \relative c'' {
    \key es \major
    \time 3/4
    % this bar contains no \breathe
    << { g4 as g } \\ { es4 bes es } >> |
    % Modern notation:
    % by default, \breathe uses the rcomma, just as if saying:
    % \override BreathingSign.text = #(make-musicglyph-markup "scripts.rcomma")
    << { g4 as g } \\ { es4 \breathe bes es } >> |

    % rvarcomma and lvarcomma are variations of the default rcomma and lcomma
    % N.B.: must use Staff context here, since we start a Voice below
    \override Staff.BreathingSign.text = \markup { \musicglyph #'scripts.rvarcomma }
    << { g4 as g } \\ { es4 \breathe bes es } >> |
```

```
% vee
\override BreathingSign.text = \markup { \musicglyph #"scripts.upbow" }
es8[ d es f g] \breathe f |

% caesura
\override BreathingSign.text = \markup { \musicglyph #"scripts.caesura.curved" }
es8[ d] \breathe es[ f g f] |
es2 r4 \bar "||"
}
```



Broken Crescendo Hairpin

In order to make parts of a crescendo hairpin invisible, the following method is used: A white rectangle is drawn on top of the respective part of the crescendo hairpin, making it invisible.

The markup command `with-dimensions` tells LilyPond to consider only the bottom edge of the rectangle when spacing it against the hairpin. The property `staff-padding` prevents the rectangle from fitting between the hairpin and staff.

Make sure to put the hairpin in a lower layer than the text markup to draw the rectangle over the hairpin.

```
\relative c' {
  <<
  {
    \dynamicUp
    r2 r16 c'8.\pp r4
  }
  \\
  {
    \override DynamicLineSpanner.layer = #0
    des,2\mf< ~
    \override TextScript.layer = #2
    \once\override TextScript.staff-padding = #6
    \once\override TextScript.vertical-skylines = #'()
    des16_\markup \with-dimensions #'(2 . 7) #'(0 . 0)
      \with-color #white
      \filled-box #'(2 . 7) #'(0 . 2) #0
    r8. des4 ~ des16->\fff
  }
  >>
}
```



Caesura ("railtracks") with fermata

A caesura is sometimes denoted by a double “railtracks” breath mark with a fermata sign positioned above. This snippet shows an optically pleasing combination of railtracks and fermata.

```
\relative c' {
  c2.
  % construct the symbol
  \override BreathingSign.text = \markup {
    \line {
      \musicglyph #'scripts.caesura.curved"
      \translate #'(-1.75 . 1.6)
      \musicglyph #'scripts.ufermata"
    }
  }
  \breathe c4
  % set the breathe mark back to normal
  \revert BreathingSign.text
  c2. \breathe c4
  \bar "|."
}
```



Center text below hairpin dynamics

This example provides a function to typeset a hairpin (de)crescendo with some additional text below it, such as “molto” or “poco”. The added text will change the direction according to the direction of the hairpin. The Hairpin is aligned to DynamicText.

The example also illustrates how to modify the way an object is normally printed, using some Scheme code.

```
hairpinWithCenteredText =
#(define-music-function (parser location text) (markup?))
#{

\once \override Voice.Hairpin.after-line-breaking =
  #(lambda (grob)
    (let* ((stencil (ly:hairpin::print grob))
           (par-y (ly:grob-parent grob Y))
           (dir (ly:grob-property par-y 'direction))
           (new-stencil (ly:stencil-aligned-to
                         (ly:stencil-combine-at-edge
                           (ly:stencil-aligned-to stencil X CENTER)
                           Y dir
                           (ly:stencil-aligned-to (grob-interpret-markup grob text) X CENTER))■
                         X LEFT)))
      (staff-space (ly:output-def-lookup (ly:grob-layout grob) 'staff-space))■
      (staff-line-thickness
        (ly:output-def-lookup (ly:grob-layout grob) 'line-thickness))
      (grob-name (lambda (x) (assq-ref (ly:grob-property x 'meta) 'name)))
      (par-x (ly:grob-parent grob X))
      (dyn-text (eq? (grob-name par-x) 'DynamicText ))
```

```

(dyn-text-stencil-x-length
  (if dyn-text
    (interval-length
      (ly:grob-property par-x 'stencil) X))
  0))
(x-shift
  (if dyn-text
    (-
      (+ staff-space dyn-text-stencil-x-length)
      (* 0.5 staff-line-thickness)) 0)))

(ly:grob-set-property! grob 'Y-offset 0)
(ly:grob-set-property! grob 'stencil
  (ly:stencil-translate-axis
    new-stencil
    x-shift X)))
#}

hairpinMolto =
\hairpinWithCenteredText \markup { \italic molto }

hairpinMore =
\hairpinWithCenteredText \markup { \larger moltissimo }

\layout { ragged-right = ##f }

\relative c' {
  \hairpinMolto
  c2< c\f
  \hairpinMore
  c2\ppppp< c\f
  \break
  \hairpinMolto
  c2^< c\f
  \hairpinMore
  c2\ppppp< c\f
}

```

The musical score consists of two staves. The top staff is in common time (C) with a treble clef. It contains two pairs of eighth notes. The first pair is preceded by a hairpin dynamic with the word "molto" written below it, and followed by a forte dynamic (f). The second pair is preceded by a hairpin dynamic with the word "moltissimo" written below it, and followed by a forte dynamic (f). The bottom staff is also in common time (C) with a treble clef. It contains two pairs of eighth notes. The first pair is preceded by a hairpin dynamic with the word "molto" written above it, and followed by a forte dynamic (f). The second pair is preceded by a hairpin dynamic with the word "moltissimo" written below it, and followed by a forte dynamic (f).


Changing \flageolet mark size

To make the \flageolet circle smaller use the following Scheme function.

```
smallFlageolet =
#(let ((m (make-articulation "flageolet")))
  (set! (ly:music-property m 'tweaks)
        (acons 'font-size -3
              (ly:music-property m 'tweaks)))
  m)

\layout { ragged-right = ##f }

\relative c' {
  d4^{\flageolet_\markup { default size } d_\flageolet}
  c4^{\smallFlageolet_\markup { smaller } c_\smallFlageolet}
}
```



Changing text and spanner styles for text dynamics

The text used for crescendos and decrescendos can be changed by modifying the context properties `crescendoText` and `decrescendoText`.

The style of the spanner line can be changed by modifying the `'style` property of `DynamicTextSpanner`. The default value is `'dashed-line`, and other possible values include `'line`, `'dotted-line` and `'none`.

```
\relative c' {
  \set crescendoText = \markup { \italic { cresc. poco } }
  \set crescendoSpanner = #'text
  \override DynamicTextSpanner.style = #'dotted-line
  a2< a
  a2 a
  a2 a
  a2 a\mf
}
```




Changing the appearance of a slur from solid to dotted or dashed

The appearance of slurs may be changed from solid to dotted or dashed.

```
\relative c' {
  c4( d e c)
  \slurDotted
  c4( d e c)
  \slurSolid
```

```
c4( d e c)
\slurDashed
c4( d e c)
\slurSolid
c4( d e c)
}
```



Changing the breath mark symbol

The glyph of the breath mark can be tuned by overriding the `text` property of the `BreathingSign` layout object with any markup text.

```
\relative c' {
  c2
  \override BreathingSign.text =
    \markup { \musicglyph #"scripts.rvarcomma" }
  \breathe
  d2
}
```



Changing the number of augmentation dots per note

The number of augmentation dots on a single note can be changed independently of the dots placed after the note.

```
\relative c' {
  c4.. a16 r2 |
  \override Dots.dot-count = #4
  c4.. a16 r2 |
  \override Dots.dot-count = #0
  c4.. a16 r2 |
  \revert Dots.dot-count
  c4.. a16 r2 |
}
```




Combining dynamics with markup texts

Some dynamics may involve text indications (such as “più forte” or “piano subito”). These can be produced using a `\markup` block.

```
piuF = \markup { \italic più \dynamic f }
\layout { ragged-right = ##f }
```

```
\relative c' {
    c2\f c-\piuF
}
```



Contemporary glissando

A contemporary glissando without a final note can be typeset using a hidden note and cadenza timing.

```
\relative c' {
    \time 3/4
    \override Glissando.style = #'zigzag
    c4 c
    \cadenzaOn
    c4\glissando
    \hideNotes
    c,,4
    \unHideNotes
    \cadenzaOff
    \bar "|"
}
```



Controlling spanner visibility after a line break

The visibility of spanners which end on the first note following a line break is controlled by the `after-line-breaking` callback `ly:spanner::kill-zero-spanned-time`.

For objects such as glissandos and hairpins, the default behaviour is to hide the spanner after a break; disabling the callback will allow the left-broken span to be shown.

Conversely, spanners which are usually visible, such as text spans, can be hidden by enabling the callback.

```
\paper { ragged-right = ##t }

\relative c' {
    \override Hairpin.to-barline = ##f
    \override Glissando.breakable = ##t
    % show hairpin
    \override Hairpin.after-line-breaking = ##t
    % hide text span
    \override TextSpanner.after-line-breaking =
        #ly:spanner::kill-zero-spanned-time
    e2\<\startTextSpan
    % show glissando
    \override Glissando.after-line-breaking = ##t
```

```
f2\glissando
\break
f,1!\stopTextSpan
}
```



Controlling the vertical ordering of scripts

The vertical ordering of scripts is controlled with the 'script-priority' property. The lower this number, the closer it will be put to the note. In this example, the `TextScript` (the sharp symbol) first has the lowest priority, so it is put lowest in the first example. In the second, the prall trill (the `Script`) has the lowest, so it is on the inside. When two objects have the same priority, the order in which they are entered determines which one comes first.

```
\relative c''' {
    \once \override TextScript.script-priority = #-100
    a2^\prall^\markup { \sharp }

    \once \override Script.script-priority = #-100
    a2^\prall^\markup { \sharp }
}
```



Creating a delayed turn

Creating a delayed turn, where the lower note of the turn uses the accidental, requires several overrides. The `outside-staff-priority` property must be set to `#f`, as otherwise this would take precedence over the `avoid-slur` property. Changing the fractions `2/3` and `1/3` adjusts the horizontal position.

```
\relative c'' {
    c2*2/3 ( s2*1/3\turn d4) r
    <<
    { c4.( d8) }
    { s4 s\turn }
    >>
    \transpose c d \relative c'' <<
    { c4.( d8) }
    {
        s4
        \once \set suggestAccidentals = ##t
        \once \override AccidentalSuggestion #'outside-staff-priority = ##f
    }
}
```

```
\once \override AccidentalSuggestion #'avoid-slur = #'inside
\once \override AccidentalSuggestion #'font-size = #-3
\once \override AccidentalSuggestion #'script-priority = #-1
\single \hideNotes
b8-\turn \noBeam
s8
}
>>
}
```



Creating arpeggios across notes in different voices

An arpeggio can be drawn across notes in different voices on the same staff if the `Span_arpeggio_engraver` is added to the `Staff` context:

```
\new Staff \with {
  \consists "Span_arpeggio_engraver"
}
\relative c' {
  \set Staff.connectArpeggios = ##t
  <<
  { <e' g>4\arpeggio <d f> <d f>2 }
  \\
  { <d, f>2\arpeggio <g b>2 }
  >>
}
```



Creating cross-staff arpeggios in a piano staff


In a `PianoStaff`, it is possible to let an arpeggio cross between the staves by setting the property `PianoStaff.connectArpeggios`.

```
\new PianoStaff \relative c' <<
  \set PianoStaff.connectArpeggios = ##t
  \new Staff {
    <c e g c>4\arpeggio
    <g c e g>4\arpeggio
    <e g c e>4\arpeggio
    <c e g c>4\arpeggio
  }
  \new Staff {
    \clef bass
    \repeat unfold 4 {
      <c,, e g c>4\arpeggio
    }
  }
}
```

```

    }
}
>>

```




Creating cross-staff arpeggios in other contexts

Cross-staff arpeggios can be created in contexts other than `GrandStaff`, `PianoStaff` and `StaffGroup` if the `Span_arpeggio_engraver` is included in the `Score` context.

```

\score {
  \new ChoirStaff {
    \set Score.connectArpeggios = ##t
    <<
    \new Voice \relative c' {
      <c e>2\arpeggio
      <d f>2\arpeggio
      <c e>1\arpeggio
    }
    \new Voice \relative c {
      \clef bass
      <c g'>2\arpeggio
      <b g'>2\arpeggio
      <c g'>1\arpeggio
    }
    >>
  }
  \layout {
    \context {
      \Score
      \consists "Span_arpeggio_engraver"
    }
  }
}


```



Creating double-digit fingerings

Creating fingerings larger than 5 is possible.

```
\relative c' {
    c1-10
    c1-50
    c1-36
    c1-29
}
```



Creating "real" parenthesized dynamics

Although the easiest way to add parentheses to a dynamic mark is to use a `\markup` block, this method has a downside: the created objects will behave like text markups, and not like dynamics.

However, it is possible to create a similar object using the equivalent Scheme code (as described in the Notation Reference), combined with the `make-dynamic-script` function. This way, the markup will be regarded as a dynamic, and therefore will remain compatible with commands such as `\dynamicUp` or `\dynamicDown`.

```
paren =
#(define-event-function (parser location dyn) (ly:event?)
  (make-dynamic-script
    #{
      \markup \concat {
        \normal-text \italic \fontsize #2 (
        \pad-x #0.2 #(ly:music-property dyn 'text)
        \normal-text \italic \fontsize #2 )
      }
    #}))

\relative c'' {
  c4\paren\f c c \dynamicUp c\paren\p
}
```



Creating simultaneous rehearsal marks

Unlike text scripts, rehearsal marks cannot be stacked at a particular point in a score: only one `RehearsalMark` object is created. Using an invisible measure and bar line, an extra rehearsal mark can be added, giving the appearance of two marks in the same column. This method may also prove useful for placing rehearsal marks at both the end of one system and the start of the following system.

```
{
  \key a \major
  \set Score.markFormatter = #format-mark-box-letters
  \once \override Score.RehearsalMark.outside-staff-priority = #5000
  \once \override Score.RehearsalMark.self-alignment-X = #LEFT
```

```
\once \override Score.RehearsalMark.break-align-symbols = #'(key-signature)
\mark \markup { \bold { Senza denti } }

% the hidden measure and bar line
% \cadenzaOn turns off automatic calculation of bar numbers
\cadenzaOn
\once \omit Score.TimeSignature
\time 1/16
s16 \bar ""
\cadenzaOff

\time 4/4
\once \override Score.RehearsalMark.self-alignment-X = #LEFT
\mark \markup { \box \bold Intro }
d'1
\mark \default
d'1
}
```

Senza denti

Intro **A**

A musical staff with a treble clef, two sharps in the key signature, and a time signature of 4/4. It contains two notes: a solid black note head followed by an empty note head.

Creating slurs across voices

In some situations, it may be necessary to create slurs between notes from different voices.

The solution is to add invisible notes to one of the voices, using `\hideNotes`.

This example is measure 235 of the Ciaconna from Bach's 2nd Partita for solo violin, BWV 1004.

```
\relative c' {
<<
{
  d16( a') s a s a[ s a] s a[ s a]
}
\\
{
  \slurUp
  bes,16[ s e]( 
  \hideNotes a)
  \unHideNotes f[( 
  \hideNotes a)
  \unHideNotes fis]( 
  \hideNotes a)
  \unHideNotes g[( 
  \hideNotes a)
  \unHideNotes gis]( 
  \hideNotes a)
}
>>
}
```



Creating text spanners

The `\startTextSpan` and `\stopTextSpan` commands allow the creation of text spanners as easily as pedal indications or octavations. Override some properties of the `TextSpanner` object to modify its output.

```
\paper { ragged-right = ##f }


\relative c' {
    \override TextSpanner.bound-details.left.text = #"bla"
    \override TextSpanner.bound-details.right.text = #"blu"
    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan

    \override TextSpanner.style = #'line
    \once \override TextSpanner.bound-details.left.stencil-align-dir-y = #CENTER
    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan

    \override TextSpanner.style = #'dashed-line
    \override TextSpanner.bound-details.left.text =
        \markup { \draw-line #'(0 . 1) }
    \override TextSpanner.bound-details.right.text =
        \markup { \draw-line #'(0 . -2) }
    \once \override TextSpanner.bound-details.right.padding = #-2

    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan

    \set Staff.middleCPosition = #-13
    \override TextSpanner.dash-period = #10
    \override TextSpanner.dash-fraction = #0.5
    \override TextSpanner.thickness = #10
    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan
}
```



Double glissando

To connect chords with glissando lines, attach a second glissando to a hidden voice.

```
\relative c {
```

```
\clef bass
<<
{
  % new voice (= \voiceOne), hidden
  \hideNotes
  % attach glissando to note heads
  e2\glissando g
}
\\
{
  % original voice with chords rearranged so that
  % glissando is attached to a & c
  <e a,>2\glissando <g c,>
}
>>
}
```




Dynamics custom text spanner postfix

Postfix functions for custom crescendo text spanners. The spanners should start on the first note of the measure. One has to use -\mycresc, otherwise the spanner start will rather be assigned to the next note.

```
% Two functions for (de)crescendo spanners where you can explicitly give the
% spanner text.
mycresc =
#(define-music-function (parser location mymarkup) (markup?))
  (make-music 'CrescendoEvent
              'span-direction START
              'span-type 'text
              'span-text mymarkup))

mydecresc =
#(define-music-function (parser location mymarkup) (markup?))
  (make-music 'DecrescendoEvent
              'span-direction START
              'span-type 'text
              'span-text mymarkup))

\relative c' {
  c4-\mycresc "custom cresc" c4 c4 c4 |
  c4 c4 c4 c4 |
  c4-\mydecresc "custom decresc" c4 c4 c4 |
  c4 c4! c4 c4
}
```



Dynamics text spanner postfix

Custom text spanners can be defined and used with hairpin and text crescendos. \< and \> produce hairpins by default, \cresc etc. produce text spanners by default.

```
% Some sample text dynamic spanners, to be used as postfix operators
```

```
crpoco =
 #(make-music 'CrescendoEvent
              'span-direction START
              'span-type 'text
              'span-text "cresc. poco a poco")

\relative c' {
  c4\cresc d4 e4 f4 |
  g4 a4\! b4\crpoco c4 |
  c4 d4 e4 f4 |
  g4 a4\! b4\< c4 |
  g4\dim a4 b4\decresc c4\!
}
```



Glissandi can skip grobs

NoteColumn grobs can be skipped over by glissandi.

```
\relative c' {
  a2 \glissando
  \once \override NoteColumn.glissando-skip = ##t
  f'''4 d,
}
```




Hairpins with different line styles

Hairpins can take any style from line-interface - dashed-line, dotted-line, line, trill or zigzag.

```
\relative c' {
  c2\< c\!
  \override Hairpin.style = #'dashed-line
  c2\< c\!
  \override Hairpin.style = #'dotted-line
  c2\< c\!
  \override Hairpin.style = #'line
  c2\< c\!
  \override Hairpin.style = #'trill
  c2\< c\!
  \override Hairpin.style = #'zigzag
  c2\< c\!
```


```
\revert Hairpin.style
c2\< c\!
}
```



Hiding the extender line for text dynamics

Text style dynamic changes (such as cresc. and dim.) are printed with a dashed line showing their extent. This line can be suppressed in the following way:

```
\relative c' {
  \override DynamicTextSpanner.style = #'none
  \crescTextCresc
  c1\< | d | b | c\!
}
```



Horizontally aligning custom dynamics (e.g. "sempre pp" "piu f" "subito p")

Some dynamic expressions involve additional text, like “sempre pp”. Since dynamics are usually centered under the note, the \pp would be displayed way after the note it applies to.

To correctly align the “sempre pp” horizontally, so that it is aligned as if it were only the \pp, there are several approaches:

- * Simply use \once\override DynamicText.X-offset = #-9.2 before the note with the dynamics to manually shift it to the correct position. Drawback: This has to be done manually each time you use that dynamic markup...

- * Add some padding (#:hspace 7.1) into the definition of your custom dynamic mark, so that after lilypond center-aligns it, it is already correctly aligned. Drawback: The padding really takes up that space and does not allow any other markup or dynamics to be shown in that position.

- * Shift the dynamic script \once\override ...X-offset = ... Drawback: \once\override is needed for every invocation!

- * Set the dimensions of the additional text to 0 (using #:with-dimensions '(0 . 0) '(0 . 0)). Drawback: To LilyPond “sempre” has no extent, so it might put other stuff there and create collisions (which are not detected by the collision detection!). Also, there seems to be some spacing, so it's not exactly the same alignment as without the additional text

- * Add an explicit shifting directly inside the scheme function for the dynamic-script.

- * Set an explicit alignment inside the dynamic-script. By default, this won't have any effect, only if one sets X-offset! Drawback: One needs to set DynamicText #'X-offset, which will apply to all dynamic texts! Also, it is aligned at the right edge of the additional text, not at the center of pp.

```
\header { title = "Horizontally aligning custom dynamics" }
```

```
\paper { ragged-right = ##f }

% Solution 1: Using a simple markup with a particular halign value
% Drawback: It's a markup, not a dynamic command, so \dynamicDown
%           etc. will have no effect
semppMarkup = \markup { \halign #1.4 \italic "sempre" \dynamic "pp" }

% Solution 2: Using a dynamic script & shifting with
%             \once \override ...X-offset = ..
% Drawback: \once \override needed for every invocation
semppK =
#(make-dynamic-script
  (markup #:line
    (#:normal-text
      #:italic "sempre"
      #:dynamic "pp")))

% Solution 3: Padding the dynamic script so the center-alignment
%             puts it at the correct position
% Drawback: the padding really reserves the space, nothing else can be there
semppT =
#(make-dynamic-script
  (markup #:line
    (#:normal-text
      #:italic "sempre"
      #:dynamic "pp"
      #:hspace 7.1)))

% Solution 4: Dynamic, setting the dimensions of the additional text to 0
% Drawback: To lilypond "sempre" has no extent, so it might put
%           other stuff there => collisions
% Drawback: Also, there seems to be some spacing, so it's not exactly the
%           same alignment as without the additional text
semppM =
#(make-dynamic-script
  (markup #:line
    (#:with-dimensions '(0 . 0) '(0 . 0)
      #:right-align
      #:normal-text
      #:italic "sempre"
      #:dynamic "pp")))

% Solution 5: Dynamic with explicit shifting inside the scheme function
semppG =
#(make-dynamic-script
  (markup #:hspace 0
    #:translate '(-18.85 . 0)
    #:line (#:normal-text
      #:italic "sempre"
      #:dynamic "pp")))






% Solution 6: Dynamic with explicit alignment. This has only effect
```

```
%           if one sets X-offset!
% Drawback: One needs to set DynamicText.X-offset!
% Drawback: Aligned at the right edge of the additional text,
%           not at the center of pp
semppMII =
#(make-dynamic-script
  (markup #:line (#:right-align
                  #:normal-text
                  #:italic "sempre"
                  #:dynamic "pp")))

\context StaffGroup <<
\context Staff = "s" <<
  \set Staff.instrumentName = #"Normal"
  \relative c' {
    \key es \major
    c4\pp c\p c c | c\ff c c\pp c
  }
>>
\context Staff = "sMarkup" <<
  \set Staff.instrumentName = \markup \column { Normal markup }
  \relative c' {
    \key es \major
    c4-\semppMarkup c\p c c | c\ff c c-\semppMarkup c
  }
>>
\context Staff = "sK" <<
  \set Staff.instrumentName = \markup \column { Explicit shifting }
  \relative c' {
    \key es \major
    \once \override DynamicText.X-offset = #-9.2
    c4\semppK c\p c c
    c4\ff c
    \once \override DynamicText.X-offset = #-9.2
    c4\semppK c
  }
>>
\context Staff = "sT" <<
  \set Staff.instrumentName = \markup \column { Right padding }
  \relative c' {
    \key es \major
    c4\semppT c\p c c | c\ff c c\semppT c
  }
>>
\context Staff = "sM" <<
  \set Staff.instrumentName = \markup \column { Setting dimension "to zero" }
  \relative c' {
    \key es \major
    c4\semppM c\p c c | c\ff c c\semppM c
  }
>>
\context Staff = "sG" <<
```

```
\set Staff.instrumentName = \markup \column { Shifting inside dynamics }
\relative c' {
    \key es \major
    c4\semppG c\p c c | c\ff c c\semppG c
}
>>
\context Staff = "sMII" <<
\set Staff.instrumentName = \markup \column { Alignment inside dynamics }
\relative c' {
    \key es \major
    % Setting to ##f (false) gives the same result
    \override DynamicText.X-offset = #0
    c4\semppMII c\p c c | c\ff c c\semppMII c
}
>>
>>
```

Horizontally aligning custom dynamics

	Left	Right
Normal		
Normal markup		
Explicit shifting		
Right padding		
Setting dimension to zero		
Shifting inside dynamics		
Alignment inside dynamics		

How to print two rehearsal marks above and below the same barline (method 1)

This method prints two 'rehearsal marks', one on top of the other. It shifts the lower rehearsal mark below the staff and then adds padding above it in order to place the upper rehearsal mark above the staff.

By adjusting the extra-offset and baseline-skip values you can increase or decrease the overall space between the rehearsal mark and the staff.

Because nearly every type of glyph or string can be made to behave like a rehearsal mark it is possible to centre those above and below a bar line.

Adding the appropriate 'break visibility' as shown in snippet 1 will allow you to position two marks at the end of a line as well.

Note: Method 1 is less complex than Method 2 but does not really allow for fine tuning of placement of one of the rehearsal marks without affecting the other. It may also give some problems with vertical spacing, since using `extra-offset` does not change the bounding box of the mark from its original value.

```
\relative c'{
    c d e f |
    \once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
    \once \override Score.RehearsalMark.baseline-skip = #9
    \mark \markup \center-column { \circle 1 \box A }
    g f e d |
    \once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
    \once \override Score.RehearsalMark.baseline-skip = #9
    \mark \markup \center-column { \flat { \bold \small \italic Fine. } }
    g f e d |
    \once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
    \once \override Score.RehearsalMark.baseline-skip = #9
    \override Score.RehearsalMark.break-visibility = #begin-of-line-invisible
    \mark \markup \center-column { \fermata \box z }
}
```



How to print two rehearsal marks above and below the same barline (method 2)

This method prints two 'rehearsal marks' - one above the stave and one below, by creating two voices, adding the Rehearsal Mark engraver to each voice - without this no rehearsal mark is printed - and then placing each rehearsal mark UP and DOWN in each voice respectively.


This method (as opposed to method 1) is more complex, but allows for more flexibility, should it be needed to tweak each rehearsal mark independently of the other.

```
\score {
    \relative c'
    <<
    \new Staff {
        <<
        \new Voice \with {
            \consists Mark_engraver
            \consists "Staff_collecting_engraver"
        }
        { c4 d e f
            \mark \markup { \box A }
        }
    }
}
```

```

c4 d e f
}
\new Voice \with {
  \consists Mark_engraver
  \consists "Staff_collecting_engraver"
  \override RehearsalMark.direction = #DOWN
}
{ s4 s s s
  \mark \markup { \circle 1 }
  s4 s s s
}
>>
}
>>
\layout {
  \context {
    \Score
    \remove "Mark_engraver"
    \remove "Staff_collecting_engraver"
  }
}
}

```



Inserting a caesura

Caesura marks can be created by overriding the 'text' property of the BreathingSign object. A curved caesura mark is also available.

```

\relative c' {
  \override BreathingSign.text = \markup {
    \musicglyph #"scripts.caesura.straight"
  }
  c8 e4. \breathe g8. e16 c4

  \override BreathingSign.text = \markup {
    \musicglyph #"scripts.caesura.curved"
  }
  g8 e'4. \breathe g8. e16 c4
}

```



Laissez vibrer ties

Laissez vibrer ties have a fixed size. Their formatting can be tuned using 'tie-configuration'.

```
\relative c' {
  <c e g>4\laissezVibrer r <c f g>\laissezVibrer r
  <c d f g>4\laissezVibrer r <c d f g>4.\laissezVibrer r8

  <c d e f>4\laissezVibrer r
  \override LaissezVibrerTieColumn.tie-configuration
    = #`((-7 . ,DOWN)
      (-5 . ,DOWN)
      (-3 . ,UP)
      (-1 . ,UP))
  <c d e f>4\laissezVibrer r
}
```



Line arrows

Arrows can be applied to text-spanners and line-spanners (such as the Glissando).

```
\relative c'' {
  \override TextSpanner.bound-padding = #1.0
  \override TextSpanner.style = #'line
  \override TextSpanner.bound-details.right.arrow = ##t
  \override TextSpanner.bound-details.left.text = #"fof"
  \override TextSpanner.bound-details.right.text = #"gag"
  \override TextSpanner.bound-details.right.padding = #0.6

  \override TextSpanner.bound-details.right.stencil-align-dir-y = #CENTER
  \override TextSpanner.bound-details.left.stencil-align-dir-y = #CENTER

  \override Glissando.bound-details.right.arrow = ##t
  \override Glissando.arrow-length = #0.5
  \override Glissando.arrow-width = #0.25

  a8\startTextSpan gis a4 b\glissando b,
  g'4 c\stopTextSpan c2
}
```



Making slurs with complex dash structure

Slurs can be made with complex dash patterns by defining the `dash-definition` property. `dash-definition` is a list of `dash-elements`. A `dash-element` is a list (`start-t stop-t dash-fraction dash-period`). The region of the slur from `start-t` to `stop-t` will have a

The slur is defined in terms of the bezier parameter `t` which ranges from 0 at the left end of the slur to 1 at the right end of the slur. `dash-element` is a list (`start-t stop-t dash-fraction dash-period`). The region of the slur from `start-t` to `stop-t` will have a

fraction dash-fraction of each dash-period black. dash-period is defined in terms of staff spaces. dash-fraction is set to 1 for a solid slur.

```
\relative c' {
  \once \override
    Slur.dash-definition = #'((0 0.3 0.1 0.75)
                               (0.3 0.6 1 1)
                               (0.65 1.0 0.4 0.75))

  c4( d e f)
  \once \override
    Slur.dash-definition = #'((0 0.25 1 1)
                               (0.3 0.7 0.4 0.75)
                               (0.75 1.0 1 1))

  c4( d e f)
}
```




Modifying default values for articulation shorthand notation

The shorthands are defined in ‘ly/script-init.ly’, where the variables `dashHat`, `dashPlus`, `dashDash`, `dashBang`, `dashLarger`, `dashDot`, and `dashUnderscore` are assigned default values. The default values for the shorthands can be modified. For example, to associate the `-+` (`dashPlus`) shorthand with the trill symbol instead of the default `+` symbol, assign the value `trill` to the variable `dashPlus`:

```
\relative c'' { c1-+ }

dashPlus = "trill"

\relative c'' { c1-+ }
```




Moving slur positions vertically

The vertical position of a slur can be adjusted using the `positions` property of `Slur`. The property has 2 parameters, the first referring to the left end of the slur and the second to the right. The values of the parameters are not used by LilyPond to make an exact movement of the slur - instead it selects what placement of the slur looks best, taking into account the parameter values. Positive values move the slur up, and are appropriate for notes with stems down. Negative values move downward slurs further down.

```
\relative c' {
  \stemDown
  e4( a)
```


```
\override Slur.positions = #'(1 . 1)
e4( a)
\override Slur.positions = #'(2 . 2)
e4( a)
\override Slur.positions = #'(3 . 3)
e4( a)
\override Slur.positions = #'(4 . 4)
e4( a)
\override Slur.positions = #'(5 . 5)
e4( a)
\override Slur.positions = #'(0 . 5)
e4( a)
\override Slur.positions = #'(5 . 0)
e4( a)
\stemUp
\override Slur.positions = #'(-5 . -5)
e4( a)
\stemDown
\revert Slur.positions
e4( a)
}
```



Positioning arpeggios

If you need to extend or shorten an arpeggio, you can modify the upper and lower start positions independently.

```
\relative c' {
  <c e g b>1\arpeggio
  \once \override Arpeggio.positions = #'(-5 . 0)
  <c e g b>1\arpeggio
  \once \override Arpeggio.positions = #'(0 . 5)
  <c e g b>1\arpeggio
  \once \override Arpeggio.positions = #'(-5 . 5)
  <c e g b>1\arpeggio
}
```



Positioning text markups inside slurs

Text markups need to have the `outside-staff-priority` property set to false in order to be printed inside slurs.

```
\relative c'' {
  \override TextScript.avoid-slur = #'inside
```



```
\override TextScript.outside-staff-priority = ##f
c2(^\markup { \halign #10 \natural } d4.) c8
}
```



Printing hairpins in various styles

Hairpin dynamics may be created in a variety of styles

```
\relative c' {
  \override Hairpin.stencil = #flared-hairpin
  a4< a a a\f
  a4\p< a a a\ff
  a4\sfz< a a a\!
  \override Hairpin.stencil = #constante-hairpin
  a4< a a a\f
  a4\p< a a a\ff
  a4\sfz< a a a\!
  \override Hairpin.stencil = #flared-hairpin
  a4> a a a\f
  a4\p> a a a\ff
  a4\sfz> a a a\!
  \override Hairpin.stencil = #constante-hairpin
  a4> a a a\f
  a4\p> a a a\ff
  a4\sfz> a a a\!
}
```



Printing hairpins using al niente notation

Hairpin dynamics may be printed with a circled tip (“al niente” notation) by setting the `circled-tip` property of the `Hairpin` object to `#t`.

```
\relative c' {
  \override Hairpin.circled-tip = ##t
  c2< c\!
  c4> c< c2\!
}
```




Printing metronome and rehearsal marks below the staff

By default, metronome and rehearsal marks are printed above the staff. To place them below the staff simply set the `direction` property of `MetronomeMark` or `RehearsalMark` appropriately.

```
\layout { ragged-right = ##f }

{
    % Metronome marks below the staff
    \override Score.MetronomeMark.direction = #DOWN
    \tempo 8. = 120
    c''1


    % Rehearsal marks below the staff
    \override Score.RehearsalMark.direction = #DOWN
    \mark \default
    c''1
}
```



Setting hairpin behavior at bar lines

If the note which ends a hairpin falls on a downbeat, the hairpin stops at the bar line immediately preceding. This behavior can be controlled by overriding the '`to-barline`' property.

```
\relative c'' {
    e4< e2.
    e1\!
    \override Hairpin.to-barline = ##f
    e4< e2.
    e1\!
}
```



Setting the minimum length of hairpins

If hairpins are too short, they can be lengthened by modifying the `minimum-length` property of the `Hairpin` object.

```
\relative c'' {
    c4< c\! d> e\!
    \override Hairpin.minimum-length = #5
    << f1 { s4 s< s> s\! } >>
}
```



Showing the same articulation above and below a note or chord


By default, LilyPond does not allow the same articulation (e.g., an accent, a fermata, a flageolet, etc.) to be displayed above and below a note. For example, `c4_\fermata^\fermata` will only show a fermata below. The fermata above will simply be ignored. However, one can stick scripts (just like fingerings) inside a chord, which means it is possible to have as many articulations as desired. This approach has the advantage that it ignores the stem and positions the articulation relative to the note head. This can be seen in the case of the flageolets in the snippet. To mimic the behaviour of scripts outside a chord, `'add-stem-support` would be required. So, the solution is to write the note as a chord and add the articulations inside the `<...>`. The direction will always be above, but one can tweak this via a `\tweak`: `<c-\tweak direction #DOWN-\fermata^\fermata>`

```
% The same as \flageolet, just a little smaller
smallFlageolet =
#(let ((m (make-articulation "flageolet")))
  (set! (ly:music-property m 'tweaks)
    (acons 'font-size -2
      (ly:music-property m 'tweaks)))
  m)

\relative c' {
  s4^"Wrong:"
  c4_\fermata^\fermata % The second fermata is ignored!
  <e d'>4^smallFlageolet_\smallFlageolet

  s4^"Works if written inside a chord:"
  <e_\smallFlageolet d'^\smallFlageolet>4
  <e_\flageolet d'^\flageolet>4
  <e_\smallFlageolet^\smallFlageolet>4
  <e_\fermata^\fermata>4
}
```


Wrong: Works if written inside a chord:



Snap-pizzicato or Bartok pizzicato

A snap-pizzicato (also known as “Bartok pizzicato”) is a “strong pizzicato where the string is plucked vertically by snapping and rebounds off the fingerboard of the instrument” (Wikipedia). It is denoted by a circle with a vertical line going from the center upwards outside the circle.

```
\relative c' {
  c4\snappizzicato
  <c' e g>4\snappizzicato
  <c' e g>4^\snappizzicato
  <c, e g>4_\snappizzicato
}
```



Using a tick as the breath mark symbol

Vocal and wind music frequently uses a tick mark as a breathing sign. This indicates a breath that subtracts a little time from the previous note rather than causing a short pause, which is indicated by the comma breath mark. The mark can be moved up a little to take it away from the stave.

```
\relative c' {
  c2
  \breathe
  d2
  \override BreathingSign.Y-offset = #2.6
  \override BreathingSign.text =
    \markup { \musicglyph #'scripts.tickmark" }
  c2
  \breathe
  d2
}
```



Using arpeggioBracket to make divisi more visible

The `arpeggioBracket` can be used to indicate the division of voices where there are no stems to provide the information. This is often seen in choral music.


```
\include "english.ly"

\score {
  \relative c' {
    \key a \major
    \time 2/2
    <<
    \new Voice = "upper"
    <<
    { \voiceOne \arpeggioBracket
      a2( b2
      <b d>1\arpeggio)
      <cs e>\arpeggio ~
      <cs e>4
    }
    \addlyrics { \lyricmode { A -- men. } }
    >>
    \new Voice = "lower"
    { \voiceTwo
      a1 ~
      a
      a ~
    }
  }
}
```

```

    a4 \bar "|."
}
>>
}
\layout { ragged-right = ##t }
}

```



Using double slurs for legato chords

Some composers write two slurs when they want legato chords. This can be achieved by setting `doubleSlurs`.

```

\relative c' {
  \set doubleSlurs = ##
  <c e>4( <d f> <c e> <d f>)
}

```



Using the whiteout property

Any graphical object can be printed over a white background to mask parts of objects that lie beneath. This can be useful to improve the appearance of collisions in complex situations when repositioning objects is impractical. It is necessary to explicitly set the `layer` property to control which objects are masked by the white background.

In this example the collision of the tie with the time signature is improved by masking out the part of the tie that crosses the time signature by setting the `whiteout` property of `TimeSignature`. To do this `TimeSignature` is moved to a layer above `Tie`, which is left in the default layer of 1, and `StaffSymbol` is moved to a layer above `TimeSignature` so it is not masked.

```

{
  \override Score.StaffSymbol.layer = #4
  \override Staff.TimeSignature.layer = #3
  b'2 b'~
  \once \override Staff.TimeSignature.whiteout = ##t
  \time 3/4
  b' r4
}

```



Vertical line as a baroque articulation mark

This short vertical line placed above the note is commonly used in baroque music. Its meaning can vary, but generally indicates notes that should be played with more “weight”. The following example demonstrates how to achieve such a notation.

```
upline =
#(let ((m (make-articulation "stopped")))
  (set! (ly:music-property m 'tweaks)
        (acons 'font-size 3
              (acons 'stencil (lambda (grob)
                                (grob-interpret-markup
                                 grob
                                 (make-draw-line-markup '(0 . 1)))))
              (ly:music-property m 'tweaks))))
  m)
```


```
\relative c' {
  a'4^upline a( c d')_upline
}
```



Vertically aligning dynamics across multiple notes

Dynamics that occur at, begin on, or end on the same note will be vertically aligned. To ensure that dynamics are aligned when they do not occur on the same note, increase the `staff-padding` property of the `DynamicLineSpanner` object.

```
\relative c' {
  \override DynamicLineSpanner.staff-padding = #4
  c2\p f\mf
  g2\< b4\> c\  
!
```



Repeats

Section “Repeats” in *Notation Reference*

Adding volta brackets to additional staves

The `Volta_engraver` by default resides in the `Score` context, and brackets for the repeat are thus normally only printed over the topmost staff. This can be adjusted by adding the `Volta_engraver` to the `Staff` context where the brackets should appear; see also the “Volta multi staff” snippet.

```
<<
\new Staff { \repeat volta 2 { c'1 } \alternative { c' } }
\new Staff { \repeat volta 2 { c'1 } \alternative { c' } }
\new Staff \with { \consists "Volta_engraver" } { c'2 g' e' a' }
\new Staff { \repeat volta 2 { c'1 } \alternative { c' } }
>>
```



Centered measure numbers

Scores of large ensemble works often have bar numbers placed beneath the system, centered horizontally on the measure’s extent. This snippet shows how the `Measure_counter_engraver` may be used to simulate this notational practice. Here, the engraver has been added to a `Dynamics` context.

```
\layout {
  \context {
    \Dynamics
    \consists #Measure_counter_engraver
    \override MeasureCounter.direction = #DOWN
    \override MeasureCounter.font-encoding = #'latin1
    \override MeasureCounter.font-shape = #'italic
    % to control the distance of the Dynamics context from the staff:
    \override VerticalAxisGroup.nonstaff-relatedstaff-spacing.padding = #2
  }
  \context {
    \Score
    \remove "Bar_number_engraver"
  }
}
```


```

}

pattern = \repeat unfold 7 { c'4 d' e' f' }

\new StaffGroup <-
  \new Staff {
    \pattern
  }
  \new Staff {
    \pattern
  }
  \new Dynamics {
    \startMeasureCount
    s1*7
    \stopMeasureCount
  }
>>

```




Cross-staff tremolos

Since `\repeat tremolo` expects exactly two musical arguments for chord tremolos, the note or chord which changes staff within a cross-staff tremolo should be placed inside curly braces together with its `\change Staff` command.

```

\new PianoStaff <-
  \new Staff = "up" \relative c' {
    \key a \major
    \time 3/8
    s4.
  }
  \new Staff = "down" \relative c' {
    \key a \major
    \time 3/8
    \voiceOne
    \repeat tremolo 6 {
      <a e'>32
      {
        \change Staff = "up"
        \voiceTwo
        <cis a' dis>32
      }
    }
  }
>>

```



Engraving tremolos with floating beams

If a tremolo's total duration is less than a quarter-note, or exactly a half-note, or between a half-note and a whole-note, it is normally typeset with all beams touching the stems. Certain engraving styles typeset some of these beams as centered floating beams that do not touch the stems. The number of floating beams in this type of tremolo is controlled with the 'gap-count' property of the Beam object, and the size of the gaps between beams and stems is set with the 'gap' property.

```
\relative c'' {
    \repeat tremolo 8 { a32 f }
    \override Beam.gap-count = #1
    \repeat tremolo 8 { a32 f }
    \override Beam.gap-count = #2
    \repeat tremolo 8 { a32 f }
    \override Beam.gap-count = #3
    \repeat tremolo 8 { a32 f }

    \override Beam.gap-count = #3
    \override Beam.gap = #1.33
    \repeat tremolo 8 { a32 f }
    \override Beam.gap = #1
    \repeat tremolo 8 { a32 f }
    \override Beam.gap = #0.67
    \repeat tremolo 8 { a32 f }
    \override Beam.gap = #0.33
    \repeat tremolo 8 { a32 f }
}
```



Isolated percent repeats

Isolated percents can also be printed.

```
makePercent =
#(define-music-function (parser location note) (ly:music?))
  "Make a percent repeat the same length as NOTE."
  (make-music 'PercentEvent
              'length (ly:music-length note)))

\relative c'' {
    \makePercent s1
}
```



Measure counter

This snippet provides a workaround for emitting measure counters using transparent percent repeats.

```
<<
\context Voice = "foo" {
  \clef bass
  c4 r g r
  c4 r g r
  c4 r g r
  c4 r g r
}
\context Voice = "foo" {
  \set countPercentRepeats = ##t
  \hide PercentRepeat
  \override PercentRepeatCounter.staff-padding = #1
  \repeat percent 4 { s1 }
}
>>
```



Numbering groups of measures

This snippet demonstrates the use of the `Measure_counter_engraver` to number groups of successive measures. Any stretch of measures may be numbered, whether consisting of repetitions or not.

The engraver must be added to the appropriate context. Here, a `Staff` context is used; another possibility is a `Dynamics` context.

The counter is begun with `\startMeasureCount` and ended with `\stopMeasureCount`. Numbering will start by default with 1, but this behavior may be modified by overriding the `count-from` property.

When a measure extends across a line break, the number will appear twice, the second time in parentheses.

```
\layout {
  \context {
    \Staff
    \consists #Measure_counter_engraver
  }
}

\new Staff {
  \startMeasureCount
  \repeat unfold 7 {
    c'4 d' e' f'
  }
  \stopMeasureCount
  \bar "| |"
```

```

g'4 f' e' d'
\override Staff.MeasureCounter.count-from = #2
\startMeasureCount
\repeat unfold 5 {
    g'4 f' e' d'
}
g'4 f'
\bar ""
\break
e'4 d'
\repeat unfold 7 {
    g'4 f' e' d'
}
\stopMeasureCount
}

```




Percent repeat count visibility

Percent repeat counters can be shown at regular intervals by setting the context property `repeatCountVisibility`.

```

\relative c'' {
    \set countPercentRepeats = ##
    \set repeatCountVisibility = #(every-nth-repeat-count-visible 5)
    \repeat percent 10 { c1 } \break
    \set repeatCountVisibility = #(every-nth-repeat-count-visible 2)
    \repeat percent 6 { c1 d1 }
}

```



Percent repeat counter

Measure repeats of more than two repeats can get a counter when the convenient property is switched, as shown in this example:

```
\relative c' {
  \set countPercentRepeats = ##t
  \repeat percent 4 { c1 }
}
```



Positioning segno and coda (with line break)

If you want to place an exiting segno sign and add text like “D.S. al Coda” next to it where usually the staff lines are you can use this snippet. The coda will resume in a new line. There is a variation documented in this snippet, where the coda will remain on the same line.

```
{
  \clef treble
  \key g \major
  \time 4/4
  \relative c' {
    \repeat unfold 4 {
      c4 c c c
    }

    % Set segno sign as rehearsal mark and adjust size if needed
    % \once \override Score.RehearsalMark.font-size = #3
    \mark \markup { \musicglyph #"scripts.segno" }
    \repeat unfold 2 {
      c4 c c c
    }

    % Set coda sign as rehearsal mark and adjust size if needed
    \once \override Score.RehearsalMark.font-size = #4
    \mark \markup { \musicglyph #"scripts.coda" }
    \repeat unfold 2 {
      c4 c c c
    }

    % Should Coda be on anew line?
    % Coda NOT on new line: use \nobreak
    % Coda on new line: DON'T use \nobreak
    % \noBreak

    \bar "||"

    % Set segno sign as rehearsal mark and adjust size if needed
    \once \override Score.RehearsalMark.break-visibility = #begin-of-line-invisible■
    % \once \override Score.RehearsalMark.font-size = #3
    \mark \markup { \musicglyph #"scripts.segno" }
```

```
% Here begins the trickery!
% \cadenzaOn will suppress the bar count and \stopStaff removes the staff lines.■
\cadenzaOn
\stopStaff
% Some examples of possible text-displays

% text line-aligned
% =====
% Move text to the desired position
% \once \override TextScript.extra-offset = #'( 2 . -3.5 )
% | <>^markup { D.S. al Coda } }

% text center-aligned
% =====
% Move text to the desired position
% \once \override TextScript.extra-offset = #'( 6 . -5.0 )
% | <>^markup { \center-column { D.S. "al Coda" } }

% text and symbols center-aligned
% =====
% Move text to the desired position and tweak spacing for optimum text alignment■
\repeat unfold 1 {
    s1
    \bar ""
}
\once \override TextScript.extra-offset = #'( 0 . -3.0 )
\once \override TextScript.word-space = #1.5
<>^markup { \center-column { "D.S. al Coda" \line { \musicglyph #"scripts.coda" \mu
}

% Increasing the unfold counter will expand the staff-free space
\repeat unfold 3 {
    s1
    \bar ""
}
% Resume bar count and show staff lines again
\startStaff
\cadenzaOff

% Should Coda be on new line?
% Coda NOT on new line: DON'T use \break
% Coda on new line: use \break
\break

% Show up, you clef and key!
\once \override Staff.KeySignature.break-visibility = #end-of-line-invisible
\once \override Staff.Clef.break-visibility = #end-of-line-invisible

% Set coda sign as rehearsal mark and adjust size and position

% Put the coda sign ontop of the (treble-)clef dependend on coda's line-position■
```

```
% Coda NOT on new line, use this:  

% \once \override Score.RehearsalMark.extra-offset = #'( -2 . 1.75 )  
  

% Coda on new line, use this:  

\once \override Score.RehearsalMark.extra-offset = #'( -4.5 . 0 )  
  

\once \override Score.RehearsalMark.font-size = #5  

\mark \markup { \musicglyph {"scripts.coda"} }  
  

% The coda  

\repeat unfold 5 {  


    c4 c c c  

}  

\bar "|."  

}  

}
```



Printing a repeat sign at the beginning of a piece

A .|: bar line can be printed at the beginning of a piece, by overriding the relevant property:

```
\relative c' {  

\once \override Score.BreakAlignment.break-align-orders =  

#(make-vector 3 '(instrument-name  

    left-edge  

    ambitus  

    breathing-sign  

    clef  

    key-signature  

    time-signature  

    staff-bar  

    custos))  
  

\once \override Staff.TimeSignature.space-alist =  

#'( (first-note . (fixed-space . 2.0))  


    (right-edge . (extra-space . 0.5))  

    ;; free up some space between time signature
```

```

;; and repeat bar line
(staff-bar . (extra-space . 1)))
\bar ".|:"
c1
d1
d4 e f g
}

```




Setting the double repeat default for volte

There are three different styles of double repeats for volte, that can be set using `doubleRepeatType`.

```

\relative c' {
  \repeat volta 1 { c1 }
  \set Score.doubleRepeatType = #":...:"
  \repeat volta 1 { c1 }
  \set Score.doubleRepeatType = #":|.|:"
  \repeat volta 1 { c1 }
  \set Score.doubleRepeatType = #":|.:"
  \repeat volta 1 { c1 }
}

```



Shortening volta brackets

By default, the volta brackets will be drawn over all of the alternative music, but it is possible to shorten them by setting `voltaSpannerDuration`. In the next example, the bracket only lasts one measure, which is a duration of $3/4$.

```

\relative c' {
  \time 3/4
  c4 c c
  \set Score.voltaSpannerDuration = #(ly:make-moment 3/4)
  \repeat volta 5 { d4 d d }
  \alternative {
    {
      e4 e e
      f4 f f
    }
    { g4 g g }
  }
}


```



Volta below chords

By adding the `Volta_engraver` to the relevant staff, volta can be put under chords.

```
\score {
  <<
  \chords {
    c1
    c1
  }
  \new Staff \with {
    \consists "Volta_engraver"
  }
  {
    \repeat volta 2 { c'1 }
    \alternative { c' }
  }
  >>
  \layout {
    \context {
      \Score
      \remove "Volta_engraver"
    }
  }
}
```



Volta multi staff

By adding the `Volta_engraver` to the relevant staff, volta can be put over staves other than the topmost one in a score.

```
voltaMusic = \relative c'' {
  \repeat volta 2 {
    c1
  }
  \alternative {
    d1
    e1
  }
}

<<
\new StaffGroup <<
  \new Staff \voltaMusic
  \new Staff \voltaMusic
>>
\new StaffGroup <<
  \new Staff \with { \consists "Volta_engraver" }
  \voltaMusic
```

```
\new Staff \voltaMusic
>>
>>
```

Volta text markup using repeatCommands

Though volte are best specified using `\repeat volta`, the context property `repeatCommands` must be used in cases where the volta text needs more advanced formatting with `\markup`.

Since `repeatCommands` takes a list, the simplest method of including markup is to use an identifier for the text and embed it in the command list using the Scheme syntax `#(list (list 'volta textIdentifier))`. Start- and end-repeat commands can be added as separate list elements:

```
voltaAdLib = \markup { 1. 2. 3... \text \italic { ad lib. } }

\relative c' {
  c1
  \set Score.repeatCommands = #(list (list 'volta voltaAdLib) 'start-repeat)
  c4 b d e
  \set Score.repeatCommands = #'((volta #f) (volta "4.") end-repeat)
  f1
  \set Score.repeatCommands = #'((volta #f))
}
```

Simultaneous notes

Section “Simultaneous notes” in *Notation Reference*

Additional voices to avoid collisions

In some instances of complex polyphonic music, additional voices are necessary to prevent collisions between notes. If more than four parallel voices are needed, additional voices can be added by defining a variable using the Scheme function `context-spec-music`.

```
voiceFive = #(context-spec-music (make-voice-props-set 4) 'Voice)
```

```
\relative c' {
  \time 3/4
  \key d \minor
  \partial 2
  <<
  \new Voice {
    \voiceOne
    a4. a8
    e'4 e4. e8
    f4 d4. c8
  }
  \new Voice {
    \voiceTwo
    d,2
    d4 cis2
    d4 bes2
  }
  \new Voice {
    \voiceThree
    f'2
    bes4 a2
    a4 s2
  }
  \new Voice {
    \voiceFive
    s2
    g4 g2
    f4 f2
  }
  >>
}
```




Changing a single note's size in a chord

Individual note heads in a chord can be modified with the `\tweak` command inside a chord, by altering the `font-size` property.

Inside the chord (within the brackets < >), before the note to be altered, place the \tweak command, followed by #'font-size and define the proper size like #-2 (a tiny note head).

```
\relative c' {
  <\tweak font-size #+2 c e g c \tweak font-size #-2 e>1^{\markup { A tiny e }}_ {\markup { A b }}
```



Changing partcombine texts

When using the automatic part combining feature, the printed text for the solo and unison sections may be changed:

```
\new Staff <<
  \set Staff.soloText = #"girl"
  \set Staff.soloIIText = #"boy"
  \set Staff.aDueText = #"together"
  \partcombine
    \relative c'' {
      g4 g r r
      a2 g
    }
    \relative c'' {
      r4 r a( b)
      a2 g
    }
  >>
```




Clusters

Clusters are a device to denote that a complete range of notes is to be played.

```
fragment = \relative c' {
  c4 f <e d'>4
  <g a>8 <e a> a4 c2 <d b>4
  e2 c
}

<<
  \new Staff \fragment
  \new Staff \makeClusters \fragment
>>
```



Combining two parts on the same staff

The part combiner tool (\partcombine command) allows the combination of several different parts on the same staff. Text directions such as “solo” or “a2” are added by default; to remove them, simply set the property printPartCombineTexts to f. For vocal scores (hymns), there is no need to add “solo/a2” texts, so they should be switched off. However, it might be better not to use it if there are any solos, as they won’t be indicated. In such cases, standard polyphonic notation may be preferable.

This snippet presents the three ways two parts can be printed on a same staff: standard polyphony, \partcombine without texts, and \partcombine with texts.

```

musicUp = \relative c' {
    \time 4/4
    a4 c4.( g8) a4 |
    g4 e' g,( a8 b) |
    c b a2.
}

musicDown = \relative c' {
    g4 e4.( d8) c4 |
    r2 g'4( f8 e) |
    d2 \stemDown a
}

\score {
    <<
    <<
    \new Staff {
        \set Staff.instrumentName = #"Standard polyphony"
        << \musicUp \\ \musicDown >>
    }
    \new Staff \with { printPartCombineTexts = ##f } {
        \set Staff.instrumentName = #"PartCombine without texts"
        \partcombine \musicUp \musicDown
    }
    \new Staff {
        \set Staff.instrumentName = #"PartCombine with texts"
        \partcombine \musicUp \musicDown
    }
    >>
    >>
    \layout {
        indent = 6.0\cm
        \context {
            \Score
            \override SystemStartBar.collapse-height = #30
        }
    }
}

```

}

Standard polyphony

PartCombine without texts

PartCombine with texts

Displaying complex chords

Here is a way to display a chord where the same note is played twice with different accidentals.

```
fixA = {
    \once \override Stem.length = #9
}
fixB = {
    \once \override NoteHead.X-offset = #1.7
    \once \override Stem.rotation = #'(45 0 0)
    \once \override Stem.extra-offset = #'(-0.2 . -0.2)
    \once \override Flag.style = #'no-flag
    \once \override Accidental.extra-offset = #'(4 . 0)
}

\relative c' {
    << { \fixA <b d!>8 } \\ { \voiceThree \fixB dis } >> s
}
```



Double glissando

To connect chords with glissando lines, attach a second glissando to a hidden voice.

```
\relative c {
    \clef bass
    <<
    {
        % new voice (= \voiceOne), hidden
        \hideNotes
        % attach glissando to note heads
        e2\glissando g
    }
    \\
    {
        % original voice with chords rearranged so that
    }
}
```

```
% glissando is attached to a & c
<e a,>2\glissando <g c,>
}
>>
}
```



Forcing horizontal shift of notes

When the typesetting engine cannot cope, the following syntax can be used to override typesetting decisions. The units of measure used here are staff spaces.

```
\relative c' <<
{
  <d g>2 <d g>
}
\\
{
  <b f'>2
  \once \override NoteColumn.force-hshift = #1.7
  <b f'>2
}
>>
```



Making an object invisible with the 'transparent' property

Setting the `transparent` property will cause an object to be printed in “invisible ink”: the object is not printed, but all its other behavior is retained. The object still takes up space, it takes part in collisions, and slurs, ties and beams can be attached to it.

This snippet demonstrates how to connect different voices using ties. Normally, ties only connect two notes in the same voice. By introducing a tie in a different voice, and blanking the first up-stem in that voice, the tie appears to cross voices.

```
\relative c'' {
  \time 2/4
  <<
  {
    \once \hide Stem
    \once \override Stem.length = #8
    b8 ~ b\noBeam
    \once \hide Stem
    \once \override Stem.length = #8
    g8 ~ g\noBeam
  }
  \\
```

```
{
  b8 g g e
}
>>
}
```



Moving dotted notes in polyphony

When a dotted note in the upper voice is moved to avoid a collision with a note in another voice, the default is to move the upper note to the right. This behaviour can be over-ridden by using the `prefer-dotted-right` property of `NoteCollision`.

```
\new Staff \relative c' <<
  { f2. f4
    \override Staff.NoteCollision.prefer-dotted-right = ##f
    f2. f4
    \override Staff.NoteCollision.prefer-dotted-right = ##t
    f2. f4
  }
  \\
  { e4 e e e e e e e e}
>>
```



Suppressing warnings for clashing note columns

If notes from two voices with stems in the same direction are placed at the same position, and both voices have no shift or the same shift specified, the error message ‘warning: ignoring too many clashing note columns’ will appear when compiling the LilyPond file. This message can be suppressed by setting the ‘`ignore-collision`’ property of the `NoteColumn` object to `#t`. Please note that this does not just suppress warnings but stops LilyPond trying to resolve collisions at all and so may have unintended results unless used with care.

```
ignore = \override NoteColumn.ignore-collision = ##t

\relative c' {
  <<
  \ignore
  { \stemDown f2 g }
  \\
  { c2 c, }
  >>
}
```



Staff notation

Section “Staff notation” in *Notation Reference*

Adding ambitus per voice

Ambitus can be added per voice. In this case, the ambitus must be moved manually to prevent collisions.

```
\new Staff <<
  \new Voice \with {
    \consists "Ambitus_engraver"
  } \relative c' {
    \override Ambitus.X-offset = #2.0
    \voiceOne
    c4 a d e
    f1
  }
  \new Voice \with {
    \consists "Ambitus_engraver"
  } \relative c' {
    \voiceTwo
    es4 f g as
    b1
  }
>>
```



Adding an extra staff at a line break

When adding a new staff at a line break, some extra space is unfortunately added at the end of the line before the break (to fit in a key signature change, which will never be printed anyway). The workaround is to add a setting of `Staff.explicitKeySignatureVisibility` as is shown in the example.

```
\score {
  \new StaffGroup \relative c' {
    \new Staff
    \key f \major
    c1 c^"Unwanted extra space" \break
    << { c1 | c }
    \new Staff {
      \key f \major
      \once \omit Staff.TimeSignature
      c1 | c
    }
  }
>>
c1 | c^"Fixed here" \break
<< { c1 | c }
\new Staff {
  \once \set Staff.explicitKeySignatureVisibility = #end-of-line-invisible
```

```

\key f \major
\once \omit Staff.TimeSignature
c1 | c
}
>>
}
}

```

The image contains three musical staves. The first staff shows two measures of music with a key signature of one flat. The second measure has an extra space after the first note, labeled "Unwanted extra space". The third staff shows four measures of music with a key signature of one flat. The fourth measure has an extra space after the first note, labeled "Fixed here". The fifth staff shows two measures of music with a key signature of one flat. The second measure has an extra space after the first note.

Adding an extra staff


An extra staff can be added (possibly temporarily) after the start of a piece.

```

\score {
  <<
  \new Staff \relative c' {
    c1 | c | c | c | c
  }
  \new StaffGroup \relative c' {
    \new Staff {
      c1 | c
      <<
      {
        c1 | d
      }
      \new Staff {
        \once \omit Staff.TimeSignature
        c1 | b
      }
    }
    >>
    c1
  }
}

```

}



Adding indicators to staves which get split after a break

This snippet defines the `\splitStaffBarLine` command, which adds arrows in north-east and south-east directions at a bar line, to denote that several voices sharing a staff will each continue on a staff of their own in the next system.

```
#(define-markup-command (arrow-at-angle layout props angle-deg length fill)
  (number? number? boolean?)
  (let* (
    ;; PI-OVER-180 and degrees->radians are taken from flag-styles.scm
    (PI-OVER-180 (/ (atan 1 1) 45))
    (degrees->radians (lambda (degrees) (* degrees PI-OVER-180)))
    (angle-rad (degrees->radians angle-deg))
    (target-x (* length (cos angle-rad)))
    (target-y (* length (sin angle-rad))))
  (interpret-markup layout props
    (markup
      #:translate (cons (/ target-x 2) (/ target-y 2)))
      #:rotate angle-deg
      #:translate (cons (/ length -2) 0)
      #:concat (#:draw-line (cons length 0)
        #:arrow-head X RIGHT fill)))))

splitStaffBarLineMarkup = \markup \with-dimensions #'(0 . 0) #'(0 . 0) {
  \combine
  \arrow-at-angle #45 #(sqrt 8) ##f
  \arrow-at-angle #-45 #(sqrt 8) ##f
}

splitStaffBarLine = {
  \once \override Staff.BarLine.stencil =
  #(\lambda (grob)
    (ly:stencil-combine-at-edge
      (ly:bar-line::print grob)
      X RIGHT
      (grob-interpret-markup grob splitStaffBarLineMarkup)
      0))
  \break
}
```

```
\paper {
    ragged-right = ##t
    short-indent = 5\mm
}

\score {
    <<
    \new ChoirStaff <<
        \new Staff \with { instrumentName = #"High I + II" } {
            <<
                \repeat unfold 4 f''1
                \\
                \repeat unfold 4 d''1
            >>
            \splitStaffBarLine
        }
        \new Staff \with { instrumentName = #"Low" } {
            <<
                \repeat unfold 4 b'1
                \\
                \repeat unfold 4 g'1
            >>
        }
    >>
}

\new Staff \with { shortInstrumentName = #"H I" } {
    R1*4
    \repeat unfold 2 { r4 f''2 r4 } \repeat unfold 2 e''1
}
\new Staff \with { shortInstrumentName = #"H II" } {
    R1*4
    \repeat unfold 4 b'2 \repeat unfold 2 c''1
}
\new Staff \with { shortInstrumentName = #"L" } {
    R1*4
    <<
        \repeat unfold 4 g'1
        \\
        \repeat unfold 4 c'1
    >>
}
>>
>>
\layout {
    \context {
        \Staff \RemoveEmptyStaves
        \override VerticalAxisGroup.remove-first = ##t
    }
}
```

Adding orchestral cues to a vocal score

This shows one approach to simplify adding many orchestral cues to the piano reduction in a vocal score. The music function \cueWhile takes four arguments: the music from which the cue is to be taken, as defined by \addQuote, the name to be inserted before the cue notes, then either #UP or #DOWN to specify either \voiceOne with the name above the staff or \voiceTwo with the name below the staff, and finally the piano music in parallel with which the cue notes are to appear. The name of the cued instrument is positioned to the left of the cued notes. Many passages can be cued, but they cannot overlap each other in time.

```

cueWhile =
#(define-music-function
  (parser location instrument name dir music)
  (string? string? ly:dir? ly:music?))
#{
  \cueDuring $instrument #dir {
    \once \override TextScript.self-alignment-X = #RIGHT
    \once \override TextScript.direction = $dir
    <>-\markup { \tiny #name }
    $music
  }
#})
}

flute = \relative c'' {
  \transposition c'
  s4 s4 e g
}
\addQuote "flute" { \flute }

clarinet = \relative c' {
  \transposition bes
  fis4 d d c
}
\addQuote "clarinet" { \clarinet }

singer = \relative c'' { c4. g8 g4 bes4 }
words = \lyricmode { here's the lyr -- ics }

```

```

pianoRH = \relative c' {
    \transposition c'
    \cueWhile "clarinet" "Clar." #DOWN { c4. g8 }
    \cueWhile "flute" "Flute" #UP { g4 bes4 }
}
pianoLH = \relative c { c4 <c' e> e, <g c> }

\score {
    <<
        \new Staff {
            \new Voice = "singer" {
                \singer
            }
        }
        \new Lyrics {
            \lyricsto "singer"
            \words
        }
        \new PianoStaff <<
            \new Staff {
                \new Voice {
                    \pianoRH
                }
            }
            \new Staff {
                \clef "bass"
                \pianoLH
            }
        >>
    >>
}

```

The musical score consists of two staves. The top staff is for the piano right hand (pianoRH), featuring a melody and lyrics: "here's the lyr-ics". The bottom staff is for the piano left hand (pianoLH), showing a bass line. A clarinet part (Clar.) is also included in the bass staff. The score is in common time, C major, and includes dynamic markings like forte and piano.

Adding timing marks to long glissandi

Skipped beats in very long glissandi are sometimes indicated by timing marks, often consisting of stems without noteheads. Such stems can also be used to carry intermediate expression markings.

If the stems do not align well with the glissando, they may need to be repositioned slightly.
`glissandoSkipOn = {`

```
\override NoteColumn.glissando-skip = ##t
\hide NoteHead
\override NoteHead.no-ledgers = ##t
}

glissandoSkipOff = {
    \revert NoteColumn.glissando-skip
    \undo \hide NoteHead
    \revert NoteHead.no-ledgers
}

\relative c' {
    r8 f8\glissando
    \glissandoSkipOn
    f4 g a a8\noBeam
    \glissandoSkipOff
    a8

    r8 f8\glissando
    \glissandoSkipOn
    g4 a8
    \glissandoSkipOff
    a8 |

    r4 f\glissando \(
    \glissandoSkipOn
    a4\f \)
    \glissandoSkipOff
    b8!\! r |
}
}
```



Alternative bar numbering

Two alternative methods for bar numbering can be set, especially for when using repeated music.

```
\relative c'{
    \set Score.alternativeNumberingStyle = #'numbers
    \repeat volta 3 { c4 d e f | }

    \alternative {
        { c4 d e f | c2 d \break }
        { f4 g a b | f4 g a b | f2 a | \break }
        { c4 d e f | c2 d }
    }

    c1 \break
    \set Score.alternativeNumberingStyle = #'numbers-with-letters
    \repeat volta 3 { c,4 d e f | }

    \alternative {
        { c4 d e f | c2 d \break }
    }
}
```

```
{
  f4 g a b | f4 g a b | f2 a | \break
  { c4 d e f | c2 d }
}
c1
}
```

Centered measure numbers

Scores of large ensemble works often have bar numbers placed beneath the system, centered horizontally on the measure's extent. This snippet shows how the `Measure_counter_engraver` may be used to simulate this notational practice. Here, the engraver has been added to a `Dynamics` context.

```
\layout {
  \context {
    \Dynamics
    \consists #Measure_counter_engraver
    \override MeasureCounter.direction = #DOWN
    \override MeasureCounter.font-encoding = #'latin1
    \override MeasureCounter.font-shape = #'italic
    % to control the distance of the Dynamics context from the staff:
    \override VerticalAxisGroup.nonstaff-relatedstaff-spacing.padding = #2
  }
  \context {
    \Score
```

```


    \remove "Bar_number_engraver"
}

}

pattern = \repeat unfold 7 { c'4 d' e' f' }

\new StaffGroup <<
  \new Staff {
    \pattern
  }
  \new Staff {
    \pattern
  }
  \new Dynamics {
    \startMeasureCount
    s1*7
    \stopMeasureCount
  }
>>

```



Changing the number of lines in a staff

The number of lines in a staff may be changed by overriding the `StaffSymbol.line-count`.

```

upper = \relative c' {
  c4 d e f
}

lower = \relative c {
  \clef bass
  c4 b a g
}

\score {
  \context PianoStaff <<
    \new Staff {
      \upper
    }
    \new Staff {
      \override Staff.StaffSymbol.line-count = #4
      \lower
    }
  >>
}

```



Changing the staff size

Though the simplest way to resize staves is to use `#(set-global-staff-size xx)`, an individual staff's size can be changed by scaling the properties 'staff-space' and `fontSize`.

```
<<
  \new Staff {
    \relative c' {
      \dynamicDown
      c8\ff c c c c c c
    }
  }
  \new Staff \with {
    \fontSize = #-3
    \override StaffSymbol.staff-space = #(magstep -3)
  }
  \clef bass
  c8 c c c c\f c c c
>>
```



Creating blank staves


To create blank staves, generate empty measures then remove the `Bar_number_engraver` from the `Score` context, and the `Time_signature_engraver`, `Clef_engraver` and `Bar_engraver` from the `Staff` context.

```
#(set-global-staff-size 20)
```

```
\score {
  {
    \repeat unfold 12 { s1 \break }
  }
  \layout {
    indent = 0\in
    \context {
      \Staff
      \remove "Time_signature_engraver"
      \remove "Clef_engraver"
      \remove "Bar_engraver"
    }
    \context {
```

```
\Score
  \remove "Bar_number_engraver"
}
}
}


\paper {
  #(set-paper-size "letter")
  ragged-last-bottom = ##f
  line-width = 7.5\in
  left-margin = 0.5\in
  bottom-margin = 0.25\in
  top-margin = 0.25\in
}
```



Creating double-digit fingerings

Creating fingerings larger than 5 is possible.

```
\relative c' {
    c1-10
    c1-50
    c1-36
    c1-29
}
```



Cross staff stems

This snippet shows the use of the `Span_stem_engraver` and `\crossStaff` to connect stems across staves automatically. The stem length need not be specified, as the variable distance between noteheads and staves is calculated automatically.

```
\layout {
  \context {
    \PianoStaff
    \consists #Span_stem_engraver
  }
}

{
  \new PianoStaff <<
    \new Staff {
      <b d'>4 r d'16> e'8. g8 r!
      e'8 f' g'4 e'2
    }
    \new Staff {
      \clef bass
      \voiceOne
      \autoBeamOff
      \crossStaff { <e g>4 e, g16 a8. c8} d
      \autoBeamOn
      g8 f g4 c2
    }
  >>
}
```

Display bracket with only one staff in a system

If there is only one staff in one of the staff types `ChoirStaff` or `StaffGroup`, by default the bracket and the starting bar line will not be displayed. This can be changed by overriding `collapse-height` to set its value to be less than the number of staff lines in the staff.

Note that in contexts such as `PianoStaff` and `GrandStaff` where the systems begin with a brace instead of a bracket, another property has to be set, as shown on the second system in the example.

```
\score {
    \new StaffGroup <<
        % Must be lower than the actual number of staff lines
        \override StaffGroup.SystemStartBracket.collapse-height = #4
        \override Score.SystemStartBar.collapse-height = #4
        \new Staff {
            c'1
        }
    >>
}
\score {
    \new PianoStaff <<
        \override PianoStaff.SystemStartBrace.collapse-height = #4
        \override Score.SystemStartBar.collapse-height = #4
        \new Staff {
            c'1
        }
    >>
}
```



Extending glissandi across repeats

A glissando which extends into several `\alternative` blocks can be simulated by adding a hidden grace note with a glissando at the start of each `\alternative` block. The grace note should be at the same pitch as the note which starts the initial glissando. This is implemented here with a music function which takes the pitch of the grace note as its argument.

Note that in polyphonic music the grace note must be matched with corresponding grace notes in all other voices.

```
repeatGliss = #(define-music-function (parser location grace)
  (ly:pitch?)
  #{
      % the next two lines ensure the glissando is long enough
      % to be visible
      \once \override Glissando.springs-and-rods
      = #ly:spanner::set-spacing-rods
```

```


\once \override Glissando.minimum-length = #3.5
\once \hideNotes
\grace $grace \glissando
#})

\score {
  \relative c' {
    \repeat volta 3 { c4 d e f\glissando }
    \alternative {
      { g2 d }
      { \repeatGliss f g2 e }
      { \repeatGliss f e2 d }
    }
  }
}

music = \relative c' {
  \voiceOne
  \repeat volta 2 {
    g a b c\glissando
  }
  \alternative {
    { d1 }
    { \repeatGliss c e1 }
  }
}

\score {
  \new StaffGroup <<
    \new Staff <<
      \context Voice { \clef "G_8" \music }
    >>
    \new TabStaff <<
      \context TabVoice { \clef "moderntab" \music }
    >>
  >>
}

```



A tablature staff for a six-string guitar. The staff shows three measures. Measure 1 has notes at positions 0 and 2. Measure 2 has notes at positions 0, 1, and 3. Measure 3 has a note at position 0. The tablature includes strings A, D, G, B, and E. A 3/8 time signature is indicated. The strings are labeled A, D, G, B, and E from bottom to top.

Forcing measure width to adapt to MetronomeMark's width

By default, metronome marks do not influence horizontal spacing. This has one downside: when using compressed rests, some metronome marks may be too close and therefore are printed vertically stacked, as demonstrated in the first part of this example. This can be solved through a simple override, as shown in the second half of the example.

```
example = {
    \tempo "Allegro"
    R1*6
    \tempo "Rall."
    R1*2
    \tempo "A tempo"
    R1*8
}

{
    \compressFullBarRests

    \example

    R1
    R1

    \override Score.MetronomeMark.extra-spacing-width = #'(0 . 0)
    \example
}
```



Glissandi can skip grobs

NoteColumn grobs can be skipped over by glissandi.

```
\relative c' {
    a2 \glissando
    \once \override NoteColumn.glissando-skip = ##t
    f'''4 d,
}
```



How to print two rehearsal marks above and below the same barline (method 1)

This method prints two 'rehearsal marks', one on top of the other. It shifts the lower rehearsal mark below the staff and then adds padding above it in order to place the upper rehearsal mark above the staff.


By adjusting the extra-offset and baseline-skip values you can increase or decrease the overall space between the rehearsal mark and the staff.

Because nearly every type of glyph or string can be made to behave like a rehearsal mark it is possible to centre those above and below a bar line.

Adding the appropriate 'break visibility' as shown in snippet 1 will allow you to position two marks at the end of a line as well.

Note: Method 1 is less complex than Method 2 but does not really allow for fine tuning of placement of one of the rehearsal marks without affecting the other. It may also give some problems with vertical spacing, since using `extra-offset` does not change the bounding box of the mark from its original value.

```
\relative c'{
    c d e f |
    \once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
    \once \override Score.RehearsalMark.baseline-skip = #9
    \mark \markup \center-column { \circle 1 \box A }
    g f e d |
    \once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
    \once \override Score.RehearsalMark.baseline-skip = #9
    \mark \markup \center-column { \flat { \bold \small \italic Fine. } }
    g f e d |
    \once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
    \once \override Score.RehearsalMark.baseline-skip = #9
    \override Score.RehearsalMark.break-visibility = #begin-of-line-invisible
    \mark \markup \center-column { \fermata \box z }
}
```



How to print two rehearsal marks above and below the same barline (method 2)

This method prints two 'rehearsal marks' - one above the stave and one below, by creating two voices, adding the Rehearsal Mark engraver to each voice - without this no rehearsal mark is printed - and then placing each rehearsal mark UP and DOWN in each voice respectively.


This method (as opposed to method 1) is more complex, but allows for more flexibility, should it be needed to tweak each rehearsal mark independently of the other.

```
\score {
    \relative c'
    <<
    \new Staff {
        <<
        \new Voice \with {
            \consists Mark_engraver
            \consists "Staff_collecting_engraver"
        }
    }
}
```

```

{ c4 d e f
  \mark \markup { \box A }
  c4 d e f
}
\new Voice \with {
  \consists Mark_engraver
  \consists "Staff_collecting_engraver"
  \override RehearsalMark.direction = #DOWN
}
{s4 s s s
  \mark \markup { \circle 1 }
  s4 s s s
}
>>
}
>>
\layout {
  \context {
    \Score
    \remove "Mark_engraver"
    \remove "Staff_collecting_engraver"
  }
}
}

```



Incipit

Incipits can be added using the instrument name grob, but keeping separate the instrument name definition and the incipit definition.

```

incipit =
#(define-music-function (parser location incipit-music) (ly:music?))
#{{
  \once \override Staff.InstrumentName.self-alignment-X = #RIGHT
  \once \override Staff.InstrumentName.self-alignment-Y = ##f
  \once \override Staff.InstrumentName.padding = #0.3
  \once \override Staff.InstrumentName.stencil =
  #(lambda (grob)
    (let* ((instrument-name (ly:grob-property grob 'long-text)))
      (set! (ly:grob-property grob 'long-text)
            #{
              \markup
              \score
              {
                { \context MensuralStaff \with {
                  instrumentName = #instrument-name
                } $incipit-music
              }
            }
          )
        )
      )
    )
  )
}}
```

```

    \layout { $(ly:grob-layout grob)
      line-width = \indent
      indent =
      % primitive-eval is probably easiest for
      % escaping lexical closure and evaluating
      % everything respective to (current-module).
      #(primitive-eval
        '(or (false-if-exception (- indent incipit-width))
          (* 0.5 indent)))
      ragged-right = ##f
      ragged-last = ##f
      system-count = #1 }
    }
  #})
  (system-start-text::print grob)))
#})

%%%%%%%%%%%%%%%
global = {
  \set Score.skipBars = ##t
  \key g \major
  \time 4/4

  % the actual music
  \skip 1*8

  % let finis bar go through all staves
  \override Staff.BarLine.transparent = ##f

  % finis bar
  \bar "|."
}

discantusIncipit = <<
  \new MensuralVoice = "discantusIncipit" <<
  \repeat unfold 9 { s1 \noBreak }
  {
    \clef "neomensural-c1"
    \key f \major
    \time 2/2
    c''1.
  }
>>
  \new Lyrics \lyricsto discantusIncipit { IV- }
>>

discantusNotes = {
  \transpose c' c'' {
    \clef "treble"
    d'2. d'4 |
    b e' d'2 |
  }
}

```

```

c'4 e'4.( d'8 c' b |
a4) b a2 |
b4.( c'8 d'4) c'4 |
\once \hide NoteHead
c'1 |
b\breve |
}
}

discantusLyrics = \lyricmode {
Ju -- bi -- |
la -- te De -- |
o, om --
nis ter -- |
ra, __ om- |
"..." |
-us. |
}

altusIncipit = <<
\new MensuralVoice = "altusIncipit" <<
\repeat unfold 9 { s1 \noBreak }
{
  \clef "neomensural-c3"
  \key f \major
  \time 2/2
  r1 f'1.
}
>>
\new Lyrics \lyricsto altusIncipit { IV- }
>>

altusNotes = {
\transpose c' c'' {
  \clef "treble"
  % two measures
  r2 g2. e4 fis g |
  a2 g4 e |
  fis g4.( fis16 e fis4) |
  g1 |
  \once \hide NoteHead
  g1 |
  g\breve |
}
}

altusLyrics = \lyricmode {
% two measures
Ju -- bi -- la -- te |
De -- o, om -- |
nis ter -- ra, |
"..." |
}

```

```

-us. |
}

tenorIncipit = <<
\new MensuralVoice = "tenorIncipit" <<
\repeat unfold 9 { s1 \noBreak }
{
  \clef "neomensural-c4"
  \key f \major
  \time 2/2
  r\longa
  r\brev
  r1 c'1.
}
>>
\new Lyrics \lyricsto tenorIncipit { IV- }
>>

tenorNotes = {
  \transpose c' c' {
    \clef "treble_8"
    R1 |
    R1 |
    R1 |
    % two measures
    r2 d'2. d'4 b e' |
    \once \hide NoteHead
    e'1 |
    d'\brev |
  }
}

tenorLyrics = \lyricmode {
  % two measures
  Ju -- bi -- la -- te |
  "..." |
  -us.
}

bassusIncipit = <<
\new MensuralVoice = "bassusIncipit" <<
\repeat unfold 9 { s1 \noBreak }
{
  \clef "bass"
  \key f \major
  \time 2/2
  %% incipit
  r\maxima
  f1.
}
>>
\new Lyrics \lyricsto bassusIncipit { IV- }

```

```
>>

bassusNotes = {
    \transpose c' c' {
        \clef "bass"
        R1 |
        R1 |
        R1 |
        R1 |
        g2. e4 |
        \once \hide NoteHead
        e1 |
        g\breve |
    }
}

bassusLyrics = \lyricmode {
    Ju -- bi- |
    "..." |
    -us.
}

\score {
    <<
    \new StaffGroup = choirStaff <<
        \new Voice = "discantusNotes" <<
            \global
            \set Staff.instrumentName = #"Discantus"
            \incipit \discantusIncipit
            \discantusNotes
        >>
        \new Lyrics = "discantusLyrics" \lyricsto discantusNotes { \discantusLyrics }■
        \new Voice = "altusNotes" <<
            \global
            \set Staff.instrumentName = #"Altus"
            \incipit \altusIncipit
            \altusNotes
        >>
        \new Lyrics = "altusLyrics" \lyricsto altusNotes { \altusLyrics }
        \new Voice = "tenorNotes" <<
            \global
            \set Staff.instrumentName = #"Tenor"
            \incipit \tenorIncipit
            \tenorNotes
        >>
        \new Lyrics = "tenorLyrics" \lyricsto tenorNotes { \tenorLyrics }
        \new Voice = "bassusNotes" <<
            \global
            \set Staff.instrumentName = #"Bassus"
            \incipit \bassusIncipit
            \bassusNotes
    >>
}
```

```

\new Lyrics = "bassusLyrics" \lyricsto bassusNotes { \bassusLyrics }
>>
>>
\layout {
  \context {
    \Score
    %% no bar lines in staves or lyrics
    \hide BarLine
  }
  %% the next two instructions keep the lyrics between the bar lines
  \context {
    \Lyrics
    \consists "Bar_engraver"
    \consists "Separating_line_group_engraver"
  }
  \context {
    \Voice
    %% no slurs
    \hide Slur
    %% Comment in the below "\remove" command to allow line
    %% breaking also at those bar lines where a note overlaps
    %% into the next measure. The command is commented out in this
    %% short example score, but especially for large scores, you
    %% will typically yield better line breaking and thus improve
    %% overall spacing if you comment in the following command.
    %%\remove "Forbid_line_break_engraver"
  }
  indent = 6\cm
  incipit-width = 4\cm
}
}

```

Discantus

Altus

Tenor

Bassus

IV-

IV-

IV-

IV-

Ju - bi - la - te De -

Ju bi - la - te

3
 o, om - nis ter - ra, om- ... -us.
 De - o, om - nis ter - ra, ... -us.
 Ju - bi - la - te ... -us.

Inserting score fragments above a staff as markups

The `\markup` command is quite versatile. In this snippet, it contains a `\score` block instead of texts or marks.


```
tuning = \markup {
  \score {
    \new Staff \with { \remove "Time_signature_engraver" }
    {
      \clef bass
      <c, g, d g>1
    }
    \layout { ragged-right = ##t indent = 0\cm }
  }
}

\header {
  title = "Solo Cello Suites"
  subtitle = "Suite IV"
  subsubtitle = \markup { Originalstimmung: \raise #0.5 \tuning }
}

\layout { ragged-right = ##f }

\relative c' {
  \time 4/8
  \tuplet 3/2 { c8 d e } \tuplet 3/2 { c d e }
  \tuplet 3/2 { c8 d e } \tuplet 3/2 { c d e }
  g8 a g a
  g8 a g a
}
```






Letter tablature formatting

Tablature can be formatted using letters instead of numbers.

```
music = \relative c {
    c4 d e f
    g4 a b c
    d4 e f g
}

<<
\new Staff {
    \clef "G_8"
    \music
}
\new TabStaff \with {
    tablatureFormat = #fret-letter-tablature-format
}
{
    \music
}
>>
```




Making glissandi breakable

Setting the `breakable` property to `#t` in combination with `after-line-breaking` allows a glissando to break if it occurs at a line break:

```
glissandoSkipOn = {
    \override NoteColumn.glissando-skip = ##t
    \hide NoteHead
    \override NoteHead.no-ledgers = ##t
}

\relative c' {
    \override Glissando.breakable = ##t
    \override Glissando.after-line-breaking = ##t
    f1\glissando |
    \break
    a4 r2. |
    f1\glissando
    \once \glissandoSkipOn
    \break
    a2 a4 r4 |
}
```



Making some staff lines thicker than the others

For educational purposes, a staff line can be thickened (e.g., the middle line, or to emphasize the line of the G clef). This can be achieved by adding extra lines very close to the line that should be emphasized, using the `line-positions` property of the `StaffSymbol` object.

```
{
  \override Staff.StaffSymbol.line-positions =
    #'(-4 -2 -0.2 0 0.2 2 4)
  d'4 e' f' g'
}
```



Measure counter

This snippet provides a workaround for emitting measure counters using transparent percent repeats.

```
<<
\context Voice = "foo" {
  \clef bass
  c4 r g r
  c4 r g r
  c4 r g r
  c4 r g r
}
\context Voice = "foo" {
  \set countPercentRepeats = ##t
  \hide PercentRepeat
  \override PercentRepeatCounter.staff-padding = #1
  \repeat percent 4 { s1 }
}
>>
```




Mensurstriche layout (bar lines between the staves)

The mensurstriche-layout where the bar lines do not show on the staves but between staves can be achieved with a `StaffGroup` instead of a `ChoirStaff`. The bar line on staves is blanked out by setting the `transparent` property.

```
global = {
    \hide Staff.BarLine
    s1 s
    % the final bar line is not interrupted
    \undo \hide Staff.BarLine
    \bar "|."
}


\new StaffGroup \relative c' {
    <<
        \new Staff { << \global { c1 c } >> }
        \new Staff { << \global { c c } >> }
    >>
}
```



Nesting staves

The property `systemStartDelimiterHierarchy` can be used to make more complex nested staff groups. The command `\set StaffGroup.systemStartDelimiterHierarchy` takes an alphabetical list of the number of staves produced. Before each staff a system start delimiter can be given. It has to be enclosed in brackets and takes as much staves as the brackets enclose. Elements in the list can be omitted, but the first bracket takes always the complete number of staves. The possibilities are `SystemStartBar`, `SystemStartBracket`, `SystemStartBrace`, and `SystemStartSquare`.

```
\new StaffGroup
\relative c' <<
    \set StaffGroup.systemStartDelimiterHierarchy
        = #'( SystemStartSquare ( SystemStartBrace ( SystemStartBracket a
                                                ( SystemStartSquare b ) ) c ) d )
    \new Staff { c1 }
    \new Staff { c1 }
>>
```



Non-traditional key signatures

The commonly used `\key` command sets the `keySignature` property, in the `Staff` context.

To create non-standard key signatures, set this property directly. The format of this command is a list:

```
\set Staff.keySignature = #`(((octave . step) . alter) ((octave . step) . alter)
...) where, for each element in the list, octave specifies the octave (0 being the octave from middle C to the B above), step specifies the note within the octave (0 means C and 6 means B), and alter is ,SHARP ,FLAT ,DOUBLE-SHARP etc. (Note the leading comma.) The accidentals in the key signature will appear in the reverse order to that in which they are specified.
```

Alternatively, for each item in the list, using the more concise format `(step . alter)` specifies that the same alteration should hold in all octaves.

For microtonal scales where a “sharp” is not 100 cents, `alter` refers to the alteration as a proportion of a 200-cent whole tone.

Here is an example of a possible key signature for generating a whole-tone scale:

```
\relative c' {
\set Staff.keySignature = #`(((0 . 6) . ,FLAT)
((0 . 5) . ,FLAT)
((0 . 3) . ,SHARP))
c4 d e fis
aes4 bes c2
}
```



Numbering groups of measures

This snippet demonstrates the use of the `Measure_counter_engraver` to number groups of successive measures. Any stretch of measures may be numbered, whether consisting of repetitions or not.


The engraver must be added to the appropriate context. Here, a `Staff` context is used; another possibility is a `Dynamics` context.

The counter is begun with `\startMeasureCount` and ended with `\stopMeasureCount`. Numbering will start by default with 1, but this behavior may be modified by overriding the `count-from` property.

When a measure extends across a line break, the number will appear twice, the second time in parentheses.

```
\layout {
  \context {
    \Staff
    \consists #Measure_counter_engraver
  }
}

\new Staff {
  \startMeasureCount
  \repeat unfold 7 {
    c'4 d' e' f'
  }
  \stopMeasureCount
  \bar "| |"
  g'4 f' e' d'
  \override Staff.MeasureCounter.count-from = #2
  \startMeasureCount
  \repeat unfold 5 {
    g'4 f' e' d'
  }
  g'4 f'
  \bar ""
  \break
  e'4 d'
  \repeat unfold 7 {
    g'4 f' e' d'
  }
  \stopMeasureCount
}
```



Orchestra choir and piano template

This template demonstrates the use of nested `StaffGroup` and `GrandStaff` contexts to subgroup instruments of the same type together, and a way to use `\transpose` so that variables hold music for transposing instruments at concert pitch.

```
#(set-global-staff-size 17)
\paper {
    indent = 3.0\cm % space for instrumentName
    short-indent = 1.5\cm % space for shortInstrumentName
}

fluteMusic = \relative c' { \key g \major g'1 b }
% Pitches as written on a manuscript for Clarinet in A
% are transposed to concert pitch.
clarinetMusic = \transpose c' a
    \relative c'' { \key bes \major bes1 d }
trumpetMusic = \relative c { \key g \major g'''1 b }
% Key signature is often omitted for horns
hornMusic = \transpose c' f
    \relative c { d'1 fis }
percussionMusic = \relative c { \key g \major g1 b }
sopranoMusic = \relative c'' { \key g \major g'1 b }
sopranoLyrics = \lyricmode { Lyr -- ics }
altoIMusic = \relative c' { \key g \major g'1 b }
altoIIMusic = \relative c' { \key g \major g'1 b }
altoILyrics = \sopranoLyrics
altoIIILyrics = \lyricmode { Ah -- ah }
tenorMusic = \relative c' { \clef "treble_8" \key g \major g1 b }
tenorLyrics = \sopranoLyrics
pianoRHMusic = \relative c { \key g \major g'''1 b }
pianoLHMusic = \relative c { \clef bass \key g \major g1 b }
violinIMusic = \relative c' { \key g \major g'1 b }
violinIIMusic = \relative c' { \key g \major g'1 b }
violaMusic = \relative c { \clef alto \key g \major g'1 b }
celloMusic = \relative c { \clef bass \key g \major g1 b }
bassMusic = \relative c { \clef "bass_8" \key g \major g,1 b }

\score {
    <<
    \new StaffGroup = "StaffGroup_woodwinds" <<
    \new Staff = "Staff_flute" {
        \set Staff.instrumentName = #"Flute"
        % shortInstrumentName, midiInstrument, etc.
        % may be set here as well
        \fluteMusic
    }
    \new Staff = "Staff_clarinet" {
        \set Staff.instrumentName =
        \markup { \concat { "Clarinet in B" \flat } }
        % Declare that written Middle C in the music
        % to follow sounds a concert B flat, for
        % output using sounded pitches such as MIDI.
    }
}
```

```
\transposition bes
% Print music for a B-flat clarinet
\transpose bes c' \clarinetMusic
}

>>
\new StaffGroup = "StaffGroup_brass" <<
\new Staff = "Staff_hornI" {
\set Staff.instrumentName = #"Horn in F"
\transposition f
\transpose f c' \hornMusic
}
\new Staff = "Staff_trumpet" {
\set Staff.instrumentName = #"Trumpet in C"
\trumpetMusic
}
>>
\new RhythmicStaff = "RhythmicStaff_percussion" <<
\set RhythmicStaff.instrumentName = #"Percussion"
\percussionMusic
>>
\new PianoStaff <<
\set PianoStaff.instrumentName = #"Piano"
\new Staff { \pianoRHMusic }
\new Staff { \pianoLHMusic }
>>
\new ChoirStaff = "ChoirStaff_choir" <<
\new Staff = "Staff_soprano" {
\set Staff.instrumentName = #"Soprano"
\new Voice = "soprano"
\sopranoMusic
}
\new Lyrics \lyricsto "soprano" { \sopranoLyrics }
\new GrandStaff = "GrandStaff_altos"
\with { \accepts Lyrics } <<
\new Staff = "Staff_altoI" {
\set Staff.instrumentName = #"Alto I"
\new Voice = "altoI"
\altoIMusic
}
\new Lyrics \lyricsto "altoI" { \altoILyrics }
\new Staff = "Staff_altoII" {
\set Staff.instrumentName = #"Alto II"
\new Voice = "altoII"
\altoIIMusic
}
\new Lyrics \lyricsto "altoII" { \altoIILyrics }
>>
\new Staff = "Staff_tenor" {
\set Staff.instrumentName = #"Tenor"
\new Voice = "tenor"
\tenorMusic
}
```

```
\new Lyrics \lyricsto "tenor" { \tenorLyrics }
>>
\new StaffGroup = "StaffGroup_strings" <<
\new GrandStaff = "GrandStaff_violins" <<
\new Staff = "Staff_violinI" {
    \set Staff.instrumentName = #"Violin I"
    \violinIMusic
}
\new Staff = "Staff_violinII" {
    \set Staff.instrumentName = #"Violin II"
    \violinIIMusic
}
>>
\new Staff = "Staff_viola" {
    \set Staff.instrumentName = #"Viola"
    \violaMusic
}
\new Staff = "Staff_cello" {
    \set Staff.instrumentName = #"Cello"
    \celloMusic
}
\new Staff = "Staff_bass" {
    \set Staff.instrumentName = #"Double Bass"
    \bassMusic
}
>>
>>
\layout { }
}
```

Putting lyrics inside the staff

Lyrics can be moved vertically to place them inside the staff. The lyrics are moved with `\override LyricText.extra-offset = #'(0 . dy)` and there are similar commands to move the extenders and hyphens. The offset needed is established with trial and error.

<<

```
\new Staff <<
  \new Voice = "voc" \relative c' { \stemDown a bes c8 b c4 }
>>
\new Lyrics \with {
  \override LyricText.extra-offset = #'(0 . 8.6)
  \override LyricExtender.extra-offset = #'(0 . 8.6)
  \override LyricHyphen.extra-offset = #'(0 . 8.6)
} \lyricsto "voc" { La la -- la __ _ la }
```

>>

Quoting another voice with transposition

Quotations take into account the transposition of both source and target. In this example, all instruments play sounding middle C; the target is an instrument in F. The target part may be transposed using `\transpose`. In this case, the quoted pitches will stay unchanged.

```
\addQuote clarinet {
    \transposition bes
    \repeat unfold 8 { d'16 d' d'8 }

}

\addQuote sax {
    \transposition es'
    \repeat unfold 16 { a8 }
}

quoteTest = {
    % french horn
    \transposition f
    g'4
    << \quoteDuring #"clarinet" { \skip 4 } s4^"clar." >>
    << \quoteDuring #"sax" { \skip 4 } s4^"sax." >>
    g'4
}

{
    \set Staff.instrumentName =
        \markup {
            \center-column { Horn \line { in F } }
        }
    \quoteTest
    \transpose c' d' << \quoteTest s4_ "up a tone" >>
}
```



Quoting another voice

The `quotedEventTypes` property determines the music event types which should be quoted. The default value is (`note-event rest-event tie-event beam-event tuplet-span-event`), which means that only the notes, rests, ties, beams and tuplets of the quoted voice will appear in the `\quoteDuring` expression. In the following example, a 16th rest is not quoted since `rest-event` is not in `quotedEventTypes`.

For a list of event types, consult the “Music classes” section of the Internals Reference.

```
quoteMe = \relative c' {
    fis4 r16 a8.-> b4\ff c
}
\addQuote quoteMe \quoteMe

original = \relative c'' {
```

```

c8 d s2
\once \override NoteColumn.ignore-collision = ##t
es8 gis8
}

<<
\new Staff {
  \set Staff.instrumentName = #"quoteMe"
  \quoteMe
}
\new Staff {
  \set Staff.instrumentName = #"orig"
  \original
}
\new Staff \relative c' <<
  \set Staff.instrumentName = #"orig+quote"
  \set Staff.quotedEventTypes =
    #'(note-event articulation-event)
  \original
  \new Voice {
    s4
    \set fontSize = #-4
    \override Stem.length-fraction = #(magstep -4)
    \quoteDuring #"quoteMe" { \skip 2. }
  }
>>
>>

```

Removing the first empty line

The first empty staff can also be removed from the score by setting the `VerticalAxisGroup` property `remove-first`. This can be done globally inside the `\layout` block, or locally inside the specific staff that should be removed. In the latter case, you have to specify the context (`Staff` applies only to the current staff) in front of the property.

The lower staff of the second staff group is not removed, because the setting applies only to the specific staff inside of which it is written.





```
\layout {
  \context {
    \Staff \RemoveEmptyStaves
    % To use the setting globally, uncomment the following line:
    % \override VerticalAxisGroup.remove-first = ##t
```

```

    }
}

\new StaffGroup <<
  \new Staff \relative c' {
    e4 f g a \break
    c1
  }
  \new Staff {
    % To use the setting globally, comment this line,
    % uncomment the line in the \layout block above
    \override Staff.VerticalAxisGroup.remove-first = ##t
    R1 \break
    R
  }
>>
\new StaffGroup <<
  \new Staff \relative c' {
    e4 f g a \break
    c1
  }
  \new Staff {
    R1 \break
    R
  }
>>

```



Setting system separators

System separators can be inserted between systems. Any markup can be used, but `\slashSeparator` has been provided as a sensible default.

```
\paper {
    system-separator-markup = \slashSeparator
}

notes = \relative c' {
    c1 | c \break
    c1 | c \break
    c1 | c
}

\book {
    \score {
        \new GrandStaff <<
            \new Staff \notes
            \new Staff \notes
        >>
    }
}
```



Tick bar lines

'Tick' bar lines are often used in music where the bar line is used only for coordination and is not meant to imply any rhythmic stress.

```
\relative c' {
  \set Score.defaultBarType = #"""
  c4 d e f
  g4 f e d
  c4 d e f
  g4 f e d
  \bar "|."
}
```



Time signature in parentheses - method 3

Another way to put the time signature in parenthesis

```
\relative c'' {
  \override Staff.TimeSignature.stencil = #(lambda (grob)
    (parenthesize-stencil (ly:time-signature::print grob) 0.1 0.4 0.4 0.1 ))
  \time 2/4
  a4 b8 c
}
```



Time signature in parentheses

The time signature can be enclosed within parentheses.

```
\relative c'' {
  \override Staff.TimeSignature.stencil = #(lambda (grob)
    (bracketify-stencil (ly:time-signature::print grob) Y 0.1 0.2 0.1))
  \time 2/4
  a4 b8 c
}
```



Tweaking clef properties

The command `\clef "treble_8"` is equivalent to setting `clefGlyph`, `clefPosition` (which controls the vertical position of the clef), `middleCPosition` and `clefTransposition`. A clef is printed when any of the properties except `middleCPosition` are changed.

Note that changing the glyph, the position of the clef, or the octavation does not in itself change the position of subsequent notes on the staff: the position of middle C must also be specified to do this. In order to get key signatures on the correct staff lines, `middleCClefPosition`

must also be set. The positional parameters are relative to the staff center line, positive numbers displacing upwards, counting one for each line and space. The `clefTransposition` value would normally be set to 7, -7, 15 or -15, but other values are valid.

When a clef change takes place at a line break the new clef symbol is printed at both the end of the previous line and the beginning of the new line by default. If the warning clef at the end of the previous line is not required it can be suppressed by setting the `Staff` property `explicitClefVisibility` to the value `end-of-line-invisible`. The default behavior can be recovered with `\unset Staff.explicitClefVisibility`.

The following examples show the possibilities when setting these properties manually. On the first line, the manual changes preserve the standard relative positioning of clefs and notes, whereas on the second line, they do not.

```
\layout { ragged-right = ##t }
{
    % The default treble clef
    \key f \major
    c'1
    % The standard bass clef
    \set Staff.clefGlyph = #"clefs.F"
    \set Staff.clefPosition = #2
    \set Staff.middleCPosition = #6
    \set Staff.middleCClefPosition = #6
    \key g \major
    c'1
    % The baritone clef
    \set Staff.clefGlyph = #"clefs.C"
    \set Staff.clefPosition = #4
    \set Staff.middleCPosition = #4
    \set Staff.middleCClefPosition = #4
    \key f \major
    c'1
    % The standard choral tenor clef
    \set Staff.clefGlyph = #"clefs.G"
    \set Staff.clefPosition = #-2
    \set Staff.clefTransposition = #-7
    \set Staff.middleCPosition = #1
    \set Staff.middleCClefPosition = #1
    \key f \major
    c'1
    % A non-standard clef
    \set Staff.clefPosition = #0
    \set Staff.clefTransposition = #0
    \set Staff.middleCPosition = #-4
    \set Staff.middleCClefPosition = #-4
    \key g \major
    c'1 \break

    % The following clef changes do not preserve
    % the normal relationship between notes, key signatures
    % and clefs:
    \set Staff.clefGlyph = #"clefs.F"
```

```
\set Staff.clefPosition = #2
c'1
\set Staff.clefGlyph = #"clefs.G"
c'1
\set Staff.clefGlyph = #"clefs.C"
c'1
\set Staff.clefTransposition = #7
c'1
\set Staff.clefTransposition = #0
\set Staff.clefPosition = #0
c'1

% Return to the normal clef:
\set Staff.middleCPosition = #0
c'1
}
```

The musical score consists of two staves. The first staff begins with a bass clef (F), followed by a treble clef (G), then a bass clef (F) with a sharp sign, and finally a treble clef (G). The second staff begins with a bass clef (F) with a sharp sign, followed by a bass clef (F) with a sharp sign, then a bass clef (F) with a sharp sign, and finally a bass clef (F) with a sharp sign.

Use square bracket at the start of a staff group

The system start delimiter `SystemStartSquare` can be used by setting it explicitly in a `StaffGroup` or `ChoirStaff` context.

```
\score {
  \new StaffGroup { <<
    \set StaffGroup.systemStartDelimiter = #'SystemStartSquare
    \new Staff { c'4 d' e' f' }
    \new Staff { c'4 d' e' f' }
  >> }
}
```

The musical score consists of two staves. Both staves begin with a bass clef (F) and contain four quarter notes each.

Using autochange with more than one voice

Using autochange with more than one voice.

```
\score
{
  \new PianoStaff
```


```

<<
\new Staff = "up" {
  <<
    \set Timing.beamExceptions = #'()
    \set Timing.beatStructure = #'(4)
    \new Voice {
      \voiceOne
      \autochange
      \relative c' {
        g8 a b c d e f g
        g,,8 a b c d e f g
      }
    }

    \new Voice {
      \voiceTwo
      \autochange
      \relative c' {
        g8 a b c d e f g
        g,,8 a b c d e f g
      }
    }
  >>
}

\new Staff = "down" {
  \clef bass
}
>>
}

```



Vertical aligned StaffGroups without connecting SystemStartBar

This snippet shows how to achieve vertically aligned StaffGroups with a SystemStartBar for each StaffGroup, but without connecting them.

% by Thomas Morley

```
#(set-global-staff-size 18)
```

```
\paper {
  indent = 0
  ragged-right = ##f
  print-all-headers = ##t
```

```

}

\layout {
  \context {
    \Staff
    \consists "Mark_engraver"
    \override RehearsalMark.self-alignment-X = #LEFT
  }
  \context {
    \StaffGroup
    systemStartDelimiterHierarchy =
      #'(SystemStartBrace (SystemStartBracket a b))
  }
  \context {
    \Score
    \override SystemStartBrace.style = #'bar-line
    \omit SystemStartBar
    \override SystemStartBrace.padding = #-0.1
    \override SystemStartBrace.thickness = #1.6
    \remove "Mark_engraver"
    \override StaffGrouper.staffgroup-staff-spacing.basic-distance = #15
  }
}

```

%%% EXAMPLE

```

txt =
\lyricmode {
  Wer4 nur den lie -- ben Gott lässt wal2 -- ten4
  und4 hof -- fet auf ihn al -- le Zeit2.
}

% First StaffGroup "exercise"

eI =
\relative c' {
  \mark \markup {
    \bold Teacher:
    This is a simple setting of the choral. Please improve it.
  }
  \key a \minor
  \time 4/4
  \voiceOne

  \partial 4
  e4
  a b c b
  a b gis2
  e4\fermata g! g f
  e a a gis
  a2.\fermata
  \bar ":|."
}

```

```
}
```

```
eII =  
\relative c' {  
    \key a \minor  
    \time 4/4  
    \voiceTwo  
    \partial 4  
    c4  
    e e e gis  
    a f e2  
    b4 b d d  
    c c d d  
    c2.  
    \bar ":|."
```

```
}
```

```
eIII =  
\relative c' {  
    \key a \minor  
    \time 4/4  
    \clef bass  
    \voiceOne  
  
    \partial 4  
    a4  
    c b a b  
    c d b2  
    gis4 g g b  
    c a f e  
    e2.  
}
```

```
eIV =  
\relative c' {  
    \key a \minor  
    \time 4/4  
    \clef bass  
    \voiceTwo  
  
    \partial 4  
    a,4  
    a' gis a e  
    a, d e2  
    e,4\fermata e' b g  
    c f d e  
    a,2.\fermata  
    \bar ":|."
```

```
}
```

```
exercise =  
\new StaffGroup = "exercise"
```

```
<<

\new Staff
<<
    \new Voice \eI
    \new Voice \eII
>>

\new Lyrics \txt

\new Staff
<<
    \new Voice \eIII
    \new Voice \eIV
>>
>>

% Second StaffGroup "simple Bach"

sbI =
\relative c' {
    \mark \markup { \bold " Pupil:" Here's my version! }
    \key a \minor
    \time 4/4
    \voiceOne

    \partial 4
    e4
    a b c b
    a b gis2
    e4\fermata g! g f
    e a a gis
    a2.\fermata
    \bar ":|."

}

sbII =
\relative c' {
    \key a \minor
    \time 4/4
    \voiceTwo
    \partial 4
    c8 d
    e4 e e8 f g4
    f f e2
    b4 b8 c d4 d
    e8 d c4 b8 c d4
    c2.
    \bar ":|."

}

sbIII =
```

```
\relative c' {
    \key a \minor
    \time 4/4
    \clef bass
    \voiceOne

    \partial 4
    a8 b
    c4 b a b8 c
    d4 d8 c b2
    gis4 g g8 a b4
    b a8 g f4 e
    e2.
}

sbIV =
\relative c' {
    \key a \minor
    \time 4/4
    \clef bass
    \voiceTwo

    \partial 4
    a,4
    a' gis a e
    f8 e d4 e2
    e,4\f \ermata e' b a8 g
    c4 f8 e d4 e
    a,2.\f \ermata
    \bar ":| ."
}

simpleBach =
\new StaffGroup = "simple Bach"
<<

\new Staff
<<
    \new Voice \sbI
    \new Voice \sbII
>>

\new Lyrics \txt

\new Staff
<<
    \new Voice \sbIII
    \new Voice \sbIV
>>
>>

% Third StaffGroup "chromatic Bach"
```

```
cbI =
\relative c' {
    \mark \markup {
        \bold "Teacher:"
        \column {
            "Well, you simply copied and transposed a version of J.S.Bach." \blacksquare
            "Do you know this one?"
        }
    }
    \key a \minor
    \time 4/4
    \voiceOne

    \partial 4
    e4
    a b c b
    a b gis4. fis8
    e4\fermata g! g f
    e a a8 b gis4
    a2.\fermata
    \bar ":"| .
}

cbII =
\relative c' {
    \key a \minor
    \time 4/4
    \voiceTwo
    \partial 4
    c8 d
    e4 e e8 fis gis4
    a8 g! f!4 e2
    b4 e e d
    d8[ cis] d dis e fis e4
    e2.
    \bar ":"| .
}

cbIII =
\relative c' {
    \key a \minor
    \time 4/4
    \clef bass
    \voiceOne

    \partial 4
    a8 b
    c[ b] a gis8 a4 d,
    e8[ e'] d c b4. a8
    gis4 b c d8 c
    b[ a] a b c b b c16 d
```

```

c2.

}

cbIV =
\relative c' {
    \key a \minor
    \time 4/4
    \clef bass
    \voiceTwo

    \partial 4
    a4
    c, e a, b
    c d e2
    e4\fermata e a b8 c
    gis[ g] fis f e dis e4
    a,2.\fermata
    \bar ":"|."
}

chromaticBach =
\new StaffGroup = "chromatic Bach"
<<

\new Staff
<<
    \new Voice \cbI
    \new Voice \cbII
>>

\new Lyrics \txt

\new Staff
<<
    \new Voice \cbIII
    \new Voice \cbIV
>>
>>

% Score

\score {
    <<
        \exercise
        \simpleBach
        \chromaticBach
    >>
    \header {
        title = \markup
            \column {
                \combine \null \vspace #1
}

```

```

    "Exercise: Improve the given choral"
    "
}

\layout {
    \context {
        \Lyrics
        \override LyricText.X-offset = #-1
    }
}
}

```

Exercise: Improve the given choral

Teacher: This is a simple setting of the choral. Please improve it.

A musical score for two voices (Soprano and Bass) in common time. The key signature is common (no sharps or flats). The soprano part consists of quarter notes, while the bass part consists of half notes. The lyrics are written below the notes. The melody is simple, with the soprano entering on the first beat and the bass on the second beat of each measure.

Soprano lyrics: Wer nur den lieben

Bass lyrics: Gott lässt wal -

Pupil: Here's my version!

A musical score for two voices (Soprano and Bass) in common time. The key signature is common (no sharps or flats). The soprano part features eighth-note patterns, while the bass part remains with half notes. The pupil has added grace notes and slurs to the original melody.

Soprano lyrics: Wer nur den lieben

Bass lyrics: Gott lässt wal -

Teacher: Well, you simply copied and transposed a version of J.S.Bach.
Do you know this one?

A musical score for two voices (Soprano and Bass) in common time. The key signature is common (no sharps or flats). The soprano part features eighth-note patterns, while the bass part remains with half notes. The teacher's version includes more complex rhythmic patterns and dynamics compared to the pupil's version.

Soprano lyrics: Wer nur den lieben

Bass lyrics: Gott lässt wal -


The image displays three staves of musical notation, each consisting of a treble clef staff and a bass clef staff. The lyrics are: "ten und hof - fet auf ihn al - le Zeit".

- Staff 1:** Shows simple quarter note chords. The vocal part has a single note per syllable.
- Staff 2:** Shows eighth-note chords. The vocal part uses eighth-note patterns like (up, down) or (down, up).
- Staff 3:** Shows sixteenth-note chords. The vocal part uses sixteenth-note patterns like (up, down, up, down) or (down, up, down, up).

Volta below chords

By adding the `Volta_engraver` to the relevant staff, volta can be put under chords.

```
\score {
  <<
  \chords {
    c1
    c1
  }
  \new Staff \with {
    \consists "Volta_engraver"
  }
  {
    \repeat volta 2 { c'1 }
    \alternative { c' }
  }
  >>
  \layout {
    \context {
      \Score
      \remove "Volta_engraver"
    }
  }
}
```



Volta multi staff

By adding the `Volta_engraver` to the relevant staff, volta can be put over staves other than the topmost one in a score.

```

voltaMusic = \relative c'' {
  \repeat volta 2 {
    c1
  }
  \alternative {
    d1
    e1
  }
}

<<
\new StaffGroup <<
  \new Staff \voltaMusic
  \new Staff \voltaMusic
>>
\new StaffGroup <<
  \new Staff \with { \consists "Volta_engraver" }
    \voltaMusic
  \new Staff \voltaMusic
>>
>>

```

Editorial annotations

Section “Editorial annotations” in *Notation Reference*

Adding fingerings to a score

Fingering instructions can be entered using a simple syntax.

```
\relative c' {
    c4-1 d-2 f-4 e-3
}
```



Adding links to objects

To add a link to a grob-stencil you could use `add-link` as defined here. Works with `\override` and `\tweak`. Drawback: `point-and-click` will be disturbed for the linked grobs.

Limitation: Works for PDF only.

The linked objects are colored with a separate command.

```
% Code by Thomas Morley
% Contributed by harm6
% Tested with 2.14.2 up to 2.17.9

#(define (add-link url-strg)
  (lambda (grob)
    (let* ((stil (ly:grob-property grob 'stencil)))
      (if (ly:stencil? stil)
          (begin
            (let* (
                  (x-ext (ly:stencil-extent stil X))
                  (y-ext (ly:stencil-extent stil Y))
                  (url-expr (list 'url-link url-strg `(quote ,x-ext) `(quote ,y-ext)))
                  (new-stil (ly:stencil-add (ly:make-stencil url-expr x-ext y-ext) stil)))
              (ly:grob-set-property! grob 'stencil new-stil)))
            #f))))
  %%% test

urlI =
"http://lilypond.org/doc/v2.14/Documentation/notation/writing-pitches"

urlII =
"http://lilypond.org/doc/v2.14/Documentation/notation/rhythms"

urlIII =
"http://lilypond.org/doc/v2.14/Documentation/notation/note-heads"

urlIV =
"http://lilypond.org/doc/v2.14/Documentation/notation/beams"
```

```

urlV =
"http://lilypond.org/doc/v2.14/Documentation/notation/note-head-styles"

\relative c' {
  \key cis \minor

  \once \override Staff.Clef.color = #green
  \once \override Staff.Clef.after-line-breaking =
    #(add-link urlI)

  \once \override Staff.TimeSignature.color = #green
  \once \override Staff.TimeSignature.after-line-breaking =
    #(add-link urlII)

  \once \override NoteHead.color = #green
  \once \override NoteHead.after-line-breaking =
    #(add-link urlIII)

  cis'1
  \once \override Beam.color = #green
  \once \override Beam.after-line-breaking =
    #(add-link urlIV)
  cis8 dis e fis gis2
  <gis,
  % With 2.17.9 you could use the command below to address the Accidental.
  % \tweak Accidental.before-line-breaking #(add-link url)
  \tweak color #green
  \tweak after-line-breaking #(add-link urlV)
  \tweak style #'harmonic
  bis
  dis
  fis
  >1
  <cis, cis' e>
}

```




Allowing fingerings to be printed inside the staff

By default, vertically oriented fingerings are positioned outside the staff. However, this behavior can be canceled. Note: you must use a chord construct `<>`, even if it is only a single note.

```

\relative c' {
  <c-1 e-2 g-3 b-5>2
  \override Fingerering.staff-padding = #'()
  <c-1 e-2 g-3 b-5>4 <g'-0>
}

```



Alternative bar numbering

Two alternative methods for bar numbering can be set, especially for when using repeated music.

```
\relative c'{
  \set Score.alternativeNumberingStyle = #'numbers
  \repeat volta 3 { c4 d e f | }
  \alternative {
    { c4 d e f | c2 d \break }
    { f4 g a b | f4 g a b | f2 a | \break }
    { c4 d e f | c2 d }
  }
  c1 \break
  \set Score.alternativeNumberingStyle = #'numbers-with-letters
  \repeat volta 3 { c,4 d e f | }
  \alternative {
    { c4 d e f | c2 d \break }
    { f4 g a b | f4 g a b | f2 a | \break }
    { c4 d e f | c2 d }
  }
  c1
}
```

Analysis brackets above the staff

Simple horizontal analysis brackets are added below the staff by default. The following example shows a way to place them above the staff instead.

```
\layout {
  \context {
    \Voice
    \consists "Horizontal_bracket_engraver"
  }
}
\relative c' {
  \once \override HorizontalBracket.direction = #UP
  c2\startGroup
  d2\stopGroup
}
```



Applying note head styles depending on the step of the scale

The `shapeNoteStyles` property can be used to define various note head styles for each step of the scale (as set by the key signature or the `tonic` property). This property requires a set of symbols, which can be purely arbitrary (geometrical expressions such as `triangle`, `cross`, and `xcircle` are allowed) or based on old American engraving tradition (some latin note names are also allowed).

That said, to imitate old American song books, there are several predefined note head styles available through shortcut commands such as `\aikenHeads` or `\sacredHarpHeads`.

This example shows different ways to obtain shape note heads, and demonstrates the ability to transpose a melody without losing the correspondence between harmonic functions and note head styles.

```
fragment = {
  \key c \major
  c2 d
  e2 f
  g2 a
  b2 c
}

\new Staff {
  \transpose c d
  \relative c' {
    \set shapeNoteStyles = ##(do re mi fa
                           #f la ti)
    \fragment
  }
  \break

  \relative c' {
    \set shapeNoteStyles = ##(cross triangle fa #f
```

```

mensural xcircle diamond)
\fragment
}
}

5



A musical staff in common time with a key signature of two sharps. It contains several notes: a quarter note, a half note, a whole note, a dotted half note, a dotted quarter note, a sixteenth note, and a sixteenth note with a stem pointing up. The stems are oriented in different directions relative to the note heads.


```

Avoiding collisions with chord fingerings

Fingerings and string numbers applied to individual notes will automatically avoid beams and stems, but this is not true by default for fingerings and string numbers applied to the individual notes of chords. The following example shows how this default behavior can be overridden.


```

\relative c' {
    \set fingeringOrientations = #'(up)
    \set stringNumberOrientations = #'(up)
    \set strokeFingerOrientations = #'(up)

    % Default behavior
    r8
    <f c'-'5>8
    <f c'\5>8
    <f c'-'rightHandFinger #2 >8

    % Corrected to avoid collisions
    r8
    \override Fingering.add-stem-support = ##t
    <f c'-'5>8
    \override StringNumber.add-stem-support = ##t
    <f c'\5>8
    \override StrokeFinger.add-stem-support = ##t
    <f c'-'rightHandFinger #2 >8
}

```



Blanking staff lines using the \whiteout command


The `\whiteout` command underlays a markup with a white box. Since staff lines are in a lower layer than most other grobs, this white box will not overlap any other grob.

```

\layout { ragged-right = ##f }
\relative c' {
    \override TextScript.extra-offset = #'(2 . 4)
    c2-\markup { \whiteout \pad-markup #0.5 "middle C" } c
}

```

}




Changing a single note's size in a chord

Individual note heads in a chord can be modified with the `\tweak` command inside a chord, by altering the `font-size` property.

Inside the chord (within the brackets `< >`), before the note to be altered, place the `\tweak` command, followed by `#'font-size` and define the proper size like `#-2` (a tiny note head).

```
\relative c' {
  <\tweak font-size #-2 c e g c \tweak font-size #2 e>1^{\markup { A tiny e }}_ {\markup { A big e }}
```



Changing the appearance of a slur from solid to dotted or dashed

The appearance of slurs may be changed from solid to dotted or dashed.

```
\relative c' {
  c4( d e c)
  \slurDotted
  c4( d e c)
  \slurSolid
  c4( d e c)
  \slurDashed
  c4( d e c)
  \slurSolid
  c4( d e c)
}
```



Coloring notes depending on their pitch

It is possible to color note heads depending on their pitch and/or their names: the function used in this example even makes it possible to distinguish enharmonics.

```
%Association list of pitches to colors.
#define color-mapping
(list
 (cons (ly:make-pitch 0 0 NATURAL) (x11-color 'red))
 (cons (ly:make-pitch 0 0 SHARP) (x11-color 'green)))
```

```

  (cons (ly:make-pitch 0 1 FLAT) (x11-color 'green))
  (cons (ly:make-pitch 0 2 NATURAL) (x11-color 'red))
  (cons (ly:make-pitch 0 2 SHARP) (x11-color 'green))
  (cons (ly:make-pitch 0 3 FLAT) (x11-color 'red))
  (cons (ly:make-pitch 0 3 NATURAL) (x11-color 'green))
  (cons (ly:make-pitch 0 4 SHARP) (x11-color 'red))
  (cons (ly:make-pitch 0 5 NATURAL) (x11-color 'green))
  (cons (ly:make-pitch 0 5 FLAT) (x11-color 'red))
  (cons (ly:make-pitch 0 6 SHARP) (x11-color 'red))
  (cons (ly:make-pitch 0 1 NATURAL) (x11-color 'blue))
  (cons (ly:make-pitch 0 3 SHARP) (x11-color 'blue))
  (cons (ly:make-pitch 0 4 FLAT) (x11-color 'blue))
  (cons (ly:make-pitch 0 5 SHARP) (x11-color 'blue))
  (cons (ly:make-pitch 0 6 FLAT) (x11-color 'blue)))))

%Compare pitch and alteration (not octave).
(define (pitch>equals? p1 p2)
  (and
    (= (ly:pitch-alteration p1) (ly:pitch-alteration p2))
    (= (ly:pitch-notename p1) (ly:pitch-notename p2)))))

(define (pitch-to-color pitch)
  (let ((color (assoc pitch color-mapping pitch>equals?)))
    (if color
        (cdr color)))))

(define (color-notehead grob)
  (pitch-to-color
    (ly:event-property (event-cause grob) 'pitch)))

\score {
  \new Staff \relative c' {
    \override NoteHead.color = #color-notehead
    c8 b d dis ees f g aes
  }
}

```



Controlling the placement of chord fingerings


The placement of fingering numbers can be controlled precisely. For fingering orientation to apply, you must use a chord construct `<>` even if it is a single note.

```

\relative c' {
  \set fingeringOrientations = #'(left)
  <c-1 e-3 a-5>4
  \set fingeringOrientations = #'(down)
  <c-1 e-3 a-5>4
  \set fingeringOrientations = #'(down right up)
  <c-1 e-3 a-5>4
}

```

```
\set fingeringOrientations = #'(up)
<c-1 e-3 a-5>4
\set fingeringOrientations = #'(left)
<c-1>2
\set fingeringOrientations = #'(down)
<e-3>2
}
```



Creating a delayed turn

Creating a delayed turn, where the lower note of the turn uses the accidental, requires several overrides. The `outside-staff-priority` property must be set to `#f`, as otherwise this would take precedence over the `avoid-slur` property. Changing the fractions $2/3$ and $1/3$ adjusts the horizontal position.

```
\relative c' {
  c2*2/3 ( s2*1/3\turn d4) r
  <<
  { c4.( d8) }
  { s4 s\turn }
  >>
  \transpose c d \relative c' <<
  { c4.( d8) }
  {
    s4
    \once \set suggestAccidentals = ##t
    \once \override AccidentalSuggestion #'outside-staff-priority = ##f
    \once \override AccidentalSuggestion #'avoid-slur = #'inside
    \once \override AccidentalSuggestion #'font-size = #-3
    \once \override AccidentalSuggestion #'script-priority = #-1
    \single \hideNotes
    b8-\turn \noBeam
    s8
  }
  >>
}
```



Creating blank staves


To create blank staves, generate empty measures then remove the `Bar_number_engraver` from the `Score` context, and the `Time_signature_engraver`, `Clef_engraver` and `Bar_engraver` from the `Staff` context.

```
#(set-global-staff-size 20)

\score {
    {
        \repeat unfold 12 { s1 \break }
    }
    \layout {
        indent = 0\in
        \context {
            \Staff
            \remove "Time_signature_engraver"
            \remove "Clef_engraver"
            \remove "Bar_engraver"
        }
        \context {
            \Score
            \remove "Bar_number_engraver"
        }
    }
}

\paper {
    #(set-paper-size "letter")
    ragged-last-bottom = ##f
    line-width = 7.5\in
    left-margin = 0.5\in
    bottom-margin = 0.25\in
    top-margin = 0.25\in
}
```






Creating double-digit fingerings

Creating fingerings larger than 5 is possible.

```
\relative c' {
    c1-10
    c1-50
    c1-36
    c1-29
}
```



Default direction of stems on the center line of the staff

The default direction of stems on the center line of the staff is set by the `Stem.neutral-direction`.

```
\relative c'' {
    a4 b c b
    \override Stem.neutral-direction = #up
    a4 b c b
    \override Stem.neutral-direction = #down
    a4 b c b
}
```



Drawing boxes around grobs

The `print`-function can be overridden to draw a box around an arbitrary grob.

```
\relative c'' {
    \override TextScript.stencil =
        #(make-stencil-boxer 0.1 0.3 ly:text-interface::print)
    c'4^"foo"

    \override Stem.stencil =
        #(make-stencil-boxer 0.05 0.25 ly:stem::print)
    \override Score.RehearsalMark.stencil =
```


```

#(make-stencil-boxer 0.15 0.3 ly:text-interface::print)
b8

\revert Stem.stencil

\revert Flag.stencil
c4. c4
\mark "F"
c1
}

```



Drawing circles around note heads

Here is how to circle a note.

```

circle =
\once \override NoteHead.stencil = #(lambda (grob)
  (let* ((note (ly:note-head::print grob))
         (combo-stencil (ly:stencil-add
                           note
                           (circle-stencil note 0.1 0.8))))
    (ly:make-stencil (ly:stencil-expr combo-stencil)
                     (ly:stencil-extent note X)
                     (ly:stencil-extent note Y)))
  )
{ \circle c' }

```



Drawing circles around various objects

The `\circle` markup command draws circles around various objects, for example fingering indications. For other objects, specific tweaks may be required: this example demonstrates two strategies for rehearsal marks and measure numbers.


```

\relative c' {
  c1
  \set Score.markFormatter =
  #(lambda (mark context)
      (make-circle-markup (format-mark-numbers mark context)))
  \mark \default

  c2 d^ \markup {
    \override #'(thickness . 3) {
      \circle \finger 2
    }
  }
}

```

```
\override Score.BarNumber.break-visibility = #all-visible
\override Score.BarNumber.stencil =
  #(make-stencil-circler 0.1 0.25 ly:text-interface::print)
}
```



Embedding native PostScript in a \markup block

PostScript code can be directly inserted inside a \markup block.

```
% PostScript is a registered trademark of Adobe Systems Inc.
```

```
\relative c' {
  a4-\markup { \postscript #"(3 4 moveto 5 3 rlineto stroke" }
  -\markup { \postscript #"( 0 1 ] 0 setdash 3 5 moveto 5 -3 rlineto stroke " }

  b4-\markup { \postscript #"(3 4 moveto 0 0 1 2 8 4 20 3.5 rcurveto stroke" }
  s2
  a'1
}
```



Grid lines: changing their appearance

The appearance of grid lines can be changed by overriding some of their properties.

```
\score {
  \new ChoirStaff <-
    \new Staff {
      \relative c' {
        \stemUp
        c'4. d8 e8 f g4
      }
    }
    \new Staff {
      \relative c {
        % this moves them up one staff space from the default position
        \override Score.GridLine.extra-offset = #'(0.0 . 1.0)
        \stemDown
        \clef bass
        \once \override Score.GridLine.thickness = #5.0
        c4
        \once \override Score.GridLine.thickness = #1.0
        g'4
        \once \override Score.GridLine.thickness = #3.0
        f4
        \once \override Score.GridLine.thickness = #5.0
      }
    }
}
```

```

    e4
}
}
>>
\layout {
  \context {
    \Staff
    % set up grids
    \consists "Grid_point_engraver"
    % set the grid interval to one quarter note
    gridInterval = #(ly:make-moment 1/4)
  }
  \context {
    \Score
    \consists "Grid_line_span_engraver"
    % this moves them to the right half a staff space
    \override NoteColumn.X-offset = #-0.5
  }
}
}
}

```



Grid lines: emphasizing rhythms and notes synchronization

Regular vertical lines can be drawn between staves to show note synchronization; however, in case of monophonic music, you may want to make the second stave invisible, and make the lines shorter like in this snippet.

```


\score {
  \new ChoirStaff {
    \relative c' <-
    \new Staff {
      \time 12/8
      \stemUp
      c4. d8 e8 f g4 f8 e8. d16 c8
    }
    \new Staff {
      % hides staff and notes so that only the grid lines are visible
      \hideNotes
      \hide Staff.BarLine
      \override Staff.StaffSymbol.line-count = #0
      \hide Staff.TimeSignature
      \hide Staff.Clef
      % dummy notes to force regular note spacing
    }
  }
}

```

```

\once \override Score.GridLine.thickness = #4.0
c8 c c
\once \override Score.GridLine.thickness = #3.0
c8 c c
\once \override Score.GridLine.thickness = #4.0
c8 c c
\once \override Score.GridLine.thickness = #3.0
c8 c c
}
>>
}
\layout {
  \context {
    \Score
    \consists "Grid_line_span_engraver"
    % center grid lines horizontally below note heads
    \override NoteColumn.X-offset = #-0.5
  }
  \context {
    \Staff
    \consists "Grid_point_engraver"
    gridInterval = #(ly:make-moment 1/8)
    % set line length and positioning:
    % two staff spaces above center line on hidden staff
    % to four spaces below center line on visible staff
    \override GridPoint.Y-extent = #'(2 . -4)
  }
  ragged-right = ##t
}
}

```




Hammer on and pull off using chords

When using hammer-on or pull-off with chorded notes, only a single arc is drawn. However ‘double arcs’ are possible by setting the `doubleSlurs` property to `#t`.

```

\new TabStaff {
  \relative c' {
    % chord hammer-on and pull-off
    \set doubleSlurs = ##t
    <g' b>8( <a c> <g b>
  }
}


```



Hammer on and pull off using voices

The arc of hammer-on and pull-off is upwards in voices one and three and downwards in voices two and four:


```
\new TabStaff {
    \relative c' {
        << { \voiceOne g2( a) }
        \\ { \voiceTwo a,( b) }
        >> \oneVoice
    }
}
```



Hammer on and pull off

Hammer-on and pull-off can be obtained using slurs.

```
\new TabStaff {
    \relative c' {
        d4( e\2)
        a( g)
    }
}
```



How to print two rehearsal marks above and below the same barline (method 1)

This method prints two 'rehearsal marks', one on top of the other. It shifts the lower rehearsal mark below the staff and then adds padding above it in order to place the upper rehearsal mark above the staff.

By adjusting the extra-offset and baseline-skip values you can increase or decrease the overall space between the rehearsal mark and the staff.

Because nearly every type of glyph or string can be made to behave like a rehearsal mark it is possible to centre those above and below a bar line.

Adding the appropriate 'break visibility' as shown in snippet 1 will allow you to position two marks at the end of a line as well.

Note: Method 1 is less complex than Method 2 but does not really allow for fine tuning of placement of one of the rehearsal marks without affecting the other. It may also give some problems with vertical spacing, since using `extra-offset` does not change the bounding box of the mark from its original value.

```
\relative c'{
    c d e f |
```

```
\once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
\once \override Score.RehearsalMark.baseline-skip = #9
\mark \markup \center-column { \circle 1 \box A }
g f e d |
\once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
\once \override Score.RehearsalMark.baseline-skip = #9
\mark \markup \center-column { \flat { \bold \small \italic Fine. } }
g f e d |
\once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
\once \override Score.RehearsalMark.baseline-skip = #9
\override Score.RehearsalMark.break-visibility = #begin-of-line-invisible
\mark \markup \center-column { \fermata \box z }
}
```



How to print two rehearsal marks above and below the same barline (method 2)

This method prints two 'rehearsal marks' - one above the stave and one below, by creating two voices, adding the Rehearsal Mark engraver to each voice - without this no rehearsal mark is printed - and then placing each rehearsal mark UP and DOWN in each voice respectively.


This method (as opposed to method 1) is more complex, but allows for more flexibility, should it be needed to tweak each rehearsal mark independently of the other.

```
\score {
  \relative c'
  <<
  \new Staff {
    <<
    \new Voice \with {
      \consists Mark_engraver
      \consists "Staff_collecting_engraver"
    }
    { c4 d e f
      \mark \markup { \box A }
      c4 d e f
    }
    \new Voice \with {
      \consists Mark_engraver
      \consists "Staff_collecting_engraver"
      \override RehearsalMark.direction = #DOWN
    }
    { s4 s s s
      \mark \markup { \circle 1 }
      s4 s s s
    }
  }
}
```

```

    >>
}
>>
\layout {
  \context {
    \Score
    \remove "Mark_engraver"
    \remove "Staff_collecting_engraver"
  }
}
}

```



Making some staff lines thicker than the others

For educational purposes, a staff line can be thickened (e.g., the middle line, or to emphasize the line of the G clef). This can be achieved by adding extra lines very close to the line that should be emphasized, using the `line-positions` property of the `StaffSymbol` object.

```
{
  \override Staff.StaffSymbol.line-positions =
    #'(-4 -2 -0.2 0 0.2 2 4)
  d'4 e' f' g'
}
```



Marking notes of spoken parts with a cross on the stem

This example shows how to put crosses on stems. Mark the beginning of a spoken section with the `\speakOn` keyword, and end it with the `\speakOff` keyword.

```

\speakOn = {
  \override Stem.stencil =
  #(\lambda (grob)
    (let* ((x-parent (ly:grob-parent grob X))
           (is-rest? (ly:grob? (ly:grob-object x-parent 'rest))))
      (if is-rest?
          empty-stencil
          (ly:stencil-combine-at-edge
            (ly:stem::print grob)
            Y
            (- (ly:grob-property grob 'direction))
            (grob-interpret-markup grob
              (markup #:center-align #:fontsize -4
                     #:musicglyph "noteheads.s2cross"))
              -2.3))))
}

```

```

}

speakOff = {
    \revert Stem.stencil
    \revert Flag.stencil
}

\score {
    \new Staff {
        \relative c' {
            a4 b a c
            \speakOn
            g4 f r g
            b4 r d e
            \speakOff
            c4 a g f
        }
    }
}

```



Measure counter

This snippet provides a workaround for emitting measure counters using transparent percent repeats.

```

<<
\context Voice = "foo" {
    \clef bass
    c4 r g r
    c4 r g r
    c4 r g r
    c4 r g r
}
\context Voice = "foo" {
    \set countPercentRepeats = ##t
    \hide PercentRepeat
    \override PercentRepeatCounter.staff-padding = #1
    \repeat percent 4 { s1 }
}
>>

```



Numbering groups of measures

This snippet demonstrates the use of the `Measure_counter_engraver` to number groups of successive measures. Any stretch of measures may be numbered, whether consisting of repetitions or not.

The engraver must be added to the appropriate context. Here, a `Staff` context is used; another possibility is a `Dynamics` context.

The counter is begun with `\startMeasureCount` and ended with `\stopMeasureCount`. Numbering will start by default with 1, but this behavior may be modified by overriding the `count-from` property.

When a measure extends across a line break, the number will appear twice, the second time in parentheses.

```
\layout {
  \context {
    \Staff
    \consists #Measure_counter_engraver
  }
}


\new Staff {
  \startMeasureCount
  \repeat unfold 7 {
    c'4 d' e' f'
  }
  \stopMeasureCount
  \bar "||"
  g'4 f' e' d'
  \override Staff.MeasureCounter.count-from = #2
  \startMeasureCount
  \repeat unfold 5 {
    g'4 f' e' d'
  }
  g'4 f'
  \bar ""
  \break
  e'4 d'
  \repeat unfold 7 {
    g'4 f' e' d'
  }
  \stopMeasureCount
}
```



Positioning fingering indications precisely

Generally the options available for positioning the fingering of chords work well by default, but if one of the indications needs to positioned more precisely the following tweak may be used. This is particularly useful for correcting the positioning when intervals of a second are involved.

```
\relative c' {
    \set fingeringOrientations = #'(left)
    <c-1 d-2 a'-5>4
    <c-1 d-\tweak extra-offset #'(0 . 0.7)-2 a'-5>4
    \set fingeringOrientations = #'(down)
    <c-1 d-2 a'-5>4
    <c-1 d-\tweak extra-offset #'(-1.2 . 0)-2 a'-5>4
    \set fingeringOrientations = #'(down right up)
    <c-1 d-2 a'-5>4
    <c-1 d-\tweak extra-offset #'(-1 . 1.2)-2 a'-5>4
    \set fingeringOrientations = #'(up)
    <c-1 d-2 a'-5>4
    <c-1 d-\tweak extra-offset #'(-1.2 . 0)-2 a'-5>4
}
```



Positioning text markups inside slurs

Text markups need to have the `outside-staff-priority` property set to false in order to be printed inside slurs.


```
\relative c'' {
    \override TextScript.avoid-slur = #'inside
    \override TextScript.outside-staff-priority = ##f
    c2(^\markup { \halign #-10 \natural } d4.) c8
}
```



Printing text from right to left

It is possible to print text from right to left in a markup object, as demonstrated here.

```
{
  b1^\markup {
    \line { i n g i r u m i m u s n o c t e }
  }
  f'_-\markup {
    \override #'(text-direction . -1)
    \line { i n g i r u m i m u s n o c t e }
  }
}
```




String number extender lines

Make an extender line for string number indications, showing that a series of notes is supposed to be played all on the same string.

```
stringNumberSpanner =
#(define-music-function (parser location StringNumber) (string?))
#{
  \override TextSpanner.style = #'solid
  \override TextSpanner.font-size = #-5
  \override TextSpanner.bound-details.left.stencil-align-dir-y = #CENTER
  \override TextSpanner.bound-details.left.text = \markup { \circle \number #StringNumber
#})

\relative c {
  \clef "treble_8"
  \stringNumberSpanner "5"
  \textSpannerDown
  a8\startTextSpan
  b c d e f\stopTextSpan
  \stringNumberSpanner "4"
  g\startTextSpan a
  bes4 a g2\stopTextSpan
}
```



Using PostScript to generate special note head shapes

When a note head with a special shape cannot easily be generated with graphic markup, PostScript code can be used to generate the shape. This example shows how a parallelogram-shaped note head is generated.

```
parallelogram =
#(ly:make-stencil (list 'embedded-ps
  "gsave
  currentpoint translate
  newpath
  0 0.25 moveto
  1.3125 0.75 lineto
  1.3125 -0.25 lineto
  0 -0.75 lineto
  closepath
  fill
  grestore" )
  (cons 0 1.3125)
  (cons -.75 .75))
```

```

myNoteHeads = \override NoteHead.stencil = \parallelogram
normalNoteHeads = \revert NoteHead.stencil

\relative c' {
  \myNoteHeads
  g4 d'
  \normalNoteHeads
  <f, \tweak stencil \parallelogram b e>4 d
}

```



Using the whiteout property

Any graphical object can be printed over a white background to mask parts of objects that lie beneath. This can be useful to improve the appearance of collisions in complex situations when repositioning objects is impractical. It is necessary to explicitly set the `layer` property to control which objects are masked by the white background.

In this example the collision of the tie with the time signature is improved by masking out the part of the tie that crosses the time signature by setting the `whiteout` property of `TimeSignature`. To do this `TimeSignature` is moved to a layer above `Tie`, which is left in the default layer of 1, and `StaffSymbol` is moved to a layer above `TimeSignature` so it is not masked.

```

{
  \override Score.StaffSymbol.layer = #4
  \override Staff.TimeSignature.layer = #3
  b'2 b'~
  \once \override Staff.TimeSignature.whiteout = ##t
  \time 3/4
  b' r4
}

```



Text

Section “Text” in *Notation Reference*

Adding the current date to a score

With a little Scheme code, the current date can easily be added to a score.

```
% first, define a variable to hold the formatted date:  
date = #(strftme "%d-%m-%Y" (localtime (current-time)))  
  
% use it in the title block:  
\header {  
    title = "Including the date!"  
    subtitle = \date  
}  
  
\score {  
    \relative c' {  
        c4 c c c  
    }  
}  
% and use it in a \markup block:  
\markup {  
    \date  
}
```

Including the date!

17-03-2014



17-03-2014

Adjusting lyrics vertical spacing

This snippet shows how to bring the lyrics line closer to the staff.

```
% Default layout:  
<<  
    \new Staff \new Voice = melody \relative c' {  
        c4 d e f  
        g4 f e d  
        c1  
    }  
    \new Lyrics \lyricsto melody { aa aa aa aa aa aa aa aa }  
  
    \new Staff {  
        \new Voice = melody \relative c' {  
            c4 d e f  
            g4 f e d
```

```

    c1
}
}

% Reducing the minimum space below the staff and above the lyrics:
\new Lyrics \with {
  \override VerticalAxisGroup.nonstaff-relatedstaff-spacing = #'((basic-distance . 1))■
}
\lyricsto melody { aa aa aa aa aa aa aa aa }

>>

```



Aligning and centering instrument names

The horizontal alignment of instrument names is tweaked by changing the `Staff.InstrumentName #'self-alignment-X` property. The `\layout` variables `indent` and `short-indent` define the space in which the instrument names are aligned before the first and the following systems, respectively.



```

\paper {
  left-margin = 3\cm
}

\score {
  \new StaffGroup <<
  \new Staff {
    \override Staff.InstrumentName.self-alignment-X = #LEFT
    \set Staff.instrumentName = \markup \left-column {
      "Left aligned"
      "instrument name"
    }
    \set Staff.shortInstrumentName = #"Left"
    c''1
    \break
    c''1
  }
  \new Staff {
    \override Staff.InstrumentName.self-alignment-X = #CENTER
    \set Staff.instrumentName = \markup \center-column {
      Centered
      "instrument name"
    }
    \set Staff.shortInstrumentName = #"Centered"
    g'1
    g'1
  }
  \new Staff {

```

```
\override Staff.InstrumentName.self-alignment-X = #RIGHT
\set Staff.instrumentName = \markup \right-column {
  "Right aligned"
  "instrument name"
}
\set Staff.shortInstrumentName = #"Right"
e'1
e'1
}
>>
\layout {
  ragged-right = ##t
  indent = 4\cm
  short-indent = 2\cm
}
}
```



Aligning objects created with the \mark command

By default the \mark command centers objects over a bar line. This behavior can be modified to align at right or left.

```
\relative c' {
  c1 \mark "(Center)"
  c1
\once \override Score.RehearsalMark.self-alignment-X = #LEFT
\mark "(Left)"
c4 c c c
c4 c c c
\once \override Score.RehearsalMark.self-alignment-X = #RIGHT
\mark "(Right)"
```

```
c1
}
```

Aligning syllables with melisma


By default, lyrics syllables that start a melisma are left aligned on their note. The alignment can be altered using the `lyricMelismaAlignment` property.

```
\score {
<<
  \new Staff {
    \relative c' {
      \new Voice = "vocal" {
        c d^~\markup default d e
        c d^~\markup "right aligned" d e
        c d^~\markup "center aligned" d e
        c d^~\markup "reset to default" d e
      }
    }
  \new Lyrics \lyricsto "vocal" \lyricmode {
    word word word
    \set lyricMelismaAlignment = #RIGHT
    word word word
    \set lyricMelismaAlignment = #CENTER
    word word word
    \unset lyricMelismaAlignment
    word word word
  }
>>
}
```

Blanking staff lines using the \whiteout command

The `\whiteout` command underlays a markup with a white box. Since staff lines are in a lower layer than most other grobs, this white box will not overlap any other grob.

```
\layout { ragged-right = ##f }
\relative c' {
  \override TextScript.extra-offset = #'(2 . 4)
  c2-\markup { \whiteout \pad-markup #0.5 "middle C" } c
}
```



Center text below hairpin dynamics

This example provides a function to typeset a hairpin (de)crescendo with some additional text below it, such as “molto” or “poco”. The added text will change the direction according to the direction of the hairpin. The Hairpin is aligned to DynamicText.

The example also illustrates how to modify the way an object is normally printed, using some Scheme code.

```

hairpinWithCenteredText =
#(define-music-function (parser location text) (markup?))
#{
  \once \override Voice.Hairpin.after-line-breaking =
  #(\lambda (grob)
    (let* ((stencil (ly:hairpin::print grob))
           (par-y (ly:grob-parent grob Y))
           (dir (ly:grob-property par-y 'direction))
           (new-stencil (ly:stencil-aligned-to
                         (ly:stencil-combine-at-edge
                           (ly:stencil-aligned-to stencil X CENTER)
                           Y dir
                           (ly:stencil-aligned-to (grob-interpret-markup grob text) X CENTER))■
                         X LEFT)))
      (staff-space (ly:output-def-lookup (ly:grob-layout grob) 'staff-space))■
      (staff-line-thickness
        (ly:output-def-lookup (ly:grob-layout grob) 'line-thickness))
      (grob-name (lambda (x) (assq-ref (ly:grob-property x 'meta) 'name)))
      (par-x (ly:grob-parent grob X))
      (dyn-text (eq? (grob-name par-x) 'DynamicText ))
      (dyn-text-stencil-x-length
        (if dyn-text
            (interval-length
              (ly:stencil-extent (ly:grob-property par-x 'stencil) X))
            0))
      (x-shift
        (if dyn-text
            (-
              (+ staff-space dyn-text-stencil-x-length)
              (* 0.5 staff-line-thickness)) 0)))
    (ly:grob-set-property! grob 'Y-offset 0)
    (ly:grob-set-property! grob 'stencil
      (ly:stencil-translate-axis
        new-stencil
        x-shift X))))
#}

hairpinMolto =
\hairpinWithCenteredText \markup { \italic molto }

hairpinMore =

```

```
\hairpinWithCenteredText \markup { \larger moltissimo }

\layout { ragged-right = ##f }

\relative c' {
  \hairpinMolto
  c2< c\f
  \hairpinMore
  c2\ppppp< c\f
  \break
  \hairpinMolto
  c2^< c\f
  \hairpinMore
  c2\ppppp< c\f
}
}
```

The image shows a musical score with two staves. The top staff begins with a note followed by a hairpin labeled "molto" and a forte dynamic "f". The bottom staff begins with a note followed by a hairpin labeled "ppppp" and a hairpin labeled "moltissimo" with a forte dynamic "f". Measure numbers "1" and "3" are positioned above the staves.

Centering markup on note heads automatically

For technical reasons, text scripts attached to note heads cannot easily be centered on a note head's width, unlike articulations.

Instead of using trial-and-error offset tweaks, this snippet uses a Scheme engraver to reset the horizontal parent of each markup to a `NoteColumn`. This also allows text to follow note heads which have been shifted via `force-hshift`.

```
#:define (Text_align_engraver ctx)
  (let ((scripts '()))
    (note-column #f))
  (make-engraver
    (acknowledgers
      ((note-column-interface trans grob source)
       ;; cache NoteColumn in this Voice context
       (set! note-column grob))
      ((text-script-interface trans grob source)
       ;; whenever a TextScript is acknowledged,
       ;; add it to `scripts' list
       (set! scripts (cons grob scripts))))
    ((stop-translation-timestep trans)
     ;; if any TextScript grobs exist,
     ;; set NoteColumn as X-parent
     (for-each (lambda (script)
```


```

        (set! (ly:grob-parent script X) note-column)
        scripts)
;; clear scripts ready for next timestep
(set! scripts '()))))

\layout {
\context {
\Voice
\consists #Text_align_engraver
\override TextScript.X-offset =
#ly:self-alignment-interface::aligned-on-x-parent
\override TextScript.self-alignment-X = #CENTER
}
}

\new Staff <-
\relative c' {
\override NoteColumn.force-hshift = #3
c1-\markup { \arrow-head #Y #DOWN ##t }
}
\\
\relative c' {
a4 a-\markup { \huge ^ } a a
}
>>

```



Changing the default text font family

The default font families for text can be overridden with `make-pango-font-tree`.

```
\relative c' {
  c4^\markup {
    roman: foo \bold bla \italic bar \italic \bold baz
  }
  c'4_^\markup {
    \override #'(font-family . sans)
    {
      sans: foo \bold bla \italic bar \italic \bold baz
    }
  }
  c'2^\markup {
    \override #'(font-family . typewriter)
    {
      mono: foo \bold bla \italic bar \italic \bold baz
    }
  }
}
```

mono: foo **bla** *bar* **baz**
 roman: foo **bla** *bar* **baz**

sans: foo **bla** *bar* **baz**

Combining dynamics with markup texts

Some dynamics may involve text indications (such as “più forte” or “piano subito”). These can be produced using a `\markup` block.

```
piuF = \markup { \italic più \dynamic f }
\layout { ragged-right = ##f }
\relative c' {
  c2\f c-\piuF
}
```

Combining two parts on the same staff

The part combiner tool (`\partcombine` command) allows the combination of several different parts on the same staff. Text directions such as “solo” or “a2” are added by default; to remove them, simply set the property `printPartCombineTexts` to `f`. For vocal scores (hymns), there is no need to add “solo/a2” texts, so they should be switched off. However, it might be better not to use it if there are any solos, as they won’t be indicated. In such cases, standard polyphonic notation may be preferable.

This snippet presents the three ways two parts can be printed on a same staff: standard polyphony, `\partcombine` without texts, and `\partcombine` with texts.

```

musicUp = \relative c' {
    \time 4/4
    a4 c4.( g8) a4 |
    g4 e' g,( a8 b) |
    c b a2.
}

musicDown = \relative c' {
    g4 e4.( d8) c4 |
    r2 g'4( f8 e) |
    d2 \stemDown a
}

\score {
    <<
    <<
    \new Staff {
        \set Staff.instrumentName = #"Standard polyphony"
        << \musicUp \\ \musicDown >>
    }
    \new Staff \with { printPartCombineTexts = ##f } {
        \set Staff.instrumentName = #"PartCombine without texts"
        \partcombine \musicUp \musicDown
    }
    \new Staff {
        \set Staff.instrumentName = #"PartCombine with texts"
        \partcombine \musicUp \musicDown
    }
    >>
}
>>
\layout {
    indent = 6.0\cm
    \context {
        \Score
        \override SystemStartBar.collapse-height = #30
    }
}
}

```

Standard polyphony

PartCombine without texts

PartCombine with texts

Creating "real" parenthesized dynamics

Although the easiest way to add parentheses to a dynamic mark is to use a \markup block, this method has a downside: the created objects will behave like text markups, and not like dynamics.

However, it is possible to create a similar object using the equivalent Scheme code (as described in the Notation Reference), combined with the `make-dynamic-script` function. This way, the markup will be regarded as a dynamic, and therefore will remain compatible with commands such as `\dynamicUp` or `\dynamicDown`.

```
paren =
#(define-event-function (parser location dyn) (ly:event?)
  (make-dynamic-script
    #{
      \markup \concat {
        \normal-text \italic \fontsize #2 (
          \pad-x #0.2 #(ly:music-property dyn 'text)
        \normal-text \italic \fontsize #2 )
      }
    #})))
\relative c' {
  c4\paren\f c c \dynamicUp c\paren\p
}
```



Creating simultaneous rehearsal marks

Unlike text scripts, rehearsal marks cannot be stacked at a particular point in a score: only one `RehearsalMark` object is created. Using an invisible measure and bar line, an extra rehearsal mark can be added, giving the appearance of two marks in the same column. This method may also prove useful for placing rehearsal marks at both the end of one system and the start of the following system.

```
{
  \key a \major
  \set Score.markFormatter = #format-mark-box-letters
  \once \override Score.RehearsalMark.outside-staff-priority = #5000
  \once \override Score.RehearsalMark.self-alignment-X = #LEFT
  \once \override Score.RehearsalMark.break-align-symbols = #'(key-signature)
  \mark \markup { \bold { Senza denti } }

  % the hidden measure and bar line
  % \cadenzaOn turns off automatic calculation of bar numbers
  \cadenzaOn
  \once \omit Score.TimeSignature
  \time 1/16
  s16 \bar ""
  \cadenzaOff
```

```
\time 4/4
\once \override Score.RehearsalMark.self-alignment-X = #LEFT
\mark \markup { \box \bold Intro }
d'1
\mark \default
d'1
}
```

Senza denti

Intro A

Creating text spanners

The `\startTextSpan` and `\stopTextSpan` commands allow the creation of text spanners as easily as pedal indications or octavations. Override some properties of the `TextSpanner` object to modify its output.

```
\paper { ragged-right = ##f }

\relative c' {
    \override TextSpanner.bound-details.left.text = #"bla"
    \override TextSpanner.bound-details.right.text = #"blu"
    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan


    \override TextSpanner.style = #'line
    \once \override TextSpanner.bound-details.left.stencil-align-dir-y = #CENTER
    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan

    \override TextSpanner.style = #'dashed-line
    \override TextSpanner.bound-details.left.text =
        \markup { \draw-line #'(0 . 1) }
    \override TextSpanner.bound-details.right.text =
        \markup { \draw-line #'(0 . -2) }
    \once \override TextSpanner.bound-details.right.padding = #-2

    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan

    \set Staff.middleCPosition = #-13
    \override TextSpanner.dash-period = #10
    \override TextSpanner.dash-fraction = #0.5
    \override TextSpanner.thickness = #10
    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan
```

}



Demonstrating all headers

All header fields with special meanings.


```
\header {
    copyright = "copyright"
    title = "title"
    subtitle = "subtitle"
    composer = "composer"
    arranger = "arranger"
    instrument = "instrument"
    metre = "metre"
    opus = "opus"
    piece = "piece"
    poet = "poet"
    texidoc = "All header fields with special meanings."
    copyright = "public domain"
    enteredby = "jcn"
    source = "urtext"
}

\layout {
    ragged-right = ##f
}


\score {
    \relative c' { c1 | c | c | c }
}

\score {
    \relative c' { c1 | c | c | c }
    \header {
        title = "localtitle"
        subtitle = "localsubtitle"
        composer = "localcomposer"
        arranger = "localarranger"
        instrument = "localinstrument"
        metre = "localmetre"
        opus = "localopus"
        piece = "localpiece"
        poet = "localpoet"
        copyright = "localcopyright"
    }
}
```

	title	
	subtitle	
poet	instrument	composer arranger
piece		opus



localpiece localopus



Embedding native PostScript in a \markup block

PostScript code can be directly inserted inside a \markup block.

% PostScript is a registered trademark of Adobe Systems Inc.

```
\relative c' {
  a4-\markup { \postscript #3 4 moveto 5 3 rlineto stroke" }
  -\markup { \postscript #"[ 0 1 ] 0 setdash 3 5 moveto 5 -3 rlineto stroke " }

  b4-\markup { \postscript #3 4 moveto 0 0 1 2 8 4 20 3.5 rcurveto stroke" }
  s2
  a'1
}
```




Formatting lyrics syllables

Markup mode may be used to format individual syllables in lyrics.

```
mel = \relative c' { c4 c c c }
lyr = \lyricmode {
  Lyrics \markup { \italic can } \markup { \with-color #red contain }
  \markup { \fontsize #8 \bold Markup! }
}

<<
  \new Voice = melody \mel
  \new Lyrics \lyricsto melody \lyr
>>
```



Lyrics *can contain* **Markup!**

How to put ties between syllables in lyrics

This can be achieved by separating those syllables by tildes.


```
\lyrics {
    wa~o~a
}
```

waoa

Lyrics alignment

Horizontal alignment for lyrics can be set by overriding the `self-alignment-X` property of the `LyricText` object. `#-1` is left, `#0` is center and `#1` is right; however, you can use `#LEFT`, `#CENTER` and `#RIGHT` as well.

```
\layout { ragged-right = ##f }
\relative c' {
    c1
    c1
    c1
}
\addlyrics {
    \once \override LyricText.self-alignment-X = #LEFT
    "This is left-aligned"
    \once \override LyricText.self-alignment-X = #CENTER
    "This is centered"
    \once \override LyricText.self-alignment-X = #1
    "This is right-aligned"
}
```



This is left-aligned This is centered This is right-aligned

Markup lines

Text that can spread over pages is entered with the `\markuplist` command.

```
%(set-default-paper-size "a6")

#(define-markup-list-command (paragraph layout props args) (markup-list?
  (interpret-markup-list layout props
    (make-justified-lines-markup-list (cons (make-hspace-markup 2) args)))))

% Candide, Voltaire
\markuplist {
  \override-lines #'(baseline-skip . 2.5) {
    \paragraph {
      Il y avait en Westphalie, dans le château de M. le baron de
      Thunder-ten-tronckh, un jeune garçon à qui la nature avait donné
      les mœurs les plus douces. Sa physionomie annonçait son âme.
      Il avait le jugement assez droit, avec l'esprit le plus simple ;
      c'est, je crois, pour cette raison qu'on le nommait Candide. Les
```

anciens domestiques de la maison soupçonnaient qu'il était fils de la sœur de monsieur le baron et d'un bon et honnête gentilhomme du voisinage, que cette demoiselle ne voulut jamais épouser parce qu'il n'avait pu prouver que soixante et onze quartiers, et que le reste de son arbre généalogique avait été perdu par l'injure du temps.

}

\paragraph {

Monsieur le baron était un des plus puissants seigneurs de la Westphalie, car son château avait une porte et des fenêtres. Sa grande salle même était ornée d'une tapisserie. Tous les chiens de ses basses-cours componaient une meute dans le besoin ; ses palefreniers étaient ses piqueurs; le vicaire du village était son grand-aumônier. Ils l'appelaient tous monseigneur, et ils riaient quand il faisait des contes.

}

}

}

Il y avait en Westphalie, dans le château de M. le baron de Thunder-ten-tronckh, un jeune garçon à qui la nature avait donné les mœurs les plus douces. Sa physionomie annonçait son âme. Il avait le jugement assez droit, avec l'esprit le plus simple ; c'est, je crois, pour cette raison qu'on le nommait Candide. Les anciens domestiques de la maison soupçonnaient qu'il était fils de la sœur de monsieur le baron et d'un bon et honnête gentilhomme du voisinage, que cette demoiselle ne voulut jamais épouser parce qu'il n'avait pu prouver que soixante et onze quartiers, et que le reste de son arbre généalogique avait été perdu par l'injure du temps.

Monsieur le baron était un des plus puissants

seigneurs de la Westphalie, car son château avait une

porte et des fenêtres. Sa grande salle même était

ornée d'une tapisserie. Tous les chiens de ses

basses-cours componaient une meute dans le besoin ;

ses palefreniers étaient ses piqueurs; le vicaire du

village était son grand-aumônier. Ils l'appelaient tous

monseigneur, et ils riaient quand il faisait des contes.

Multi-measure rest markup

Markups attached to a multi-measure rest will be centered above or below it. Long markups attached to multi-measure rests do not cause the measure to expand. To expand a multi-measure rest to fit the markup, use an empty chord with an attached markup before the multi-measure rest.

Text attached to a spacer rest in this way is left-aligned to the position where the note would be placed in the measure, but if the measure length is determined by the length of the text, the text will appear to be centered.


```
\relative c' {
  \compressFullBarRests
  \textLengthOn
  <>^markup { [MAJOR GENERAL] }
  R1*19
  <>_markup { \italic { Cue: ... it is yours } }
  <>^markup { A }
  R1*30^markup { [MABEL] }
  \textLengthOff
  c4^markup { CHORUS } d f c
}
```

Cue: ... it is yours

Ottava text

Internally, `\ottava` sets the properties `ottavation` (for example, to `8va` or `8vb`) and `middleCPosition`. To override the text of the bracket, set `ottavation` after invoking `\ottava`.

```
{
  \ottava #1
  \set Staff.ottavation = #"8"
  c''1
  \ottava #0
  c'1
  \ottava #1
  \set Staff.ottavation = #"Text"
  c''1
}
```



Outputting the version number

By putting the output of `lilypond-version` into a lyric, it is possible to print the version number of LilyPond in a score, or in a document generated with `lilypond-book`. Another possibility is to append the version number to the doc-string, in this manner:

```
\score {
  \new Lyrics {
    \override Score.RehearsalMark.self-alignment-X = #LEFT
    \mark #(string-append "Processed with LilyPond version " (lilypond-version))
    s2
  }
}
```

Processed with LilyPond version 2.18.2

Piano template with centered lyrics

Instead of having a full staff for the melody and lyrics, lyrics can be centered between the staves of a piano staff.

```
upper = \relative c'' {
  \clef treble
  \key c \major
  \time 4/4

  a4 b c d
}

lower = \relative c {
  \clef bass
  \key c \major
  \time 4/4

  a2 c
}
```

```

}

text = \lyricmode {
  Aaa Bee Cee Dee
}

\score {
  \new GrandStaff <<
    \new Staff = upper { \new Voice = "singer" \upper }
    \new Lyrics \lyricsto "singer" \text
    \new Staff = lower { \lower }
  >>
  \layout {
    \context {
      \GrandStaff
      \accepts "Lyrics"
    }
    \context {
      \Lyrics
      \consists "Bar_engraver"
    }
  }
  \midi { }
}

```



Printing marks at the end of a line


Marks can be printed at the end of the current line, instead of the beginning of the following line. In such cases, it might be preferable to align the right end of the mark with the bar line.

```

\relative c' {
  g2 c
  d,2 a'
  \once \override Score.RehearsalMark.break-visibility = #end-of-line-visible
  \once \override Score.RehearsalMark.self-alignment-X = #RIGHT
  \mark "D.C. al Fine"
  \break
  g2 b,
  c1 \bar "||"
}

```






Printing marks on every staff

Although text marks are normally only printed above the topmost staff, they may also be printed on every staff.


```
\score {
  <<
    \new Staff { c''1 \mark "molto" c'' }
    \new Staff { c'1 \mark "molto" c' }
  >>
  \layout {
    \context {
      \Score
      \remove "Mark_engraver"
      \remove "Staff_collecting_engraver"
    }
    \context {
      \Staff
      \consists "Mark_engraver"
      \consists "Staff_collecting_engraver"
    }
  }
}
```



Printing text from right to left

It is possible to print text from right to left in a markup object, as demonstrated here.

```
{
  b1^\markup {
    \line { i n g i r u m i m u s n o c t e }
  }
  f'_\markup {
    \override #'(text-direction . -1)
    \line { i n g i r u m i m u s n o c t e }
  }
}
```



Putting lyrics inside the staff

Lyrics can be moved vertically to place them inside the staff. The lyrics are moved with `\override LyricText.extra-offset = #'(0 . dy)` and there are similar commands to move the extenders and hyphens. The offset needed is established with trial and error.

```
<<
\new Staff <-
  \new Voice = "voc" \relative c' { \stemDown a bes c8 b c4 }
>>
\new Lyrics \with {
  \override LyricText.extra-offset = #'(0 . 8.6)
  \override LyricExtender.extra-offset = #'(0 . 8.6)
  \override LyricHyphen.extra-offset = #'(0 . 8.6)
} \lyricsto "voc" { La la -- la __ _ la }
>>
```



Stand-alone two-column markup

Stand-alone text may be arranged in several columns using `\markup` commands:

```
\markup {
  \fill-line {
    \hspace #1
    \column {
      \line { O sacrum convivium }
      \line { in quo Christus sumitur, }
      \line { recolitur memoria passionis ejus, }
      \line { mens impletur gratia, }
      \line { futurae gloriae nobis pignus datur. }
      \line { Amen. }
    }
    \hspace #2
    \column \italic {
      \line { O sacred feast }
      \line { in which Christ is received, }
      \line { the memory of His Passion is renewed, }
      \line { the mind is filled with grace, }
      \line { and a pledge of future glory is given to us. }
      \line { Amen. }
    }
    \hspace #1
  }
}
```

O sacrum convivium
 in quo Christus sumitur,
 recolitur memoria passionis ejus,
 mens impletur gratia,
 futurae gloriae nobis pignus datur.
 Amen.


*O sacred feast
 in which Christ is received,
 the memory of His Passion is renewed,
 the mind is filled with grace,
 and a pledge of future glory is given to us.
 Amen.*

String number extender lines

Make an extender line for string number indications, showing that a series of notes is supposed to be played all on the same string.

```
stringNumberSpanner =
#(define-music-function (parser location StringNumber) (string?))
#{
  \override TextSpanner.style = #'solid
  \override TextSpanner.font-size = #-5
  \override TextSpanner.bound-details.left.stencil-align-dir-y = #CENTER
  \override TextSpanner.bound-details.left.text = \markup { \circle \number #StringNumber
#})

\relative c {
  \clef "treble_8"
  \stringNumberSpanner "5"
  \textSpannerDown
  a8\startTextSpan
  b c d e f\stopTextSpan
  \stringNumberSpanner "4"
  g\startTextSpan a
  bes4 a g2\stopTextSpan
}
```



Three-sided box

This example shows how to add a markup command to get a three sided box around some text (or other markup).

```
% New command to add a three sided box, with sides north, west and south
% Based on the box-stencil command defined in scm/stencil.scm
% Note that ";" is used to comment a line in Scheme
#(define-public (NWS-box-stencil stencil thickness padding)
  "Add a box around STENCIL, producing a new stencil."
  (let* ((x-ext (interval-widen (ly:stencil-extent stencil X) padding))
         (y-ext (interval-widen (ly:stencil-extent stencil Y) padding))
         (y-rule (make-filled-box-stencil (cons 0 thickness) y-ext))
         (x-rule (make-filled-box-stencil
                  (interval-widen x-ext thickness) (cons 0 thickness)))))


  ;; (set! stencil (ly:stencil-combine-at-edge stencil X 1 y-rule padding))
  (set! stencil (ly:stencil-combine-at-edge stencil X LEFT y-rule padding))
  (set! stencil (ly:stencil-combine-at-edge stencil Y UP x-rule 0.0)))
```

```
(set! stencil (ly:stencil-combine-at-edge stencil Y DOWN x-rule 0.0))
stencil))

% The corresponding markup command, based on the \box command defined
% in scm/define-markup-commands.scm
#define-markup-command (NWS-box layout props arg) (markup?)
  "Draw a box round @var{arg}. Looks at @code{thickness},
@code{box-padding} and @code{font-size} properties to determine line
thickness and padding around the markup."
  (let* ((th (chain-assoc-get 'thickness props 0.1))
         (size (chain-assoc-get 'font-size props 0)))
         (pad (* (magstep size)
                  (chain-assoc-get 'box-padding props 0.2)))
         (m (interpret-markup layout props arg)))
    (NWS-box-stencil m th pad)))

% Test it:

\relative c' {
  c1^\markup { \NWS-box ABCD }
  c1^\markup { \NWS-box \note #"4" #1.0 }
}
```



UTF-8

Various scripts may be used for texts (like titles and lyrics) by entering them in UTF-8 encoding, and using a Pango based backend. Depending on the fonts installed, this fragment will render Bulgarian (Cyrillic), Hebrew, Japanese and Portuguese.

```
% end verbatim - this comment is a hack to prevent texinfo.tex
% from choking on non-European UTF-8 subsets
```

```
%% Edit this file using a Unicode aware editor, such as GVIM, GEDIT, Emacs
```

```
%{
```

You may have to install additional fonts.

Red Hat Fedora

```
taipeifonts fonts-xorg-truetype ttffonts-jp fonts-arabic \
ttffonts-zh_CN fonts-jp fonts-hebrew
```

Debian GNU/Linux

```
apt-get install emacs-intl-fonts xfonts-intl.* \
ttf-kochi-gothic ttf-kochi-mincho \
xfonts-bolkhov-75dpi xfonts-cronyx-100dpi xfonts-cronyx-75dpi
```

```
%}
```

```
% Cyrillic font
```

```
bulgarian = \lyricmode {
```

```
Жълтата дюля беше щастлива, че пухът, който цъфна, замръзна като гъон.
```

```
}
```

```
hebrew = \lyricmode {
```

```
.
```

```
japanese = \lyricmode {
```

```
}
```

```
% "a legal song to you"
```

```
portuguese = \lyricmode {
```

```
à vo -- cê uma can -- ção legal
```

```
}
```

```
\relative c' {
```

```
c2 d
```

```
e2 f
```

```
g2 f
```

```
e1
```

```
}
```

```
\addlyrics { \bulgarian }
```

```
\addlyrics { \hebrew }
```

```
\addlyrics { \japanese }
```

```
\addlyrics { \portuguese }
```

A musical staff in common time (C) with a treble clef. It consists of four measures. The first measure contains the lyrics "Жълтата" (Bulgarian), "dюля" (Hebrew), "беше" (Japanese), and "щастлива," (Portuguese). The second measure contains "п" (Bulgarian), "כִּיְ" (Hebrew), "салм" (Japanese), and "לשםוע" (Portuguese). The third measure contains "いろはにほへど" (Bulgarian), "ちりぬるを" (Hebrew), "わがよたれぞ" (Japanese), and "つねならむ" (Portuguese). The fourth measure contains "à" (Bulgarian), "vo" (Hebrew), "cê" (Japanese), and "uma" (Portuguese).

3

A continuation of the musical staff. The first measure contains the lyrics "че" (Bulgarian), "пухът," (Hebrew), and "който" (Japanese). The second measure contains "אי" (Bulgarian), "ונצח" (Hebrew), and "קרפָד" (Japanese). The third measure contains "うみのおくや" (Bulgarian), "まけふこえて" (Hebrew), and "あさきゆめみじ" (Japanese). The fourth measure contains "can" (Bulgarian), "ção" (Hebrew), and "legal" (Japanese).

Vocal ensemble template with lyrics aligned below and above the staves

This template is basically the same as the simple “Vocal ensemble” template, with the exception that here all the lyrics lines are placed using `alignAboveContext` and `alignBelowContext`.

```
global = {
    \key c \major
    \time 4/4
}

sopMusic = \relative c' {
    c4 c c8[( b)] c4
}
sopWords = \lyricmode {
    hi hi hi hi
}

altoMusic = \relative c' {
    e4 f d e
}
altoWords = \lyricmode {
    ha ha ha ha
}

tenorMusic = \relative c' {
    g4 a f g
}
tenorWords = \lyricmode {
    hu hu hu hu
}

bassMusic = \relative c {
    c4 c g c
}
bassWords = \lyricmode {
    ho ho ho ho
}

\score {
    \new ChoirStaff <<
        \new Staff = "women" <<
            \new Voice = "sopranos" { \voiceOne << \global \sopMusic >> }
            \new Voice = "altos" { \voiceTwo << \global \altoMusic >> }
        >>
        \new Lyrics \with { alignAboveContext = #"women" }
            \lyricsto "sopranos" \sopWords
        \new Lyrics \with { alignBelowContext = #"women" }
            \lyricsto "altos" \altoWords
    % we could remove the line about this with the line below, since
    % we want the alto lyrics to be below the alto Voice anyway.
    % \new Lyrics \lyricsto "altos" \altoWords

    \new Staff = "men" <<
```

```
\clef bass
\new Voice = "tenors" { \voiceOne << \global \tenorMusic >> }
\new Voice = "basses" { \voiceTwo << \global \bassMusic >> }
>>
\new Lyrics \with { alignAboveContext = #"men" }
  \lyricsto "tenors" \tenorWords
\new Lyrics \with { alignBelowContext = #"men" }
  \lyricsto "basses" \bassWords
% again, we could replace the line above this with the line below.
% \new Lyrics \lyricsto "basses" \bassWords
>>
}
```

Volta text markup using repeatCommands

Though volte are best specified using `\repeat volta`, the context property `repeatCommands` must be used in cases where the volta text needs more advanced formatting with `\markup`.

Since `repeatCommands` takes a list, the simplest method of including markup is to use an identifier for the text and embed it in the command list using the Scheme syntax `#(list (list 'volta textIdentifier))`. Start- and end-repeat commands can be added as separate list elements:

```
voltaAdLib = \markup { 1. 2. 3... \text \italic { ad lib. } }

\relative c' {
  c1
  \set Score.repeatCommands = #(list (list 'volta voltaAdLib) 'start-repeat)
  c4 b d e
  \set Score.repeatCommands = #'((volta #f) (volta "4.") end-repeat)
  f1
  \set Score.repeatCommands = #'((volta #f))
}
```

Vocal music

Section “Vocal music” in *Notation Reference*

Adding ambitus per voice

Ambitus can be added per voice. In this case, the ambitus must be moved manually to prevent collisions.

```
\new Staff <<
  \new Voice \with {
    \consists "Ambitus_engraver"
  } \relative c'' {
    \override Ambitus.X-offset = #2.0
    \voiceOne
    c4 a d e
    f1
  }
  \new Voice \with {
    \consists "Ambitus_engraver"
  } \relative c' {
    \voiceTwo
    es4 f g as
    b1
  }
>>
```



Adding indicators to staves which get split after a break

This snippet defines the `\splitStaffBarLine` command, which adds arrows in north-east and south-east directions at a bar line, to denote that several voices sharing a staff will each continue on a staff of their own in the next system.

```
;(define-markup-command (arrow-at-angle layout props angle-deg length fill)
  (number? number? boolean?)
  (let* (
    ;; PI-OVER-180 and degrees->radians are taken from flag-styles.scm
    (PI-OVER-180 (/ (atan 1 1) 45))
    (degrees->radians (lambda (degrees) (* degrees PI-OVER-180)))
    (angle-rad (degrees->radians angle-deg))
    (target-x (* length (cos angle-rad)))
    (target-y (* length (sin angle-rad))))
  (interpret-markup layout props
    (markup
      #:translate (cons (/ target-x 2) (/ target-y 2)))
      #:rotate angle-deg
      #:translate (cons (/ length -2) 0)
      #:concat (#:draw-line (cons length 0)
        #:arrow-head X RIGHT fill))))
```

```
splitStaffBarLineMarkup = \markup \with-dimensions #'(0 . 0) #'(0 . 0) {
  \combine
    \arrow-at-angle #45 #(sqrt 8) ##f
    \arrow-at-angle #-45 #(sqrt 8) ##f
}

splitStaffBarLine = {
  \once \override Staff.BarLine.stencil =
  #(\lambda (grob)
    (ly:stencil-combine-at-edge
      (ly:bar-line::print grob)
      X RIGHT
      (grob-interpret-markup grob splitStaffBarLineMarkup)
      0))
  \break
}

\paper {
  ragged-right = ##t
  short-indent = 5\mm
}

\score {
  <<
  \new ChoirStaff <<
    \new Staff \with { instrumentName = #"High I + II" } {
      <<
        \repeat unfold 4 f''1
        \\
        \repeat unfold 4 d''1
      >>
      \splitStaffBarLine
    }
    \new Staff \with { instrumentName = #"Low" } {
      <<
        \repeat unfold 4 b'1
        \\
        \repeat unfold 4 g'1
      >>
    }
  >>
}

\new Staff \with { shortInstrumentName = #"H I" } {
  R1*4
  \repeat unfold 2 { r4 f''2 r4 } \repeat unfold 2 e''1
}
\new Staff \with { shortInstrumentName = #"H II" } {
  R1*4
  \repeat unfold 4 b'2 \repeat unfold 2 c''1
}
\new Staff \with { shortInstrumentName = #"L" } {
  R1*4
  <<
```

```
\repeat unfold 4 g'1
\\
\repeat unfold 4 c'1
>>
}
>>
>>
\layout {
  \context {
    \Staff \RemoveEmptyStaves
    \override VerticalAxisGroup.remove-first = ##t
  }
}
}
```

High I + II

Low

H I

H II

L

Adding orchestral cues to a vocal score

This shows one approach to simplify adding many orchestral cues to the piano reduction in a vocal score. The music function `\cueWhile` takes four arguments: the music from which the cue is to be taken, as defined by `\addQuote`, the name to be inserted before the cue notes, then either `#UP` or `#DOWN` to specify either `\voiceOne` with the name above the staff or `\voiceTwo` with the name below the staff, and finally the piano music in parallel with which the cue notes are to appear. The name of the cued instrument is positioned to the left of the cued notes. Many passages can be cued, but they cannot overlap each other in time.

```
cueWhile =
#(define-music-function
  (parser location instrument name dir music)
  (string? string? ly:dir? ly:music?)
  #{
    \cueDuring $instrument #dir {
      \once \override TextScript.self-alignment-X = #RIGHT
      \once \override TextScript.direction = $dir
      <>- \markup { \tiny #name }
    }
  }
)
```

```
$music
}

#})
}

flute = \relative c' {
    \transposition c'
    s4 s4 e g
}
\addQuote "flute" { \flute }

clarinet = \relative c' {
    \transposition bes
    fis4 d d c
}
\addQuote "clarinet" { \clarinet }

singer = \relative c' { c4. g8 g4 bes4 }
words = \lyricmode { here's the lyr -- ics }

pianoRH = \relative c' {
    \transposition c'
    \cueWhile "clarinet" "Clar." #DOWN { c4. g8 }
    \cueWhile "flute" "Flute" #UP { g4 bes4 }
}
pianoLH = \relative c { c4 <c' e> e, <g c> }

\score {
<<
    \new Staff {
        \new Voice = "singer" {
            \singer
        }
    }
    \new Lyrics {
        \lyricsto "singer"
        \words
    }
    \new PianoStaff <<
        \new Staff {
            \new Voice {
                \pianoRH
            }
        }
        \new Staff {
            \clef "bass"
            \pianoLH
        }
    >>
}
}
```



Adjusting lyrics vertical spacing

This snippet shows how to bring the lyrics line closer to the staff.

```
% Default layout:
<<
\new Staff \new Voice = melody \relative c' {
    c4 d e f
    g4 f e d
    c1
}
\new Lyrics \lyricsto melody { aa aa aa aa aa aa aa aa }

\new Staff {
    \new Voice = melody \relative c' {
        c4 d e f
        g4 f e d
        c1
    }
}
% Reducing the minimum space below the staff and above the lyrics:
\new Lyrics \with {
    \override VerticalAxisGroup.nonstaff-relatedstaff-spacing = #'((basic-distance . 1))■
}
\lyricsto melody { aa aa aa aa aa aa aa aa }
>>
```



Aligning syllables with melisma

By default, lyrics syllables that start a melisma are left aligned on their note. The alignment can be altered using the `lyricMelismaAlignment` property.

```
\score {
    <<
    \new Staff {
        \relative c''
        \new Voice = "vocal" {
```

```

c d^^\markup default d e
c d^^\markup "right aligned" d e
c d^^\markup "center aligned" d e
c d^^\markup "reset to default" d e
}
}
\new Lyrics \lyricsto "vocal" \lyricmode {
    word word word
    \set lyricMelismaAlignment = #RIGHT
    word word word
    \set lyricMelismaAlignment = #CENTER
    word word word
    \unset lyricMelismaAlignment
    word word word
}
>>
}

```



Ambitus with multiple voices

Adding the `Ambitus_engraver` to the `Staff` context creates a single ambitus per staff, even in the case of staves with multiple voices.

```

\new Staff \with {
    \consists "Ambitus_engraver"
}
<<
\new Voice \relative c'' {
    \voiceOne
    c4 a d e
    f1
}
\new Voice \relative c' {
    \voiceTwo
    es4 f g as
    b1
}
>>

```



Ambitus

Ambitus indicate pitch ranges for voices.

Accidentals only show up if they are not part of the key signature. `AmbitusNoteHead` grobs also have ledger lines.

```
\layout {
  \context {
    \Voice
    \consists "Abitus_engraver"
  }
}

<<
\new Staff {
  \relative c' {
    \time 2/4
    c4 f'
  }
}
\new Staff {
  \relative c' {
    \time 2/4
    \key d \major
    cis4 as'
  }
}
>>
```



Ancient notation template – modern transcription of gregorian music

This example demonstrates how to do modern transcription of Gregorian music. Gregorian music has no measure, no stems; it uses only half and quarter note heads, and special marks, indicating rests of different length.

```
\include "gregorian.ly"

chant = \relative c' {
  \set Score.timing = ##f
  f4 a2 \divisioMinima
  g4 b a2 f2 \divisioMaior
  g4( f) f( g) a2 \finalis
}

verba = \lyricmode {
  Lo -- rem ip -- sum do -- lor sit a -- met
}

\score {
  \new Staff <<
    \new Voice = "melody" \chant
```

```
\new Lyrics = "one" \lyricsto melody \verba
>>
\layout {
  \context {
    \Staff
    \remove "Time_signature_engraver"
    \remove "Bar_engraver"
    \hide Stem
  }
  \context {
    \Voice
    \override Stem.length = #0
  }
  \context {
    \Score
    barAlways = ##t
  }
}
}
```



Anglican psalm template

This template shows one way of setting out an Anglican psalm chant. It also shows how the verses may be added as stand-alone text under the music. The two verses are coded in different styles to demonstrate more possibilities.

```
SopranoMusic = \relative g' {
  g1 | c2 b | a1 | \bar "||"
  a1 | d2 c | c b | c1 | \bar "||"
}

AltoMusic = \relative c' {
  e1 | g2 g | f1 |
  f1 | f2 e | d d | e1 |
}

TenorMusic = \relative a {
  c1 | c2 c | c1 |
  d1 | g,2 g | g g | g1 |
}

BassMusic = \relative c {
  c1 | e2 e | f1 |
  d1 | b2 c | g' g | c,1 |
}

global = {
  \time 2/2
```

```
}

dot = \markup {
  \raise #0.7 \musicglyph #"dots.dot"
}

tick = \markup {
  \raise #1 \fontsize #-5 \musicglyph #"scripts.rvarcomma"
}


% Use markup to center the chant on the page
\markup {
  \fill-line {
    \score { % centered
      <<
      \new ChoirStaff <<
      \new Staff <<
      \global
      \clef "treble"
      \new Voice = "Soprano" <<
      \voiceOne
      \SopranoMusic
      >>
      \new Voice = "Alto" <<
      \voiceTwo
      \AltoMusic
      >>
      >>
      \new Staff <<
      \clef "bass"
      \global
      \new Voice = "Tenor" <<
      \voiceOne
      \TenorMusic
      >>
      \new Voice = "Bass" <<
      \voiceTwo
      \BassMusic
      >>
      >>
    >>
  \layout {
    \context {
      \Score
      \override SpacingSpanner.base-shortest-duration = #(ly:make-moment 1/2)
    }
    \context {
      \Staff
      \remove "Time_signature_engraver"
    }
  }
}
```

```

    } % End score
}
} % End markup

\markup {
  \fill-line {
    \column {
      \left-align {
        \null \null \null
        \line {
          \fontsize #5 0
          \fontsize #3 come
          let us \bold sing | unto \dot the | Lord : let
        }
        \line {
          us heartily
          \concat { re \bold joyce }
          in the | strength of | our
        }
        \line {
          sal | vation.
        }
        \null
        \line {
          \hspace #2.5 8. Today if ye will hear his voice *
        }
        \line {
          \concat { \bold harden }
          \text{not your } \text{hearts : as in the pro-}
        }
        \line {
          vocation * and as in the \bold day of tempt- \text{tempt-}
        }
        \line {
          -ation \text{tempt-} in the \text{tempt-} wilderness.
        }
      }
    }
  }
}

```



O come let us **sing** | unto • the | Lord : let
us heartily **rejoice** in the | strength of | our
sal | vation.

8. Today if ye will hear his voice *
harden' not your' hearts : as in the pro-
vocation * and as in the **day** of tempt-'
-ation' in the' wilderness.

Changing stanza fonts

Fonts can be changed independently for each stanza, including the font used for printing the stanza number.

```
\new Voice {
    \time 3/4
    g2 e4
    a2 f4
    g2.
}
\addlyrics {
    \set stanza = #1. "
    Hi, my name is Bert.
}
\addlyrics {
    \override StanzaNumber.font-name = #"DejaVu"
    \set stanza = #2. "
    \override LyricText.font-family = #'typewriter
    Oh, ché -- ri, je t'aime
}
```



1. Hi, my name is Bert.
2. Oh, ché-ri, jet'aime

Chant or psalms notation

This form of notation is used for the chant of the Psalms, where verses aren't always the same length.

```
stemOff = \hide Staff.Stem
stemOn  = \undo \stemOff

\score {
    \new Staff \with { \remove "Time_signature_engraver" }
    {
        \key g \minor
        \cadenzaOn
        \stemOff a'\breve bes'4 g'4
        \stemOn a'2 \bar "||"
```

```
\stemOff a'\breve g'4 a'4
\stemOn f'2 \bar "||"
\stemOff a'\breve^markup { \italic flexe }
\stemOn g'2 \bar "||"
}
}
```



Forcing hyphens to be shown

If LilyPond does not think there is space for a hyphen, it will be omitted. The behaviour can be overridden with the `minimum-distance` property of `LyricHyphen`.

```
\relative c' {
  c32 c c c
  c32 c c c
  c32 c c c
  c32 c c c
}

\addlyrics {
  syl -- lab word word
  \override LyricHyphen.minimum-distance = #1.0
  syl -- lab word word
  \override LyricHyphen.minimum-distance = #2.0
  syl -- lab word word
  \revert LyricHyphen.minimum-distance
  syl -- lab word word
}
```



Formatting lyrics syllables

Markup mode may be used to format individual syllables in lyrics.

```
mel = \relative c' { c4 c c c }
lyr = \lyricmode {
  Lyrics \markup { \italic can } \markup { \with-color #red contain }
  \markup { \fontsize #8 \bold Markup! }
}

<<
  \new Voice = melody \mel
  \new Lyrics \lyricsto melody \lyr
>>
```



How to put ties between syllables in lyrics

This can be achieved by separating those syllables by tildes.

```
\lyrics {
    wa~o~a
}
```

wa_o_a

Hymn template

This code shows one way of setting out a hymn tune when each line starts and ends with a partial measure. It also shows how to add the verses as stand-alone text under the music.

```
Timeline = {
    \time 4/4
    \tempo 4=96
    \partial 2
    s2 | s1 | s2 \breathe s2 | s1 | s2 \bar "||" \break
    s2 | s1 | s2 \breathe s2 | s1 | s2 \bar "||"
}

SopranoMusic = \relative g' {
    g4 g | g g g g | g g g g | g g g g | g2
    g4 g | g g g g | g g g g | g g g g | g2
}

AltoMusic = \relative c' {
    d4 d | d d d d | d d d d | d d d d | d2
    d4 d | d d d d | d d d d | d d d d | d2
}

TenorMusic = \relative a {
    b4 b | b b b b | b b b b | b b b b | b2
    b4 b | b b b b | b b b b | b b b b | b2
}

BassMusic = \relative g {
    g4 g | g g g g | g g g g | g g g g | g2
    g4 g | g g g g | g g g g | g g g g | g2
}

global = {
    \key g \major
}

\score { % Start score
    <<
    \new PianoStaff << % Start pianostaff
```

```
\new Staff << % Start Staff = RH
  \global
    \clef "treble"
  \new Voice = "Soprano" << % Start Voice = "Soprano"
    \Timeline
    \voiceOne
    \SopranoMusic
  >> % End Voice = "Soprano"
  \new Voice = "Alto" << % Start Voice = "Alto"
    \Timeline
    \voiceTwo
    \AltoMusic
  >> % End Voice = "Alto"
  >> % End Staff = RH
\new Staff << % Start Staff = LH
  \global
    \clef "bass"
  \new Voice = "Tenor" << % Start Voice = "Tenor"
    \Timeline
    \voiceOne
    \TenorMusic
  >> % End Voice = "Tenor"
  \new Voice = "Bass" << % Start Voice = "Bass"
    \Timeline
    \voiceTwo
    \BassMusic
  >> % End Voice = "Bass"
  >> % End Staff = LH
  >> % End pianostaff
>>
} % End score

\markup {
  \fill-line {
    ""
  {
    \column {
      \left-align {
        "This is line one of the first verse"
        "This is line two of the same"
        "And here's line three of the first verse"
        "And the last line of the same"
      }
    }
  }
  ""
}

\paper { % Start paper block
  indent = 0      % don't indent first system
  line-width = 130 % shorten line length to suit music
```

```
} % End paper block
```

A musical score for two staves. The top staff is in treble clef, common time, with a key signature of one sharp (F#). The bottom staff is in bass clef, common time, with a key signature of one sharp (F#). Both staves have a tempo of 96 BPM. The music consists of a series of eighth-note chords.

A second musical score for two staves, identical in structure and key signature to the first, showing a continuation of the musical piece.

This is line one of the first verse
 This is line two of the same
 And here's line three of the first verse
 And the last line of the same

Lyrics alignment

Horizontal alignment for lyrics can be set by overriding the `self-alignment-X` property of the `LyricText` object. `#-1` is left, `#0` is center and `#1` is right; however, you can use `#LEFT`, `#CENTER` and `#RIGHT` as well.

```
\layout { ragged-right = ##f }
\relative c' {
  c1
  c1
  c1
}
\addlyrics {
  \once \override LyricText.self-alignment-X = #LEFT
  "This is left-aligned"
  \once \override LyricText.self-alignment-X = #CENTER
  "This is centered"
  \once \override LyricText.self-alignment-X = #1
  "This is right-aligned"
}
```

A musical score with three measures. The first measure has a single note aligned to the left. The second measure has a single note aligned to the center. The third measure has a single note aligned to the right.

This is left-aligned This is centered This is right-aligned

Marking notes of spoken parts with a cross on the stem

This example shows how to put crosses on stems. Mark the beginning of a spoken section with the `\speakOn` keyword, and end it with the `\speakOff` keyword.


```

speakOn = {
    \override Stem.stencil =
    #(lambda (grob)
        (let* ((x-parent (ly:grob-parent grob X))
               (is-rest? (ly:grob? (ly:grob-object x-parent 'rest))))
        (if is-rest?
            empty-stencil
            (ly:stencil-combine-at-edge
             (ly:stem::print grob)
             Y
             (- (ly:grob-property grob 'direction))
             (grob-interpret-markup grob
                 (markup #:center-align #:fontsize -4
                         #:musicglyph "noteheads.s2cross"))
             -2.3))))
    )
}

speakOff = {
    \revert Stem.stencil
    \revert Flag.stencil
}

\score {
    \new Staff {
        \relative c' {
            a4 b a c
            \speakOn
            g4 f r g
            b4 r d e
            \speakOff
            c4 a g f
        }
    }
}

```



Obtaining 2.12 lyrics spacing in newer versions

The vertical spacing engine changed for version 2.14. This can cause lyrics to be spaced differently. It is possible to set properties for `Lyric` and `Staff` contexts to get the spacing engine to behave as it did in version 2.12.

```

global = {
    \key d \major
    \time 3/4
}

```

```
sopMusic = \relative c' {
    % VERSE ONE
    fis4 fis fis | \break
    fis4. e8 e4
}

altoMusic = \relative c' {
    % VERSE ONE
    d4 d d |
    d4. b8 b4 |
}

tenorMusic = \relative c' {
    a4 a a |
    b4. g8 g4 |
}

bassMusic = \relative c {
    d4 d d |
    g,4. g8 g4 |
}

words = \lyricmode {
    Great is Thy faith- ful- ness,
}

\score {
    \new ChoirStaff <<
        \new Lyrics = sopranos
        \new Staff = women <<
            \new Voice = "sopranos" {
                \voiceOne
                \global \sopMusic
            }
            \new Voice = "altos" {
                \voiceTwo
                \global \altoMusic
            }
        >>
        \new Lyrics = "altos"
        \new Lyrics = "tenors"
        \new Staff = men <<
            \clef bass
            \new Voice = "tenors" {
                \voiceOne
                \global \tenorMusic
            }
            \new Voice = "basses" {
                \voiceTwo \global \bassMusic
            }
        >>
}
```

```

\new Lyrics = basses
\context Lyrics = sopranos \lyricsto sopranos \words
\context Lyrics = altos \lyricsto altos \words
\context Lyrics = tenors \lyricsto tenors \words
\context Lyrics = basses \lyricsto basses \words
>>
\layout {
  \context {
    \Lyrics
    \override VerticalAxisGroup.staff-affinity = ##f
    \override VerticalAxisGroup.staff-staff-spacing =
      #'((basic-distance . 0)
        (minimum-distance . 2)
        (padding . 2)))
  }
  \context {
    \Staff
    \override VerticalAxisGroup.staff-staff-spacing =
      #'((basic-distance . 0)
        (minimum-distance . 2)
        (padding . 2)))
  }
}
}
}

```

Great is Thy

faith-

ful-

ness,

faith-

ful-

ness,

faith-

ful-

ness,

Orchestra choir and piano template

This template demonstrates the use of nested `StaffGroup` and `GrandStaff` contexts to subgroup instruments of the same type together, and a way to use `\transpose` so that variables hold music for transposing instruments at concert pitch.

```
#(set-global-staff-size 17)
\paper {
    indent = 3.0\cm % space for instrumentName
    short-indent = 1.5\cm % space for shortInstrumentName
}

fluteMusic = \relative c' { \key g \major g'1 b }
% Pitches as written on a manuscript for Clarinet in A
% are transposed to concert pitch.
clarinetMusic = \transpose c' a
    \relative c'' { \key bes \major bes1 d }
trumpetMusic = \relative c { \key g \major g''1 b }
% Key signature is often omitted for horns
hornMusic = \transpose c' f
    \relative c { d'1 fis }
percussionMusic = \relative c { \key g \major g1 b }
sopranoMusic = \relative c'' { \key g \major g'1 b }
sopranoLyrics = \lyricmode { Lyr -- ics }
altoIMusic = \relative c' { \key g \major g'1 b }
altoIIMusic = \relative c' { \key g \major g'1 b }
altoILyrics = \sopranoLyrics
altoIIILyrics = \lyricmode { Ah -- ah }
tenorMusic = \relative c' { \clef "treble_8" \key g \major g1 b }
tenorLyrics = \sopranoLyrics
pianoRHMUSIC = \relative c { \key g \major g''1 b }
pianoLHMusic = \relative c { \clef bass \key g \major g1 b }
violinIMusic = \relative c' { \key g \major g'1 b }
violinIIMusic = \relative c' { \key g \major g'1 b }
violaMusic = \relative c { \clef alto \key g \major g'1 b }
celloMusic = \relative c { \clef bass \key g \major g1 b }
bassMusic = \relative c { \clef "bass_8" \key g \major g,1 b }

\score {
    <<
    \new StaffGroup = "StaffGroup_woodwinds" <<
```

```

\new Staff = "Staff_flute" {
    \set Staff.instrumentName = #"Flute"
    % shortInstrumentName, midiInstrument, etc.
    % may be set here as well
    \fluteMusic
}
\new Staff = "Staff_clarinet" {
    \set Staff.instrumentName =
    \markup { \concat { "Clarinet in B" \flat } } }
    % Declare that written Middle C in the music
    % to follow sounds a concert B flat, for
    % output using sounded pitches such as MIDI.
    \transposition bes
    % Print music for a B-flat clarinet
    \transpose bes c' \clarinetMusic
}
>>
\new StaffGroup = "StaffGroup_brass" <<
\new Staff = "Staff_hornI" {
    \set Staff.instrumentName = #"Horn in F"
    \transposition f
    \transpose f c' \hornMusic
}
\new Staff = "Staff_trumpet" {
    \set Staff.instrumentName = #"Trumpet in C"
    \trumpetMusic
}
>>
\new RhythmicStaff = "RhythmicStaff_percussion" <<
\set RhythmicStaff.instrumentName = #"Percussion"
\percussionMusic
>>
\new PianoStaff <<
\set PianoStaff.instrumentName = #"Piano"
\new Staff { \pianoRHMusic }
\new Staff { \pianoLHMusic }
>>
\new ChoirStaff = "ChoirStaff_choir" <<
\new Staff = "Staff_soprano" {
    \set Staff.instrumentName = #"Soprano"
    \new Voice = "soprano"
    \sopranoMusic
}
\new Lyrics \lyricsto "soprano" { \sopranoLyrics }
\new GrandStaff = "GrandStaff_altos"
\with { \accepts Lyrics } <<
\new Staff = "Staff_altoI" {
    \set Staff.instrumentName = #"Alto I"
    \new Voice = "altoI"
    \altoIMusic
}
\new Lyrics \lyricsto "altoI" { \altoILyrics }

```

```
\new Staff = "Staff_altoII" {
    \set Staff.instrumentName = #"Alto II"
    \new Voice = "altoII"
    \altoIIMusic
}
\new Lyrics \lyricsto "altoII" { \altoIILyrics }
>>
\new Staff = "Staff_tenor" {
    \set Staff.instrumentName = #"Tenor"
    \new Voice = "tenor"
    \tenorMusic
}
\new Lyrics \lyricsto "tenor" { \tenorLyrics }
>>
\new StaffGroup = "StaffGroup_strings" <<
\new GrandStaff = "GrandStaff_violins" <<
\new Staff = "Staff_violinI" {
    \set Staff.instrumentName = #"Violin I"
    \violinIMusic
}
\new Staff = "Staff_violinII" {
    \set Staff.instrumentName = #"Violin II"
    \violinIIMusic
}
>>
\new Staff = "Staff_viola" {
    \set Staff.instrumentName = #"Viola"
    \violaMusic
}
\new Staff = "Staff_cello" {
    \set Staff.instrumentName = #"Cello"
    \celloMusic
}
\new Staff = "Staff_bass" {
    \set Staff.instrumentName = #"Double Bass"
    \bassMusic
}
>>
>>
\layout { }
```

The musical score consists of 15 staves. The first four staves are instrumental: Flute, Clarinet in B-flat, Horn in F, and Trumpet in C. The fifth staff is Percussion. The next two staves are for the Piano. The vocal parts begin with Soprano, followed by Alto I and Alto II sharing a staff, then Tenor. The vocal parts are labeled with lyrics: 'Lyr - ics' for Alto I and Alto II, and 'Ah - ah' for Tenor. The final six staves are for the orchestra: Violin I, Violin II, Viola, Cello, and Double Bass. The Double Bass staff includes a '8' at the beginning. The entire score is in common time and key of C major.

Piano template with melody and lyrics

Here is a typical song format: one staff with the melody and lyrics, with piano accompaniment underneath.

```

melody = \relative c' {
  \clef treble
  \key c \major
  \time 4/4

  a b c d
}

text = \lyricmode {
  Aaa Bee Cee Dee
}

upper = \relative c' {
  \clef treble
  \key c \major
  \time 4/4
}

```

```


    a4 b c d
}

lower = \relative c {
  \clef bass
  \key c \major
  \time 4/4

  a2 c
}

\score {
  <<
  \new Voice = "mel" { \autoBeamOff \melody }
  \new Lyrics \lyricsto mel \text
  \new PianoStaff <<
    \new Staff = "upper" \upper
    \new Staff = "lower" \lower
  >>
  >>
  \layout {
    \context { \Staff \RemoveEmptyStaves }
  }
  \midi { }
}

```



Putting lyrics inside the staff

Lyrics can be moved vertically to place them inside the staff. The lyrics are moved with `\override LyricText.extra-offset = #'(0 . dy)` and there are similar commands to move the extenders and hyphens. The offset needed is established with trial and error.

```

<<
\new Staff <<
  \new Voice = "voc" \relative c' { \stemDown a bes c8 b c4 }
>>
\new Lyrics \with {
  \override LyricText.extra-offset = #'(0 . 8.6)
  \override LyricExtender.extra-offset = #'(0 . 8.6)
  \override LyricHyphen.extra-offset = #'(0 . 8.6)
} \lyricsto "voc" { La la -- la __ _ la }

```

>>



SATB Choir template - four staves

SATB choir template (four staves)

```
global = {
    \key c \major
    \time 4/4
    \dynamicUp
}
sopranonotes = \relative c' {
    c2 \p \< d c d \f
}
sopranowords = \lyricmode { do do do do }
altonotes = \relative c' {
    c2\p d c d
}
altowords = \lyricmode { re re re re }
tenornotes = {
    \clef "G_8"
    c2\mp d c d
}
tenorwords = \lyricmode { mi mi mi mi }
bassnotes = {
    \clef bass
    c2\mf d c d
}
basswords = \lyricmode { mi mi mi mi }

\score {
    \new ChoirStaff <<
        \new Staff <<
            \new Voice = "soprano" <<
                \global
                \sopranonotes
            >>
            \lyricsto "soprano" \new Lyrics \sopranowords
        >>
        \new Staff <<
            \new Voice = "alto" <<
                \global
                \altonotes
            >>
            \lyricsto "alto" \new Lyrics \altowords
        >>
        \new Staff <<
}
```

```
\new Voice = "tenor" <<
    \global
    \tenornotes
>>
\lyricsto "tenor" \new Lyrics \tenorwords
>>
\new Staff <<
    \new Voice = "bass" <<
        \global
        \bassnotes
    >>
    \lyricsto "bass" \new Lyrics \basswords
>>
>>
}
```

Single staff template with notes lyrics and chords

This template allows the preparation of a song with melody, words, and chords.

```
melody = \relative c' {
    \clef treble
    \key c \major
    \time 4/4
    a4 b c d
}
```

```
text = \lyricmode {
    Aaa Bee Cee Dee
}
```


```
harmonies = \chordmode {
    a2 c
```

```

}

\score {
  <<
  \new ChordNames {
    \set chordChanges = ##t
    \harmonies
  }
  \new Voice = "one" { \autoBeamOff \melody }
  \new Lyrics \lyricsto "one" \text
  >>
  \layout { }
  \midi { }
}

```



Single staff template with notes lyrics chords and frets

Here is a simple lead sheet template with melody, lyrics, chords and fret diagrams.

```

verseI = \lyricmode {
  \set stanza = #"1."
  This is the first verse
}

verseII = \lyricmode {
  \set stanza = #"2."
  This is the second verse.
}

theChords = \chordmode {
  % insert chords for chordnames and fretboards here
  c2 g4 c
}

staffMelody = \relative c' {
  \key c \major
  \clef treble
  % Type notes for melody here
  c4 d8 e f4 g
  \bar "|."
}


\score {
  <<
  \context ChordNames { \theChords }
  \context FretBoards { \theChords }
  \new Staff {
    \context Voice = "voiceMelody" { \staffMelody }
  }
}

```

```

}
\new Lyrics = "lyricsI" {
    \lyricsto "voiceMelody" \verseI
}
\new Lyrics = "lyricsII" {
    \lyricsto "voiceMelody" \verseII
}
>>
\layout { }
\midi { }
}

```



1. This is the first verse
2. This is the second verse.

Single staff template with notes and lyrics

This small template demonstrates a simple melody with lyrics. Cut and paste, add notes, then words for the lyrics. This example turns off automatic beaming, which is common for vocal parts. To use automatic beaming, change or comment out the relevant line.

```

melody = \relative c' {
    \clef treble
    \key c \major
    \time 4/4

    a4 b c d
}

text = \lyricmode {
    Aaa Bee Cee Dee
}

\score{
    <<
    \new Voice = "one" {
        \autoBeamOff
        \melody
    }
    \new Lyrics \lyricsto "one" \text
    >>
    \layout { }
    \midi { }
}

```



Skips in lyric mode (2)

Although **s** skips cannot be used in `\lyricmode` (it is taken to be a literal “s”, not a space), double quotes (") or underscores (_) are available. So for example:


```
<<
  \relative c' { a4 b c d }
  \new Lyrics \lyricmode { a4 "" _ gap }
>>
```



Skips in lyric mode

The **s** syntax for skips is only available in note mode and chord mode. In other situations, for example, when entering lyrics, using the `\skip` command is recommended.

```
<<
  \relative c' { a1 | a }
  \new Lyrics \lyricmode { \skip 1 bla1 }
>>
```



Using arpeggioBracket to make divisi more visible

The `arpeggioBracket` can be used to indicate the division of voices where there are no stems to provide the information. This is often seen in choral music.

```
\include "english.ly"

\score {
  \relative c' {
    \key a \major
    \time 2/2
    <<
      \new Voice = "upper"
      <<
        { \voiceOne \arpeggioBracket
          a2( b2
          <b d>1\arpeggio)
          <cs e>\arpeggio ~
          <cs e>4
        }
        \addlyrics { \lyricmode { A -- men. } }
      >>
      \new Voice = "lower"
    }
  }
```

```
{
  \voiceTwo
    a1 ~
    a
    a ~
    a4 \bar "| ."
}
>>
}
\layout { ragged-right = ##t }
}
```



Vertically aligning ossias and lyrics

This snippet demonstrates the use of the context properties `alignBelowContext` and `alignAboveContext` to control the positioning of lyrics and ossias.

```
\paper {
  ragged-right = ##t
}

\relative c' <<
  \new Staff = "1" { c4 c s2 }
  \new Staff = "2" { c4 c s2 }
  \new Staff = "3" { c4 c s2 }
  { \skip 2
    <<
      \lyrics {
        \set alignBelowContext = #"1"
        lyrics4 below
      }
      \new Staff \with {
        alignAboveContext = #"3"
        fontSize = #-2
        \override StaffSymbol.staff-space = #(magstep -2)
        \remove "Time_signature_engraver"
      } {
        \tuplet 6/4 {
          \override TextScript.padding = #3
          c8[{"ossia above" d e d e f}]
        }
      }
    >>
  }
>>
```



Vertically centered common lyrics

In a vocal piece where there are several (two, four or more) lines of lyrics, and common lyrics for all voices at some point, these common lyrics may be vertically centered regardingly, as shown in the following example:

```
\include "english.ly"
leftbrace = \markup { \override #'(font-encoding . fetaBraces) \lookup #"brace240" }
rightbrace = \markup { \rotate #180 \leftbrace }

dropLyrics =
{
  \override LyricText.extra-offset = #'(0 . -5)
  \override LyricHyphen.extra-offset = #'(0 . -5)
  \override LyricExtender.extra-offset = #'(0 . -5)
}

raiseLyrics =
{
  \revert LyricText.extra-offset
  \revert LyricHyphen.extra-offset
  \revert LyricExtender.extra-offset
}

skipFour = \repeat unfold 4 { \skip 8 }

lyricsA = \lyricmode { The first verse has \dropLyrics the com -- mon
-- words \raiseLyrics used in all four. }
lyricsB = \lyricmode { In stan -- za two, \skipFour al -- so ap -- pear. }
lyricsC = \lyricmode { By the third verse, \skipFour are get -- ting dull. }
lyricsD = \lyricmode { Last stan -- za, and \skipFour get used once more. }

melody = \relative c' { c4 d e f g f e8( e f) d4 c e d c }

\score
{
  <<
    \new Voice = m \melody
    \new Lyrics \lyricsto m \lyricsA
    \new Lyrics \lyricsto m \lyricsB
    \new Lyrics \lyricsto m \lyricsC
}
```

```
\new Lyrics \lyricsto m \lyricsD
>>
}




The first verse has used in all four.  

  In stan - za two, al - so ap - pear.  

  By the third verse, the com-mon.words are get - ting dull.  

  Last stan - za, and get used once more.


```

Vocal ensemble template with automatic piano reduction

This template adds an automatic piano reduction to the standard SATB vocal score demonstrated in “Vocal ensemble template”. This demonstrates one of the strengths of LilyPond – you can use a music definition more than once. If any changes are made to the vocal notes (say, `tenorMusic`), then the changes will also apply to the piano reduction.

```
\paper {
  top-system-spacing #'basic-distance = #10
  score-system-spacing #'basic-distance = #20
  system-system-spacing #'basic-distance = #20
  last-bottom-spacing #'basic-distance = #10
}

global = {
  \key c \major
  \time 4/4
}

sopMusic = \relative c' {
  c4 c c8[( b)] c4
}
sopWords = \lyricmode {
  hi hi hi hi
}

altoMusic = \relative c' {
  e4 f d e
}
altoWords =\lyricmode {
  ha ha ha ha
}

tenorMusic = \relative c' {
  g4 a f g
}
tenorWords = \lyricmode {
  hu hu hu hu
}

bassMusic = \relative c {
```

```
c4 c g c
}

bassWords = \lyricmode {
    ho ho ho ho
}

\score {
    <<
    \new ChoirStaff <<
        \new Lyrics = "sopranos" \with {
            % This is needed for lyrics above a staff
            \override VerticalAxisGroup.staff-affinity = #DOWN
        }
        \new Staff = "women" <<
            \new Voice = "sopranos" { \voiceOne << \global \sopMusic >> }
            \new Voice = "altos" { \voiceTwo << \global \altoMusic >> }
        >>
        \new Lyrics = "altos"
        \new Lyrics = "tenors" \with {
            % This is needed for lyrics above a staff
            \override VerticalAxisGroup.staff-affinity = #DOWN
        }
        \new Staff = "men" <<
            \clef bass
            \new Voice = "tenors" { \voiceOne << \global \tenorMusic >> }
            \new Voice = "basses" { \voiceTwo << \global \bassMusic >> }
        >>
        \new Lyrics = "basses"
        \context Lyrics = "sopranos" \lyricsto "sopranos" \sopWords
        \context Lyrics = "altos" \lyricsto "altos" \altoWords
        \context Lyrics = "tenors" \lyricsto "tenors" \tenorWords
        \context Lyrics = "basses" \lyricsto "basses" \bassWords
    >>
    \new PianoStaff <<
        \new Staff <<
            \set Staff.printPartCombineTexts = ##f
            \partcombine
            << \global \sopMusic >>
            << \global \altoMusic >>
        >>
        \new Staff <<
            \clef bass
            \set Staff.printPartCombineTexts = ##f
            \partcombine
            << \global \tenorMusic >>
            << \global \bassMusic >>
        >>
    >>
    >>
}
```



Vocal ensemble template with lyrics aligned below and above the staves

This template is basically the same as the simple “Vocal ensemble” template, with the exception that here all the lyrics lines are placed using `alignAboveContext` and `alignBelowContext`.

```
global = {
    \key c \major
    \time 4/4
}

sopMusic = \relative c' {
    c4 c c8[( b)] c4
}
sopWords = \lyricmode {
    hi hi hi hi
}

altoMusic = \relative c' {
    e4 f d e
}
altoWords = \lyricmode {
    ha ha ha ha
}

tenorMusic = \relative c' {
    g4 a f g
}
tenorWords = \lyricmode {
    hu hu hu hu
}

bassMusic = \relative c {
    c4 c g c
}
bassWords = \lyricmode {
    ho ho ho ho
}
```

```
}
```

```
\score {
    \new ChoirStaff <<
        \new Staff = "women" <<
            \new Voice = "sopranos" { \voiceOne << \global \sopMusic >> }
            \new Voice = "altos" { \voiceTwo << \global \altoMusic >> }
        >>
        \new Lyrics \with { alignAboveContext = #"women" }
            \lyricsto "sopranos" \sopWords
        \new Lyrics \with { alignBelowContext = #"women" }
            \lyricsto "altos" \altoWords
        % we could remove the line about this with the line below, since
        % we want the alto lyrics to be below the alto Voice anyway.
        % \new Lyrics \lyricsto "altos" \altoWords

        \new Staff = "men" <<
            \clef bass
            \new Voice = "tenors" { \voiceOne << \global \tenorMusic >> }
            \new Voice = "basses" { \voiceTwo << \global \bassMusic >> }
        >>
        \new Lyrics \with { alignAboveContext = #"men" }
            \lyricsto "tenors" \tenorWords
        \new Lyrics \with { alignBelowContext = #"men" }
            \lyricsto "basses" \bassWords
        % again, we could replace the line above this with the line below.
        % \new Lyrics \lyricsto "basses" \bassWords
    >>
}
```

Vocal ensemble template with verse and refrain

This template creates a score which starts with a solo verse and continues into a refrain for two voices. It also demonstrates the use of spacer rests within the \global variable to define meter changes (and other elements common to all parts) throughout the entire score.

```
global = {
    \key g \major

    % verse
    \time 3/4
```

```
s2.*2
\break

% refrain
\time 2/4
s2*2
\bar "|."

}

SoloNotes = \relative g' {
    \clef "treble"

    % verse
    g4 g g |
    b4 b b |

    % refrain
    R2*2 |
}

SoloLyrics = \lyricmode {
    One two three |
    four five six |
}

SopranoNotes = \relative c'' {
    \clef "treble"

    % verse
    R2.*2 |

    % refrain
    c4 c |
    g4 g |
}

SopranoLyrics = \lyricmode {
    la la |
    la la |
}

BassNotes = \relative c {
    \clef "bass"

    % verse
    R2.*2 |

    % refrain
    c4 e |
    d4 d |
}
```

```

BassLyrics = \lyricmode {
    dum dum |
    dum dum |
}

\score {
    <<
        \new Voice = "SoloVoice" << \global \SoloNotes >>
        \new Lyrics \lyricsto "SoloVoice" \SoloLyrics

        \new ChoirStaff <<
            \new Voice = "SopranoVoice" << \global \SopranoNotes >>
            \new Lyrics \lyricsto "SopranoVoice" \SopranoLyrics

            \new Voice = "BassVoice" << \global \BassNotes >>
            \new Lyrics \lyricsto "BassVoice" \BassLyrics
        >>
    >>
    \layout {
        ragged-right = ##t
        \context { \Staff
            % these lines prevent empty staves from being printed
            \RemoveEmptyStaves
            \override VerticalAxisGroup.remove-first = ##t
        }
    }
}

```



Vocal ensemble template

Here is a standard four-part SATB vocal score. With larger ensembles, it is often useful to include a section which is included in all parts. For example, the time signature and key signature are almost always the same for all parts. Like in the “Hymn” template, the four voices are regrouped on only two staves.

```

\paper {
    top-system-spacing #'basic-distance = #10
    score-system-spacing #'basic-distance = #20
    system-system-spacing #'basic-distance = #20
}

```

```
last-bottom-spacing #'basic-distance = #10
}

global = {
    \key c \major
    \time 4/4
}

sopMusic = \relative c' {
    c4 c c8[( b)] c4
}
sopWords = \lyricmode {
    hi hi hi hi
}

altoMusic = \relative c' {
    e4 f d e
}
altoWords = \lyricmode {
    ha ha ha ha
}

tenorMusic = \relative c' {
    g4 a f g
}
tenorWords = \lyricmode {
    hu hu hu hu
}

bassMusic = \relative c {
    c4 c g c
}
bassWords = \lyricmode {
    ho ho ho ho
}

\score {
    \new ChoirStaff <<
        \new Lyrics = "sopranos" \with {
            % this is needed for lyrics above a staff
            \override VerticalAxisGroup.staff-affinity = #DOWN
        }
        \new Staff = "women" <<
            \new Voice = "sopranos" {
                \voiceOne
                << \global \sopMusic >>
            }
            \new Voice = "altos" {
                \voiceTwo
                << \global \altoMusic >>
            }
        >>
}
```

```

\new Lyrics = "altos"
\new Lyrics = "tenors" \with {
    % this is needed for lyrics above a staff
    \override VerticalAxisGroup.staff-affinity = #DOWN
}
\new Staff = "men" <<
    \clef bass
    \new Voice = "tenors" {
        \voiceOne
        << \global \tenorMusic >>
    }
    \new Voice = "basses" {
        \voiceTwo << \global \bassMusic >>
    }
>>
\new Lyrics = "basses"
\context Lyrics = "sopranos" \lyricsto "sopranos" \sopWords
\context Lyrics = "altos" \lyricsto "altos" \altoWords
\context Lyrics = "tenors" \lyricsto "tenors" \tenorWords
\context Lyrics = "basses" \lyricsto "basses" \bassWords
>>
}

```

The musical score is arranged in two staves. The top staff (treble clef) contains four measures of soprano and alto parts. The soprano part has four 'hi' lyrics, and the alto part has four 'ha' lyrics. The bottom staff (bass clef) contains four measures of tenor and bass parts. The tenor part has four 'hu' lyrics, and the bass part has four 'ho' lyrics. The music is in common time.

Chords

Section “Chord notation” in *Notation Reference*

Adding a figured bass above or below the notes

When writing a figured bass, you can place the figures above or below the bass notes, by defining the `BassFigureAlignmentPositioning.direction` property (exclusively in a `Staff` context). Choices are `#UP` (or `#1`), `#CENTER` (or `#0`) and `#DOWN` (or `#-1`).

This property can be changed as many times as you wish. Use `\once \override` if you don’t want the override to apply to the whole score.


```
bass = {
    \clef bass
    g4 b, c d
    e d8 c d2
}
continuo = \figuremode {
    <_>4 <6>4 <5/>4
    \override Staff.BassFigureAlignmentPositioning.direction = #UP
    \%bassFigureStaffAlignmentUp
    < _+ >4 <6>
    \set Staff.useBassFigureExtenders = ##t
    \override Staff.BassFigureAlignmentPositioning.direction = #DOWN
    \%bassFigureStaffAlignmentDown
    <4>4. <4>8 <_+>4
}
\score {
    <<
        \new Staff = bassStaff \bass
        \context Staff = bassStaff \continuo
    >>
}
```



Adding bar lines to ChordNames context

To add bar line indications in the `ChordNames` context, add the `Bar_engraver`.

```
\new ChordNames \with {
    \override BarLine.bar-extent = #'(-2 . 2)
    \consists "Bar_engraver"
}
\chordmode {
    f1:maj7 f:7 bes:7
}
```




Avoiding collisions with chord fingerings

Fingerings and string numbers applied to individual notes will automatically avoid beams and stems, but this is not true by default for fingerings and string numbers applied to the individual notes of chords. The following example shows how this default behavior can be overridden.

```
\relative c' {
    \set fingeringOrientations = #'(up)
    \set stringNumberOrientations = #'(up)
    \set strokeFingerOrientations = #'(up)

    % Default behavior
    r8
    <f c'-'5>8
    <f c'\5>8
    <f c'-'rightHandFinger #2 >8

    % Corrected to avoid collisions
    r8
    \override Fingering.add-stem-support = ##t
    <f c'-'5>8
    \override StringNumber.add-stem-support = ##t
    <f c'\5>8
    \override StrokeFinger.add-stem-support = ##t
    <f c'-'rightHandFinger #2 >8
}
```



Bar chords notation for Guitar (with Text Spanner)

Here is how to print bar chords, or half-bar chords (just uncomment the appropriate line for to select either one).

```
The syntax is \bbarre #"fret number" { notes } .
%%%%%%%%%%%%%%%
%% %%/%/%% Cut here ----- Start 'bbarred.ly'

%% C with slash -----
cWithSlash = \markup {
    \combine \roman C \translate #'(0.6 . -0.4) \draw-line #'(0 . 2.0)
}

%% Span -----
%% Syntax: \bbarre #"text" { notes } - text = any number of box
bbarre =
#(define-music-function (barre location str music) (string? ly:music?))
(let ((elts (extract-named-music music '(NoteEvent EventChord))))
  (if (pair? elts)
      (let ((first-element (first elts))
            (last-element (last elts)))
        (set! (ly:music-property first-element 'articulations)
```


```

        (cons (make-music 'TextSpanEvent 'span-direction -1)
              (ly:music-property first-element 'articulations)))
      (set! (ly:music-property last-element 'articulations)
            (cons (make-music 'TextSpanEvent 'span-direction 1)
                  (ly:music-property last-element 'articulations))))))
#{
  \once \override TextSpanner.font-size = #-2
  \once \override TextSpanner.font-shape = #'upright
  \once \override TextSpanner.staff-padding = #3
  \once \override TextSpanner.style = #'line
  \once \override TextSpanner.to-barline = ##f
  \once \override TextSpanner.bound-details =
    #'((left
        (text . ,#{ \markup { \draw-line #'( 0 . -.5) } #})
        (Y . 0)
        (padding . 0.25)
        (attach-dir . -2))
      (right
        (text . ,#{ \markup { \cWithSlash #str } #})
        (Y . 0)
        (padding . 0.25)
        (attach-dir . 2)))
    %% uncomment this line for make full barred
    % \once \override TextSpanner.bound-details.left.text = \markup { "B" #str } $music
  #))
}

%% %%%%%% Cut here ----- End 'bbarred.ly'
%% Copy and change the last line for full barred. Rename in 'fbarred.ly'
%%%%%%%%%%%%%%

%% Syntax: \bbarre #"text" { notes } - text = any number of box
\brelative c'{ \clef "G_8" \stemUp \bbarre #"III" { <f a'>16[ c' d c d8] } }


```



Changing chord separator

The separator between different parts of a chord name can be set to any markup.

```

\chords {
  c:7sus4
  \set chordNameSeparator
    = \markup { \typewriter | }
  c:7sus4
}

```

C^{7sus4} C^{7|sus4}

Changing the chord names to German or semi-German notation

The english naming of chords (default) can be changed to german (\germanChords replaces B and Bes with H and B) or semi-german (\semiGermanChords replaces B and Bes with H and Bb).

```

music = \chordmode {
    c1/c | cis/cis
    b1/b | bis/bis | bes/bes
}

%% The following is only here to print the names of the
%% chords styles; it can be removed if you do not need to
%% print them.

\layout {
    \context {
        \ChordNames
        \consists "Instrument_name_engraver"
    }
}

<<
\new ChordNames {
    \set ChordNames.instrumentName = #"default"
    \music
}
\new ChordNames {
    \set ChordNames.instrumentName = #"german"
    \germanChords \music }
\new ChordNames {
    \set ChordNames.instrumentName = #"semi-german"
    \semiGermanChords \music }
\context Voice { \music }

>>

```

default	C/C	C#/C#	B/B	B#/B#	Bb/Bb
german	C/c	C#/cis	H/h	H#/his	B/b
semi-german	C/c	C#/cis	H/h	H#/his	B ^b /b

Changing the positions of figured bass alterations

Accidentals and plus signs can appear before or after the numbers, depending on the `figuredBassAlterationDirection` and `figuredBassPlusDirection` properties.

```

\figures {
    <6\+> <5+> <6 4-> r
    \set figuredBassAlterationDirection = #RIGHT

```

```

<6\+> <5+> <6 4-> r
\set figuredBassPlusDirection = #RIGHT
<6\+> <5+> <6 4-> r
\set figuredBassAlterationDirection = #LEFT
<6\+> <5+> <6 4-> r
}

```

$\begin{matrix} +6 & \#5 & 6 \\ \flat 4 \end{matrix}$
 $\begin{matrix} +6 & 5\# & 6 \\ 4\flat \end{matrix}$
 $\begin{matrix} 6+ & 5\# & 6 \\ 4\flat \end{matrix}$
 $\begin{matrix} 6+ & \#5 & 6 \\ \flat 4 \end{matrix}$

Chord name exceptions

The property `chordNameExceptions` can be used to store a list of special notations for specific chords.

```

% modify maj9 and 6(add9)
% Exception music is chords with markups
chExceptionMusic = {
  <c e g b d'>1-\markup { \super "maj9" }
  <c e g a d'>1-\markup { \super "6(add9)" }
}


% Convert music to list and prepend to existing exceptions.
chExceptions = #( append
  ( sequential-music-to-chord-exceptions chExceptionMusic #t )
  ignatzekExceptions)

theMusic = \chordmode {
  g1:maj9 g1:6.9
  \set chordNameExceptions = #chExceptions
  g1:maj9 g1:6.9
}

\layout {
  ragged-right = ##t
}

<< \context ChordNames \theMusic
  \context Voice \theMusic
>>

```



chord name major7

The layout of the major 7 can be tuned with `majorSevenSymbol`.

```

\chords {
  c:7+
  \set majorSevenSymbol = \markup { j7 }
  c:7+
}

```

}

 $C^{\triangle} C^{j7}$

Clusters


Clusters are a device to denote that a complete range of notes is to be played.

```

\relative c' {
  c4 f <e d'>4
  <g a>8 <e a> a4 c2 <d b>4
  e2 c
}

<<
  \new Staff \fragment
  \new Staff \makeClusters \fragment
>>

```




Controlling the placement of chord fingerings

The placement of fingering numbers can be controlled precisely. For fingering orientation to apply, you must use a chord construct `<>` even if it is a single note.

```

\relative c' {
  \set fingeringOrientations = #'(left)
  <c-1 e-3 a-5>4
  \set fingeringOrientations = #'(down)
  <c-1 e-3 a-5>4
  \set fingeringOrientations = #'(down right up)
  <c-1 e-3 a-5>4
  \set fingeringOrientations = #'(up)
  <c-1 e-3 a-5>4
  \set fingeringOrientations = #'(left)
  <c-1>2
  \set fingeringOrientations = #'(down)
  <e-3>2
}


```



Cross-staff chords - beaming problems workaround

Sometimes it is better to use stems from the upper staff for creating cross-staff chords, because no problems with automatic beam collision avoidance then arise. If the stems from the lower staff were used in the following example, it would be necessary to change the automatic beam collision avoidance settings so that it doesn't detect collisions between staves using \override Staff.Beam.collision-voice-only = ##t

```
\new PianoStaff <<
  \new Staff = up
    \relative c' {
      <<
        { r4
          \override Stem.cross-staff = ##t
          \override Stem.length = #19 % this is in half-spaces,
            % so it makes stems 9.5 staffspaces long
          \override Stem.Y-offset = #-6 % stems are normally lengthened
            % upwards, so here we must lower the stem by the amount
            % equal to the lengthening - in this case (19 - 7) / 2
            % (7 is default stem length)
          e e e }
        { s4
          \change Staff = "bottom"
          \override NoteColumn.ignore-collision = ##t
          c, c c
        }
      >>
    }
  \new Staff = bottom
    \relative c' {
      \clef bass
      \voiceOne
      g8 a g a g a g a
    }
>>
```



Displaying complex chords

Here is a way to display a chord where the same note is played twice with different accidentals.

```
fixA = {
  \once \override Stem.length = #9
}
fixB = {
  \once \override NoteHead.X-offset = #1.7
  \once \override Stem.rotation = #'(45 0 0)
  \once \override Stem.extra-offset = #'(-0.2 . -0.2)
```

```
\once \override Flag.style = #'no-flag
\once \override Accidental.extra-offset = #'(4 . 0)
}

\relative c' {
  << { \fixA <b d!>8 } \\ { \voiceThree \fixB dis } >> s
}
```



Manually break figured bass extenders for only some numbers

Figured bass often uses extenders to indicate continuation of the corresponding step. However, in this case lilypond is in greedy-mode and uses extenders whenever possible. To break individual extenders, one can simply use a modifier `!` to a number, which breaks any extender attributed to that number right before the number.

```
bassfigures = \figuremode {
  \set useBassFigureExtenders = ##t
  <6 4>4 <6 4!> <6 4!> <6 4!> | <6! 4!> <6 4> <6 4!> <6 4>
}

<<
  \new Staff \relative c'' { c1 c1 }
  \new FiguredBass \bassfigures
>>
```




Showing chords at changes

Chord names can be displayed only at the start of lines and when the chord changes.

```
harmonies = \chordmode {
  c1:m c:m \break c:m c:m d
}
<<
  \new ChordNames {
    \set chordChanges = ##t
    \harmonies
  }
  \new Staff {
    \relative c' { \harmonies }
  }
>>
```





Simple lead sheet

When put together, chord names, a melody, and lyrics form a lead sheet:

```
<<
  \chords { c2 g:sus4 f e }
  \relative c' {
    a4 e c8 e r4
    b2 c4( d)
  }
  \addlyrics { One day this shall be free __ }
>>
```

A musical staff with a treble clef, a key signature of one flat, and a common time signature. It shows a melody line with lyrics: "One day this shall be free". The melody consists of notes C, Gsus4, F, and E.

Single staff template with notes lyrics and chords

This template allows the preparation of a song with melody, words, and chords.


```
melody = \relative c' {
  \clef treble
  \key c \major
  \time 4/4

  a4 b c d
}

text = \lyricmode {
  Aaa Bee Cee Dee
}

harmonies = \chordmode {
  a2 c
}

\score {
  <<
  \new ChordNames {
    \set chordChanges = ##t
    \harmonies
  }
  \new Voice = "one" { \autoBeamOff \melody }
  \new Lyrics \lyricsto "one" \text
  >>
  \layout { }
  \midi { }
}
```



Single staff template with notes lyrics chords and frets

Here is a simple lead sheet template with melody, lyrics, chords and fret diagrams.

```

verseI = \lyricmode {
    \set stanza = #"1."
    This is the first verse
}

verseII = \lyricmode {
    \set stanza = #"2."
    This is the second verse.
}

theChords = \chordmode {
    % insert chords for chordnames and fretboards here
    c2 g4 c
}

staffMelody = \relative c' {
    \key c \major
    \clef treble
    % Type notes for melody here
    c4 d8 e f4 g
    \bar "|."
}

\score {
    <<
    \context ChordNames { \theChords }
    \context FretBoards { \theChords }
    \new Staff {
        \context Voice = "voiceMelody" { \staffMelody }
    }
    \new Lyrics = "lyricsI" {
        \lyricsto "voiceMelody" \verseI
    }
    \new Lyrics = "lyricsII" {
        \lyricsto "voiceMelody" \verseII
    }
    >>
    \layout { }
    \midi { }
}

```

1. This is the first verse
2. This is the second verse.

Single staff template with notes and chords

Want to prepare a lead sheet with a melody and chords? Look no further!

```

melody = \relative c' {
    \clef treble
    \key c \major
    \time 4/4

    f4 e8[ c] d4 g
    a2 ~ a
}

harmonies = \chordmode {
    c4:m f:min7 g:maj c:aug
    d2:dim b:sus
}

\score {
    <<
        \new ChordNames {
            \set chordChanges = ##t
            \harmonies
        }
        \new Staff \melody
    >>
    \layout{ }
    \midi { }
}

```

Vertically centering paired figured bass extenders

Where figured bass extender lines are being used by setting `useBassFigureExtenders` to true, pairs of congruent figured bass extender lines are vertically centered if `figuredBassCenterContinuations` is set to true.

```

<<
\relative c' {
    c8 c b b a a c16 c b b
    c8 c b b a a c16 c b b
    c8 c b b a a c c b b
}


```

```
\figures {
    \set useBassFigureExtenders = ##t
    <6+ 4 3>4 <6 4 3>8 r
    <6+ 4 3>4 <6 4 3>8 <4 3+>16 r
    \set figuredBassCenterContinuations = ##t
    <6+ 4 3>4 <6 4 3>8 r
    <6+ 4 3>4 <6 4 3>8 <4 3+>16 r
    \set figuredBassCenterContinuations = ##f
    <6+ 4 3>4 <6 4 3>8 r
    <6+ 4 3>4 <6 4 3>8 <4 3+>8
}
>>
```

Volta below chords

By adding the `Volta_engraver` to the relevant staff, volta can be put under chords.

```
\score {
    <<
    \chords {
        c1
        c1
    }
    \new Staff \with {
        \consists "Volta_engraver"
    }
    {
        \repeat volta 2 { c'1 }
        \alternative { c' }
    }
    >>
    \layout {
        \context {
            \Score
            \remove "Volta_engraver"
        }
    }
}
```



Keyboards

Section “Keyboard and other multi-staff instruments” in *Notation Reference*

Accordion-discant symbols

This snippet has been obsoleted by predefined markup commands, see Section “Accordion Registers” in *Notation Reference*. It’s still useful as a simple demonstration of how to combine symbols: the placement of the symbols added with \markup can be tweaked by changing the \translate-scaled arguments. \translate-scaled is used here rather than \translate in order to let the positioning of the symbol parts adapt to changes of `font-size`.

```
discant = \markup {
  \musicglyph #"accordion.discant"
}

dot = \markup {
  \musicglyph #"accordion.dot"
}

\layout { ragged-right = ##t }

% 16 voets register
accBasson = ^\markup {
  \combine
  \discant
  \translate-scaled #'(0 . 0.5) \dot
}

% een korig 8 en 16 voets register
accBandon = ^\markup {
  \combine
  \discant
  \combine
  \translate-scaled #'(0 . 0.5) \dot
  \translate-scaled #'(0 . 1.5) \dot
}

accVCello = ^\markup {
  \combine
  \discant
  \combine
  \translate-scaled #'(0 . 0.5) \dot
  \combine
  \translate-scaled #'(0 . 1.5) \dot
  \translate-scaled #'(1 . 1.5) \dot
}

% 4-8-16 voets register
accHarmon = ^\markup {
  \combine
  \discant
  \combine
  \translate-scaled #'(0 . 0.5) \dot
```

```
\combine
  \translate-scaled #'(0 . 1.5) \dot
  \translate-scaled #'(0 . 2.5) \dot
}

accTrombon = ^\markup {
  \combine
    \discant
  \combine
    \translate-scaled #'(0 . 0.5) \dot
  \combine
    \translate-scaled #'(0 . 1.5) \dot
  \combine
    \translate-scaled #'(1 . 1.5) \dot
    \translate-scaled #'(-1 . 1.5) \dot
}
% eenkorig 4 en 16 voets register
accOrgan = ^\markup {
  \combine
    \discant
  \combine
    \translate-scaled #'(0 . 0.5) \dot
    \translate-scaled #'(0 . 2.5) \dot
}

accMaster = ^\markup {
  \combine
    \discant
  \combine
    \translate-scaled #'(0 . 0.5) \dot
  \combine
    \translate-scaled #'(0 . 1.5) \dot
  \combine
    \translate-scaled #'(1 . 1.5) \dot
  \combine
    \translate-scaled #'(-1 . 1.5) \dot
    \translate-scaled #'(0 . 2.5) \dot
}

accAccord = ^\markup {
  \combine
    \discant
  \combine
    \translate-scaled #'(0 . 1.5) \dot
  \combine
    \translate-scaled #'(1 . 1.5) \dot
  \combine
    \translate-scaled #'(-1 . 1.5) \dot
    \translate-scaled #'(0 . 2.5) \dot
}
```

```
accMusette = ^\markup {
  \combine
    \discant
    \combine
      \translate-scaled #'(0 . 1.5) \dot
    \combine
      \translate-scaled #'(1 . 1.5) \dot
      \translate-scaled #'(-1 . 1.5) \dot
}

accCeleste = ^\markup {
  \combine
    \discant
    \combine
      \translate-scaled #'(0 . 1.5) \dot
      \translate-scaled #'(-1 . 1.5) \dot
}

accOboe = ^\markup {
  \combine
    \discant
    \combine
      \translate-scaled #'(0 . 1.5) \dot
      \translate-scaled #'(0 . 2.5) \dot
}

accClarinet = ^\markup {
  \combine
    \discant
    \translate-scaled #'(0 . 1.5) \dot
}

accPiccolo = ^\markup {
  \combine
    \discant
    \translate-scaled #'(0 . 2.5) \dot
}

accViolin = ^\markup {
  \combine
    \discant
    \combine
      \translate-scaled #'(0 . 1.5) \dot
    \combine
      \translate-scaled #'(1 . 1.5) \dot
      \translate-scaled #'(0 . 2.5) \dot
}

\relative c' {
  c4 d\accBassoon e f
  c4 d\accBandoneon e f
  c4 d\accVCello e f
}
```

```
c4 d\accHarmon e f
c4 d\accTrombon e f
\break
c4 d\accOrgan e f
c4 d\accMaster e f
c4 d\accAccord e f
c4 d\accMusette e f
c4 d\accCeleste e f
\break
c4 d\accOboe e f
c4 d\accClarinet e f
c4 d\accPiccolo e f
c4 d\accViolin e f
}
```

The musical score consists of five staves of music. Each staff begins with a treble clef, followed by a 'C' key signature, and a 4/4 time signature. The music is composed of eighth-note patterns. Above each staff is a circular register symbol with a dot or dots indicating the current register setting. The first staff has one dot. The second staff has two dots. The third staff has three dots. The fourth staff has four dots. The fifth staff has two dots.

Accordion register symbols


Accordion register symbols are available as \markup as well as as standalone music events (as register changes tend to occur between actual music events. Bass registers are not overly standardized. The available commands can be found in [Section “Accordion Registers” in Notation Reference](#).

```
\layout { ragged-right = ##t }

#(use-modules (scm accreg))

\new PianoStaff
<<
  \new Staff \relative
  { \clef treble \discant "10" r8 s32 f'[ bes f] s e[ a e] s d[ g d] s16 e32[ a
    << { r16 <f bes> r <e a> r <d g>} \\ { d r a r bes r } >> | <cis e a>1 }
  \new Staff \relative
  { \clef treble \freeBass "1" r8 d'32 s16. c32 s16. bes32 s16. a32[ cis] s16
    \clef bass \stdBass "Master"
    << { r16 <f, bes d>^"b" r <e a c>^"am" r <d g bes>^"gm" |
      <e a cis>1^"a" } \\
      { d8_ "D" c_ "C" bes_ "B" | a1_ "A" }
    >>
```

```
}
>>
```




Changing the text for sustain markings

`Staff.pedalSustainStrings` can be used to set the text used for pedal down and up. Note that the only valid strings are those found in the list of pedal glyphs - the values used this snippet constitute an exhaustive list.

```
sustainNotes = { c4\sustainOn d e\sustainOff\sustainOn f\sustainOff }
```

```
\relative c' {
  \sustainNotes
  \set Staff.pedalSustainStrings = #'("P" "P-" "-")
  \sustainNotes
  \set Staff.pedalSustainStrings = #'("d" "de" "e")
  \sustainNotes
  \set Staff.pedalSustainStrings = #'("M" "M-" "-")
  \sustainNotes
  \set Staff.pedalSustainStrings = #'("Ped" "*Ped" "*")
  \sustainNotes
}
```




Clusters

Clusters are a device to denote that a complete range of notes is to be played.

```
fragment = \relative c' {
  c4 f <e d'>4
  <g a>8 <e a> a4 c2 <d b>4
  e2 c
}


<<
  \new Staff \fragment
  \new Staff \makeClusters \fragment
>>
```



Controlling the placement of chord fingerings

The placement of fingering numbers can be controlled precisely. For fingering orientation to apply, you must use a chord construct `<>` even if it is a single note.

```
\relative c' {
    \set fingeringOrientations = #'(left)
    <c-1 e-3 a-5>4
    \set fingeringOrientations = #'(down)
    <c-1 e-3 a-5>4
    \set fingeringOrientations = #'(down right up)
    <c-1 e-3 a-5>4
    \set fingeringOrientations = #'(up)
    <c-1 e-3 a-5>4
    \set fingeringOrientations = #'(left)
    <c-1>2
    \set fingeringOrientations = #'(down)
    <e-3>2
}
```



Creating slurs across voices


In some situations, it may be necessary to create slurs between notes from different voices.

The solution is to add invisible notes to one of the voices, using `\hideNotes`.

This example is measure 235 of the Ciaconna from Bach's 2nd Partita for solo violin, BWV 1004.

```
\relative c' {
  <<
  {
    d16( a') s a s a[ s a] s a[ s a]
  }
  \\
  {
    \slurUp
    bes,16[ s e](
    \hideNotes a)
    \unHideNotes f[( 
    \hideNotes a)
    \unHideNotes fis]( 
    \hideNotes a)
    \unHideNotes g[(
```


```
\hideNotes a)
\unHideNotes gis](
\hideNotes a)
}
>>
}
```



Cross-staff chords - beaming problems workaround

Sometimes it is better to use stems from the upper staff for creating cross-staff chords, because no problems with automatic beam collision avoidance then arise. If the stems from the lower staff were used in the following example, it would be necessary to change the automatic beam collision avoidance settings so that it doesn't detect collisions between staves using `\override Staff.Beam.collision-voice-only = ##t`

```
\new PianoStaff <<
  \new Staff = up
    \relative c' {
      <<
        { r4
          \override Stem.cross-staff = ##t
          \override Stem.length = #19 % this is in half-spaces,
            % so it makes stems 9.5 staffspaces long
          \override Stem.Y-offset = #-6 % stems are normally lengthened
            % upwards, so here we must lower the stem by the amount
            % equal to the lengthening - in this case (19 - 7) / 2
            % (7 is default stem length)
          e e e }
        { s4
          \change Staff = "bottom"
          \override NoteColumn.ignore-collision = ##t
          c, c c
        }
      >>
    }
  \new Staff = bottom
    \relative c' {
      \clef bass
      \voiceOne
      g8 a g a g a g a
    }
  >>
```



Cross-staff tremolos

Since `\repeat tremolo` expects exactly two musical arguments for chord tremolos, the note or chord which changes staff within a cross-staff tremolo should be placed inside curly braces together with its `\change Staff` command.

```
\new PianoStaff <<
    \new Staff = "up" \relative c' {
        \key a \major
        \time 3/8
        s4.
    }
    \new Staff = "down" \relative c' {
        \key a \major
        \time 3/8
        \voiceOne
        \repeat tremolo 6 {
            <a e'>32
            {
                \change Staff = "up"
                \voiceTwo
                <cis a' dis>32
            }
        }
    }
>>
```



Fine-tuning pedal brackets

The appearance of pedal brackets may be altered in different ways.

```
\paper { ragged-right = ##f }
\relative c' {
    c2\sostenutoOn c
    c2\sostenutoOff c
    \once \override Staff.PianoPedalBracket.shorten-pair = #'(-7 . -2)
    c2\sostenutoOn c
    c2\sostenutoOff c
    \once \override Staff.PianoPedalBracket.edge-height = #'(0 . 3)
    c2\sostenutoOn c
    c2\sostenutoOff c
}
```



Indicating cross-staff chords with arpeggio bracket

An arpeggio bracket can indicate that notes on two different staves are to be played with the same hand. In order to do this, the `PianoStaff` must be set to accept cross-staff arpeggios and the arpeggios must be set to the bracket shape in the `PianoStaff` context.

(Debussy, Les collines d'Anacapri, m. 65)

```
\new PianoStaff <<
    \set PianoStaff.connectArpeggios = ##t
    \override PianoStaff.Arpeggio.stencil = #ly:arpeggio::brew-chord-bracket
    \new Staff {
        \relative c' {
            \key b \major
            \time 6/8
            b8-.( \arpeggio fis'-.\> cis-. e-. gis-. b-. )\! \fermata^ \laissezVibrer
            \bar "||"
        }
    }
    \new Staff {
        \relative c' {
            \clef bass
            \key b \major
            <<
                {
                    <a e cis>2. \arpeggio
                }
                \\
                {
                    <a, e a,>2.
                }
            >>
        }
    }
>>
```

Jazz combo template

This is quite an advanced template, for a jazz ensemble. Note that all instruments are notated in `\key c \major`. This refers to the key in concert pitch; the key will be automatically transposed if the music is within a `\transpose` section.

```
\header {
    title = "Song"
    subtitle = "(tune)"
    composer = "Me"
    meter = "moderato"
    piece = "Swing"
    tagline = \markup {
        \column {
            "LilyPond example file by Amelie Zapf,"
            "Berlin 07/07/2003"
        }
    }
}

%#(set-global-staff-size 16)
\include "english.ly"

%%%%%%%%%%%%% Some macros %%%%%%%%%%%%%%
sl = {
    \override NoteHead.style = #'slash
    \hide Stem
}
ns1 = {
    \revert NoteHead.style
    \undo \hide Stem
}
crOn = \override NoteHead.style = #'cross
crOff = \revert NoteHead.style

%% insert chord name style stuff here.

jazzChords = { }

%%%%%%%%%%%%% Keys'n'thangs %%%%%%%%%%%%%%
global = { \time 4/4 }

Key = { \key c \major }

% ##### Horns #####
% ----- Trumpet -----
trpt = \transpose c d \relative c' {
    \Key
    c | c | c |
}
trpHarmony = \transpose c' d {
    \jazzChords
}
trumpet = {
    \global
```

```
\set Staff.instrumentName = #"Trumpet"
\clef treble
<<
  \trpt
>>
}

% ----- Alto Saxophone -----
alto = \transpose c a \relative c' {
  \Key
  c1 | c | c |
}
altoHarmony = \transpose c' a {
  \jazzChords
}
altoSax = {
  \global
  \set Staff.instrumentName = #"Alto Sax"
  \clef treble
<<
  \alto
>>
}

% ----- Baritone Saxophone -----
bari = \transpose c a' \relative c {
  \Key
  c1
  c1
  \sl
  d4^"Solo" d d d
  \nsl
}
bariHarmony = \transpose c' a \chordmode {
  \jazzChords s1 s d2:maj e:m7
}
bariSax = {
  \global
  \set Staff.instrumentName = #"Bari Sax"
  \clef treble
<<
  \bari
>>
}

% ----- Trombone -----
tbone = \relative c {
  \Key
  c1 | c | c
}
tboneHarmony = \chordmode {
  \jazzChords
```

```
}

trombone = {
    \global
    \set Staff.instrumentName = #"Trombone"
    \clef bass
    <<
        \tbone
    >>
}

% ##### Rhythm Section #####
% ----- Guitar -----
gtr = \relative c' {
    \Key
    c1
    \sl
    b4 b b b
    \nsl
    c1
}
gtrHarmony = \chordmode {
    \jazzChords
    s1 c2:min7+ d2:maj9
}
guitar = {
    \global
    \set Staff.instrumentName = #"Guitar"
    \clef treble
    <<
        \gtr
    >>
}

%% ----- Piano -----
rhUpper = \relative c' {
    \voiceOne
    \Key
    c1 | c | c
}
rhLower = \relative c' {
    \voiceTwo
    \Key
    e1 | e | e
}

lhUpper = \relative c' {
    \voiceOne
    \Key
    g1 | g | g
}
lhLower = \relative c {
```

```
\voiceTwo
\Key
c1 | c | c
}

PianoRH = {
  \clef treble
  \global
  \set Staff.midiInstrument = #"acoustic grand"
<<
  \new Voice = "one" \rhUpper
  \new Voice = "two" \rhLower
>>
}
PianoLH = {
  \clef bass
  \global
  \set Staff.midiInstrument = #"acoustic grand"
<<
  \new Voice = "one" \lhUpper
  \new Voice = "two" \lhLower
>>
}

piano = {
<<
  \set PianoStaff.instrumentName = #"Piano"
  \new Staff = "upper" \PianoRH
  \new Staff = "lower" \PianoLH
>>
}

% ----- Bass Guitar -----
Bass = \relative c {
  \Key
  c1 | c | c
}

bass = {
  \global
  \set Staff.instrumentName = #"Bass"
  \clef bass
<<
  \Bass
>>
}

% ----- Drums -----
up = \drummode {
  \voiceOne
  hh4 <hh sn> hh <hh sn>
  hh4 <hh sn> hh <hh sn>
  hh4 <hh sn> hh <hh sn>
```

```
}

down = \drummode {
    \voiceTwo
    bd4 s bd s
    bd4 s bd s
    bd4 s bd s
}

drumContents = {
    \global
    <<
        \set DrumStaff.instrumentName = #"Drums"
        \new DrumVoice \up
        \new DrumVoice \down
    >>
}

%% It All Goes Together Here %%%%%%%

\score {
    <<
        \new StaffGroup = "horns" <<
            \new Staff = "trumpet" \trumpet
            \new Staff = "altosax" \altoSax
            \new ChordNames = "barichords" \bariHarmony
            \new Staff = "barisax" \bariSax
            \new Staff = "trombone" \trombone
        >>

        \new StaffGroup = "rhythm" <<
            \new ChordNames = "chords" \gtrHarmony
            \new Staff = "guitar" \guitar
            \new PianoStaff = "piano" \piano
            \new Staff = "bass" \bass
            \new DrumStaff \drumContents
        >>
    >>
}

\layout {
    \context { \Staff \RemoveEmptyStaves }
    \context {
        \Score
        \override BarNumber.padding = #3
        \override RehearsalMark.padding = #2
        skipBars = ##t
    }
}
\midi { }

}
```

Song

(tune)

Me

moderato

Swing

Trumpet

Alto Sax

Bari Sax

Trombone

Guitar

Piano

Bass

Drums

Laissez vibrer ties

Laissez vibrer ties have a fixed size. Their formatting can be tuned using 'tie-configuration'.

```
\relative c' {
  <c e g>4\laissezVibrer r <c f g>\laissezVibrer r
  <c d f g>4\laissezVibrer r <c d f g>4.\laissezVibrer r8

  <c d e f>4\laissezVibrer r
  \override LaissezVibrerTieColumn.tie-configuration
    = #'((-7 . ,DOWN)
      (-5 . ,DOWN)
      (-3 . ,UP))
```

```

        (-1 . ,UP))
<c d e f>4\laissezVibrer r
}

```



Piano template (simple)

Here is a simple piano staff with some notes.

```

upper = \relative c' {
    \clef treble
    \key c \major
    \time 4/4


    a4 b c d
}

lower = \relative c {
    \clef bass
    \key c \major
    \time 4/4

    a2 c
}

\score {
    \new PianoStaff <<
        \set PianoStaff.instrumentName = #"Piano"
        \new Staff = "upper" \upper
        \new Staff = "lower" \lower
    >>
    \layout { }
    \midi { }
}

```



Piano template with centered lyrics

Instead of having a full staff for the melody and lyrics, lyrics can be centered between the staves of a piano staff.

```

upper = \relative c' {
    \clef treble
    \key c \major
    \time 4/4

```

```

    a4 b c d
}


lower = \relative c {
  \clef bass
  \key c \major
  \time 4/4

  a2 c
}

text = \lyricmode {
  Aaa Bee Cee Dee
}

\score {
  \new GrandStaff <<
    \new Staff = upper { \new Voice = "singer" \upper }
    \new Lyrics \lyricsto "singer" \text
    \new Staff = lower { \lower }
  >>
  \layout {
    \context {
      \GrandStaff
      \accepts "Lyrics"
    }
    \context {
      \Lyrics
      \consists "Bar_engraver"
    }
  }
  \midi { }
}

```



Piano template with melody and lyrics

Here is a typical song format: one staff with the melody and lyrics, with piano accompaniment underneath.

```

melody = \relative c' {
  \clef treble
  \key c \major
  \time 4/4

  a b c d
}

```

```

}

text = \lyricmode {
  Aaa Bee Cee Dee
}

upper = \relative c' {
  \clef treble
  \key c \major
  \time 4/4


  a4 b c d
}

lower = \relative c {
  \clef bass
  \key c \major
  \time 4/4

  a2 c
}

\score {
  <<
  \new Voice = "mel" { \autoBeamOff \melody }
  \new Lyrics \lyricsTo mel \text
  \new PianoStaff <<
    \new Staff = "upper" \upper
    \new Staff = "lower" \lower
  >>
  >>
  \layout {
    \context { \Staff \removeEmptyStaves }
  }
  \midi { }
}

```



Using autochange with more than one voice


Using autochange with more than one voice.

```
\score
```

```
{
  \new PianoStaff
  <<
  \new Staff = "up" {
    <<
    \set Timing.beamExceptions = #'()
    \set Timing.beatStructure = #'(4)
    \new Voice {
      \voiceOne
      \autochange
      \relative c' {
        g8 a b c d e f g
        g,,8 a b c d e f g
      }
    }

    \new Voice {
      \voiceTwo
      \autochange
      \relative c' {
        g8 a b c d e f g
        g,,8 a b c d e f g
      }
    }
  >>
}

\new Staff = "down" {
  \clef bass
}
>>
}
```



Vocal ensemble template with automatic piano reduction

This template adds an automatic piano reduction to the standard SATB vocal score demonstrated in “Vocal ensemble template”. This demonstrates one of the strengths of LilyPond – you can use a music definition more than once. If any changes are made to the vocal notes (say, `tenorMusic`), then the changes will also apply to the piano reduction.

```
\paper {
  top-system-spacing #'basic-distance = #10
  score-system-spacing #'basic-distance = #20
  system-system-spacing #'basic-distance = #20
  last-bottom-spacing #'basic-distance = #10
```

```
}

global = {
    \key c \major
    \time 4/4
}

sopMusic = \relative c' {
    c4 c c8[( b)] c4
}
sopWords = \lyricmode {
    hi hi hi hi
}

altoMusic = \relative c' {
    e4 f d e
}
altoWords =\lyricmode {
    ha ha ha ha
}

tenorMusic = \relative c' {
    g4 a f g
}
tenorWords = \lyricmode {
    hu hu hu hu
}

bassMusic = \relative c {
    c4 c g c
}
bassWords = \lyricmode {
    ho ho ho ho
}

\score {
    <<
    \new ChoirStaff <<
        \new Lyrics = "sopranos" \with {
            % This is needed for lyrics above a staff
            \override VerticalAxisGroup.staff-affinity = #DOWN
        }
        \new Staff = "women" <<
            \new Voice = "sopranos" { \voiceOne << \global \sopMusic >> }
            \new Voice = "altos" { \voiceTwo << \global \altoMusic >> }
        >>
        \new Lyrics = "altos"
        \new Lyrics = "tenors" \with {
            % This is needed for lyrics above a staff
            \override VerticalAxisGroup.staff-affinity = #DOWN
        }
    >>
}
```

```

\new Staff = "men" <<
  \clef bass
  \new Voice = "tenors" { \voiceOne << \global \tenorMusic >> }
  \new Voice = "basses" { \voiceTwo << \global \bassMusic >> }
>>
\new Lyrics = "basses"
\context Lyrics = "sopranos" \lyricsto "sopranos" \sopWords
\context Lyrics = "altos" \lyricsto "altos" \altoWords
\context Lyrics = "tenors" \lyricsto "tenors" \tenorWords
\context Lyrics = "basses" \lyricsto "basses" \bassWords
>>
\new PianoStaff <<
  \new Staff <<
    \set Staff.printPartCombineTexts = ##f
    \partcombine
    << \global \sopMusic >>
    << \global \altoMusic >>
>>
\new Staff <<
  \clef bass
  \set Staff.printPartCombineTexts = ##f
  \partcombine
  << \global \tenorMusic >>
  << \global \bassMusic >>
>>
>>
>>
}

```

A musical score for four voices (men) on a piano staff. The top voice (treble clef) has lyrics 'hi hi hi hi' above the notes. The second voice (bass clef) has 'ha ha ha ha'. The third voice (treble clef) has 'hu hu hu hu'. The bottom voice (bass clef) has 'ho ho ho ho'. The music consists of quarter notes and eighth notes with stems pointing down. Measures are separated by vertical bar lines.

Percussion

Section “Percussion” in *Notation Reference*

Adding drum parts

Using the powerful pre-configured tools such as the `\drummode` function and the `DrumStaff` context, inputting drum parts is quite easy: drums are placed at their own staff positions (with a special clef symbol) and have note heads according to the drum. Attaching an extra symbol to the drum or restricting the number of lines is possible.

```
drh = \drummode { cymc4.^"crash" hhc16.^"h.h." hh hhc8 hho hhc8 hh16 hh hhc4 r4 r2 }
drl = \drummode { bd4 sn8 bd bd4 << bd ss >> bd8 tomhh tommh bd toml toml bd tomfh16 tomfh
timb = \drummode { timh4 ssh timl8 ssh r timh r4 ssh8 timl r4 cb8 cb }
```

```
\score {
  <<
    \new DrumStaff \with {
      drumStyleTable = #timbales-style
      \override StaffSymbol.line-count = #2
      \override BarLine.bar-extent = #'(-1 . 1)
    } <<
    \set Staff.instrumentName = #"timbales"
    \timb
  >>
  \new DrumStaff <<
    \set Staff.instrumentName = #"drums"
    \new DrumVoice { \stemUp \drh }
    \new DrumVoice { \stemDown \drl }
  >>
  >>
  \layout { }
  \midi {
    \tempo 4 = 120
  }
}
```

The image shows a musical score with two staves. The top staff is labeled "timbales" and has a C-clef. It contains several note heads with specific symbols: a crash symbol, an "h.h." symbol, and symbols with plus signs and zeros. The bottom staff is labeled "drums" and also has a C-clef. It consists of a continuous series of note heads, mostly with plus signs, indicating a steady rhythmic pattern.

Heavily customized polymetric time signatures

Though the polymetric time signature shown was not the most essential item here, it has been included to show the beat of this piece (which is the template of a real Balkan song!).

```
melody = \relative c' {
  \set Staff.instrumentName = #"Bb Sop."
  \key g \major
  \compoundMeter #'((3 8) (2 8) (2 8) (3 8) (2 8) (2 8)
                  (2 8) (2 8) (3 8) (2 8) (2 8))
```

```
c8 c c d4 c8 c b c b a4 g fis8 e d c b' c d e4-^ fis8 g \break
c,4. d4 c4 d4. c4 d c2 d4. e4-^ d4
c4. d4 c4 d4. c4 d c2 d4. e4-^ d4 \break
c4. d4 c4 d4. c4 d c2 d4. e4-^ d4
c4. d4 c4 d4. c4 d c2 d4. e4-^ d4 \break
}
```

```
drum = \new DrumStaff \drummode {
  \bar ".|:" bd4.^{\markup { Drums }} sn4 bd \bar ";" sn4.
  bd4 sn \bar ";" bd sn bd4. sn4 bd \bar ":|."
}

{
  \melody
  \drum
}
```

Bb Sop.

Jazz combo template

This is quite an advanced template, for a jazz ensemble. Note that all instruments are notated in `\key c \major`. This refers to the key in concert pitch; the key will be automatically transposed if the music is within a `\transpose` section.

```
\header {
  title = "Song"
  subtitle = "(tune)"
  composer = "Me"
  meter = "moderato"
  piece = "Swing"
  tagline = \markup {
    \column {
      "LilyPond example file by Amelie Zapf,"
      "Berlin 07/07/2003"
    }
  }
}
```

```

        }
    }
}

%#(set-global-staff-size 16)
\include "english.ly"

%%%%%%%%%%%%%% Some macros %%%%%%%%%%%%%%%

sl = {
    \override NoteHead.style = #'slash
    \hide Stem
}
ns1 = {
    \revert NoteHead.style
    \undo \hide Stem
}
crOn = \override NoteHead.style = #'cross
crOff = \revert NoteHead.style

%% insert chord name style stuff here.

jazzChords = { }

%%%%%%%%%%%%% Keys'n'thangs %%%%%%%%%%%%%%

global = { \time 4/4 }

Key = { \key c \major }

% ##### Horns #####
% ----- Trumpet -----
trpt = \transpose c d \relative c' {
    \Key
    c1 | c | c |
}
trpHarmony = \transpose c' d {
    \jazzChords
}
trumpet = {
    \global
    \set Staff.instrumentName = #"Trumpet"
    \clef treble
    <<
        \trpt
    >>
}
% ----- Alto Saxophone -----
alto = \transpose c a \relative c' {
    \Key
}
```

```
c1 | c | c |
}

altoHarmony = \transpose c' a {
    \jazzChords
}
altoSax = {
    \global
    \set Staff.instrumentName = #"Alto Sax"
    \clef treble
    <<
        \alto
    >>
}

% ----- Baritone Saxophone -----
bari = \transpose c a' \relative c {
    \Key
    c1
    c1
    \sl
    d4^"Solo" d d d
    \nsl
}
bariHarmony = \transpose c' a \chordmode {
    \jazzChords s1 s d2:maj e:m7
}
bariSax = {
    \global
    \set Staff.instrumentName = #"Bari Sax"
    \clef treble
    <<
        \bari
    >>
}

% ----- Trombone -----
tbone = \relative c {
    \Key
    c1 | c | c
}
tboneHarmony = \chordmode {
    \jazzChords
}
trombone = {
    \global
    \set Staff.instrumentName = #"Trombone"
    \clef bass
    <<
        \tbone
    >>
}
```

```
% ##### Rhythm Section #####
% ----- Guitar -----
gtr = \relative c' {
    \Key
    c1
    \sl
    b4 b b b
    \nsl
    c1
}
gtrHarmony = \chordmode {
    \jazzChords
    s1 c2:min7+ d2:maj9
}
guitar = {
    \global
    \set Staff.instrumentName = #"Guitar"
    \clef treble
    <<
        \gtr
    >>
}

%% ----- Piano -----
rhUpper = \relative c' {
    \voiceOne
    \Key
    c1 | c | c
}
rhLower = \relative c' {
    \voiceTwo
    \Key
    e1 | e | e
}

lhUpper = \relative c' {
    \voiceOne
    \Key
    g1 | g | g
}
lhLower = \relative c {
    \voiceTwo
    \Key
    c1 | c | c
}

PianoRH = {
    \clef treble
    \global
    \set Staff.midiInstrument = #"acoustic grand"
    <<
```

```
\new Voice = "one" \rhUpper
\new Voice = "two" \rhLower
>>
}
PianoLH = {
  \clef bass
  \global
  \set Staff.midiInstrument = #"acoustic grand"
<<
  \new Voice = "one" \lhUpper
  \new Voice = "two" \lhLower
>>
}

piano = {
<<
  \set PianoStaff.instrumentName = #"Piano"
  \new Staff = "upper" \PianoRH
  \new Staff = "lower" \PianoLH
>>
}

% ----- Bass Guitar -----
Bass = \relative c {
  \Key
  c1 | c | c
}
bass = {
  \global
  \set Staff.instrumentName = #"Bass"
  \clef bass
<<
  \Bass
>>
}

% ----- Drums -----
up = \drummode {
  \voiceOne
  hh4 <hh sn> hh <hh sn>
  hh4 <hh sn> hh <hh sn>
  hh4 <hh sn> hh <hh sn>
}
down = \drummode {
  \voiceTwo
  bd4 s bd s
  bd4 s bd s
  bd4 s bd s
}

drumContents = {
  \global
```

```

<<
\set DrumStaff.instrumentName = #'Drums"
\new DrumVoice \up
\new DrumVoice \down
>>
}

%%%%% It All Goes Together Here %%%%%%%

\score {
<<
\new StaffGroup = "horns" <<
\new Staff = "trumpet" \trumpet
\new Staff = "altosax" \altoSax
\new ChordNames = "barichords" \bariHarmony
\new Staff = "barisax" \bariSax
\new Staff = "trombone" \trombone
>>

\new StaffGroup = "rhythm" <<
\new ChordNames = "chords" \gtrHarmony
\new Staff = "guitar" \guitar
\new PianoStaff = "piano" \piano
\new Staff = "bass" \bass
\new DrumStaff \drumContents
>>
>>
\layout {
\context { \Staff \RemoveEmptyStaves }
\context {
\Score
\override BarNumber.padding = #3
\override RehearsalMark.padding = #2
skipBars = ##t
}
}
\midi { }
}

```

Song (tune)

moderato

Swing

Me

The musical score consists of eight staves, each representing an instrument. The instruments are: Trumpet, Alto Sax, Bari Sax, Trombone, Guitar, Piano, Bass, and Drums. The score is in G major (two sharps) and common time. The first four measures show each instrument playing a note 'C'. In the fifth measure, the Bari Sax has a 'Solo' section with a melodic line. The piano part includes chords Cm△ and D△9. The drums provide rhythmic support with eighth-note patterns.

Percussion beaters

Graphic symbols for percussion instruments are not natively supported; however it is possible to include such symbols, either as an external EPS file or as embedded PostScript code inside a markup, as demonstrated in this example.

```
stick = \markup {
  \with-dimensions #'(0 . 5) #'(0 . 5)
  \postscript #"
  0 6 translate
  0.8 -0.8 scale
  0 0 0 setrgbcolor
  [] 0 setdash
  1 setlinewidth
  0 setlinejoin
  0 setlinecap
  gsave [1 0 0 1 0 0] concat
  gsave [1 0 0 1 -3.5406095 -199.29342] concat
  gsave
  0 0 0 setrgbcolor
  newpath
```


```
7.1434065 200.94354 moveto
7.2109628 200.90454 7.2785188 200.86554 7.3460747 200.82654 curveto
8.2056347 202.31535 9.0651946 203.80414 9.9247546 205.29295 curveto
9.8571989 205.33195 9.7896429 205.37095 9.7220864 205.40996 curveto
8.8625264 203.92115 8.0029664 202.43233 7.1434065 200.94354 curveto
closepath
eofill
grestore
gsave
0 0 0 setrgbcolor
newpath
4.9646672 203.10444 moveto
5.0036707 203.03688 5.0426744 202.96933 5.0816777 202.90176 curveto
6.5704792 203.76133 8.0592809 204.6209 9.5480824 205.48045 curveto
9.5090791 205.54801 9.4700754 205.61556 9.4310717 205.68311 curveto
7.94227 204.82356 6.4534687 203.96399 4.9646672 203.10444 curveto
closepath
eofill
grestore
gsave
<<
/ShadingType 3
/ColorSpace /DeviceRGB
/Coords [113.13708 207.87465 0 113.13708 207.87465 16.162441]
/Extend [true true]
/Domain [0 1]
/Function <<
/FunctionType 3
/Functions
[
<<
/FunctionType 2
/Domain [0 1]
/C0 [1 1 1]
/C1 [0.72941178 0.72941178 0.72941178]
/N 1
>>
]
/Domain [0 1]
/Bounds []
/Encode [ 0 1 ]
>>
>>
newpath
7.6422017 200.76488 moveto
7.6505696 201.02554 7.3905363 201.24867 7.1341335 201.20075 curveto
6.8759501 201.16916 6.6949602 200.87978 6.7801462 200.63381 curveto
6.8480773 200.39155 7.1438307 200.25377 7.3728389 200.35861 curveto
7.5332399 200.42458 7.6444521 200.59122 7.6422017 200.76488 curveto
closepath
clip
gsave [0.052859054 0.063089841 -0.020912282 0.017521108 5.7334261 189.76443] concat
```

```
shfill
grestore
grestore
0 0 0 setrgbcolor
[] 0 setdash
0.027282091 setlinewidth
0 setlinejoin
0 setlinecap
newpath
7.6422017 200.76488 moveto
7.6505696 201.02554 7.3905363 201.24867 7.1341335 201.20075 curveto
6.8759501 201.16916 6.6949602 200.87978 6.7801462 200.63381 curveto
6.8480773 200.39155 7.1438307 200.25377 7.3728389 200.35861 curveto
7.5332399 200.42458 7.6444521 200.59122 7.6422017 200.76488 curveto
closepath
stroke
gsave
<<
/ShadingType 3
/ColorSpace /DeviceRGB
/Coords [113.13708 207.87465 0 113.13708 207.87465 16.162441]
/Extend [true true]
/Domain [0 1]
/Function <<
/FunctionType 3
/Functions
[
<<
/FunctionType 2
/Domain [0 1]
/C0 [1 1 1]
/C1 [0.72941178 0.72941178 0.72941178]
/N 1
>>
]
/Domain [0 1]
/Bounds []
/Encode [ 0 1 ]
>>
>>
newpath
5.2721217 202.83181 moveto
5.2804896 203.09247 5.0204563 203.3156 4.7640539 203.26768 curveto
4.5058701 203.23609 4.3248803 202.94671 4.4100662 202.70074 curveto
4.4779975 202.45848 4.7737511 202.3207 5.0027593 202.42554 curveto
5.1631598 202.49149 5.2743721 202.65813 5.2721217 202.83181 curveto
closepath
clip
gsave [0.052859054 0.063089841 -0.020912282 0.017521108 3.363346 191.83136] concat
shfill
grestore
grestore
```

```

0 0 0 setrgbcolor
[] 0 setdash
0.027282091 setlinewidth
0 setlinejoin
0 setlinecap
newpath
5.2721217 202.83181 moveto
5.2804896 203.09247 5.0204563 203.3156 4.7640539 203.26768 curveto
4.5058701 203.23609 4.3248803 202.94671 4.4100662 202.70074 curveto
4.4779975 202.45848 4.7737511 202.3207 5.0027593 202.42554 curveto
5.1631598 202.49149 5.2743721 202.65813 5.2721217 202.83181 curveto
closepath
stroke
grestore
grestore
"
}

\score {
  b1^{\stick
}
}
```



Printing music with different time signatures

In the following snippet, two parts have a completely different time signature, yet remain synchronized. The bar lines can no longer be printed at the `Score` level; to allow independent bar lines in each part, the `Default_barline_engraver` and `Timing_translator` are moved from the `Score` context to the `Staff` context.

If bar numbers are required, the `Bar_number_engraver` should also be moved, since it relies on properties set by the `Timing_translator`; a `\with` block can be used to add bar numbers to the relevant staff.

```

\paper {
  indent = #0
  ragged-right = ##t
}

global = { \time 3/4 { s2.*3 } \bar "" \break { s2.*3 } }

\layout {
  \context {
    \Score
    \remove "Timing_translator"
    \remove "Default_bar_line_engraver"
    \remove "Bar_number_engraver"
    \override SpacingSpanner.uniform-stretching = ##t
    \override SpacingSpanner.strict-note-spacing = ##t
  }
}
```

```
    proportionalNotationDuration = #(ly:make-moment 1/64)
}
\context {
  \Staff
  \consists "Timing_translator"
  \consists "Default_bar_line_engraver"
}
\context {
  \Voice
  \remove "Forbid_line_break_engraver"
  tupletFullLength = ##t
}
}
}

Bassklarinette = \new Staff \with {
  \consists "Bar_number_engraver"
  barNumberVisibility = #(every-nth-bar-number-visible 2)
  \override BarNumber.break-visibility = #end-of-line-invisible
} <-
\global {
  \bar "|"
  \clef treble
  \time 3/8
  d''4.

  \bar "|"
  \time 3/4
  r8 des''2( c''8)

  \bar "|"
  \time 7/8
  r4. ees''2 ~

  \bar "|"
  \time 2/4
  \tupletUp
  \tuplet 3/2 { ees''4 r4 d''4 ~ }

  \bar "|"
  \time 3/8
  \tupletUp
  \tuplet 4/3 { d''4 r4 }

  \bar "|"
  \time 2/4
  e''2

  \bar "|"
  \time 3/8
  es''4.

  \bar "|"
}
```

```
\time 3/4
r8 d'2 r8
\bar "|"
}
>>

Perkussion = \new StaffGroup <-
\new Staff <-
\global {
\bar "|"
\clef percussion
\time 3/4
r4 c'2 ~

\bar "|"
c'2.

\bar "|"
R2.

\bar "|"
r2 g'4 ~

\bar "|"
g'2. ~

\bar "|"
g'2.
}

>>
\new Staff <-
\global {
\bar "|"
\clef percussion
\time 3/4
R2.

\bar "|"
g'2. ~

\bar "|"
g'2.

\bar "|"
r4 g'2 ~

\bar "|"
g'2 r4

\bar "|"
g'2.
}
```

```
>>  
>>  
  
\score {  
  <<  
    \Bassklarinette  
    \Perkussion  
  >>  
}
```

The musical score consists of three staves. The top staff is for Bassclarinet, showing a melodic line with various note heads and rests, some with stems and some without. Measure 2 starts with a rest followed by a note with a stem. Measures 3 and 4 show notes with stems and rests. The middle staff is for Percussion, with measures 2 and 4 showing note heads and rests. The bottom staff is also for Percussion, with measures 2 and 4 showing note heads and rests. Measure 8 begins with a rest followed by a note with a stem.

(4)

8

Fretted strings

Section “Fretted string instruments” in *Notation Reference*

Adding fingerings to a score

Fingering instructions can be entered using a simple syntax.

```
\relative c' {
    c4-1 d-2 f-4 e-3
}
```




Adding fingerings to tablatures

To add fingerings to tablatures, use a combination of `\markup` and `\finger`.

```
one = \markup { \finger 1 }
two = \markup { \finger 2 }
threeTwo = \markup {
    \override #'(baseline-skip . 2)
    \column {
        \finger 3
        \finger 2
    }
}
threeFour = \markup {
    \override #'(baseline-skip . 2)
    \column {
        \finger 3
        \finger 4
    }
}


\score {
    \new TabStaff {
        \tabFullNotation
        \stemUp
        e8\4^one b\2 <g\3 e'\1>[ b\2 e\4]
        <a\3 fis'\1>^\\threeTwo[ b\2 e\4]
    }
}
```



Allowing fingerings to be printed inside the staff

By default, vertically oriented fingerings are positioned outside the staff. However, this behavior can be canceled. Note: you must use a chord construct `<>`, even if it is only a single note.

```
\relative c' {
  <c-1 e-2 g-3 b-5>2
  \override Fingering.staff-padding = #'()
  <c-1 e-2 g-3 b-5>4 <g'-0>
}
```



Bar chords notation for Guitar (with Text Spanner)


Here is how to print bar chords, or half-bar chords (just uncomment the appropriate line for to select either one).

```
The syntax is \bbarre #"fret number" { notes } .
%%%%%%%%%%%%%%%
%% %%%%/%% Cut here ----- Start 'bbarred.ly'

%% C with slash -----
cWithSlash = \markup {
  \combine \roman C \translate #'(0.6 . -0.4) \draw-line #'(0 . 2.0)
}

%% Span -----
%% Syntax: \bbarre #"text" { notes } - text = any number of box
bbarre =
#(define-music-function (barre location str music) (string? ly:music?))
  (let ((elts (extract-named-music music '(NoteEvent EventChord))))
    (if (pair? elts)
      (let ((first-element (first elts))
            (last-element (last elts)))
        (set! (ly:music-property first-element 'articulations)
              (cons (make-music 'TextSpanEvent 'span-direction -1)
                    (ly:music-property first-element 'articulations)))
        (set! (ly:music-property last-element 'articulations)
              (cons (make-music 'TextSpanEvent 'span-direction 1)
                    (ly:music-property last-element 'articulations))))))
  #{
    \once \override TextSpanner.font-size = #-2
    \once \override TextSpanner.font-shape = #'upright
    \once \override TextSpanner.staff-padding = #3
    \once \override TextSpanner.style = #'line
    \once \override TextSpanner.to-barline = ##f
    \once \override TextSpanner.bound-details =
      #'((left
          (text . ,#\{ \markup { \draw-line #'( 0 . -.5) }\ #})
          (Y . 0)
```

```
(padding . 0.25)
(attach-dir . -2))
(right
  (text . ,#{ \markup { \cWithSlash #str } #})
  (Y . 0)
  (padding . 0.25)
  (attach-dir . 2)))
%% uncomment this line for make full barred
% \once \override TextSpanner.bound-details.left.text = \markup { "B" #str }■
$music
#})
%% %%%%%% Cut here ----- End 'bbarred.ly'
%% Copy and change the last line for full barred. Rename in 'fbarred.ly'
%%%%%%%%%%%%%%%
%% Syntax: \bbarre {"text" { notes } - text = any number of box
\relative c'{ \clef "G_8" \stemUp \bbarre {"III" { <f a'>16[ c' d c d8] } }  
%
```



Changing fret orientations

Fret diagrams can be oriented in three ways. By default the top string or fret in the different orientations will be aligned.

```
\include "predefined-guitar-fretboards.ly"
```

```
<<
\chords {
    c1
    c1
    c1
}
\new FretBoards {
    \chordmode {
        c1
        \override FretBoard.fret-diagram-details.orientation =
            #'landscape
        c1
        \override FretBoard.fret-diagram-details.orientation =
            #'opposing-landscape
        c1
    }
}
\new Voice {
    c'1
```

```
c'1
c'
}
>>




```

Chord glissando in tablature

Slides for chords can be indicated in both `Staff` and `TabStaff`. String numbers are necessary for `TabStaff` because automatic string calculations are different for chords and for single notes.

```
myMusic = \relative c' {
  <c\3 e\2 g\1>1 \glissando <f\3 a\2 c\1>
}
```

```
\score {
  <<
  \new Staff {
    \clef "treble_8"
    \myMusic
  }
  \new TabStaff {
    \myMusic
  }
  >>
}
```



ChordChanges for FretBoards

FretBoards can be set to display only when the chord changes or at the beginning of a new line.

```
\include "predefined-guitar-fretboards.ly"
```

```
myChords = \chordmode {
  c1 c1 \break
  \set chordChanges = ##t
  c1 c1 \break
  c1 c1
```

```
}
```

```
<<
```

```
\new ChordNames { \myChords }
\new FretBoards { \myChords }
\new Staff { \myChords }
```


```
>>
```

The image shows three staves of musical notation for a fretted string instrument, likely guitar. Each staff begins with a C chord. The first staff has fingering '3 2 1' above the board. The second staff has fingering '3 2 1' above the board. The third staff has fingering '5' above the board.

Controlling the placement of chord fingerings

The placement of fingering numbers can be controlled precisely. For fingering orientation to apply, you must use a chord construct <> even if it is a single note.

```
\relative c' {
    \set fingeringOrientations = #'(left)
    <c-1 e-3 a-5>4
    \set fingeringOrientations = #'(down)
    <c-1 e-3 a-5>4
    \set fingeringOrientations = #'(down right up)
    <c-1 e-3 a-5>4
    \set fingeringOrientations = #'(up)
    <c-1 e-3 a-5>4
    \set fingeringOrientations = #'(left)
    <c-1>2
    \set fingeringOrientations = #'(down)
    <e-3>2
}
```



Customizing fretboard fret diagrams

Fret diagram properties can be set through 'fret-diagram-details'. For FretBoard fret diagrams, overrides are applied to the `FretBoards.FretBoard` object. Like `Voice`, `FretBoards` is a bottom level context, therefore can be omitted in property overrides.

```
\include "predefined-guitar-fretboards.ly"
\storePredefinedDiagram #default-fret-table \chordmode { c' }
    #guitar-tuning
    #"x;1-1-(;3-2;3-3;3-4;1-1-);"
```

<<

```
\new ChordNames {
    \chordmode { c1 | c | c | d }
```

}

```
\new FretBoards {
    % Set global properties of fret diagram
    \override FretBoards.FretBoard.size = #'1.2
    \override FretBoard.fret-diagram-details.finger-code = #'in-dot
    \override FretBoard.fret-diagram-details.dot-color = #'white
```

`\chordmode {`

```
    c
    \once \override FretBoard.size = #'1.0
    \once \override FretBoard.fret-diagram-details.barre-type = #'straight
    \once \override FretBoard.fret-diagram-details.dot-color = #'black
    \once \override FretBoard.fret-diagram-details.finger-code = #'below-string
```

`c'`

```
    \once \override FretBoard.fret-diagram-details.barre-type = #'none
    \once \override FretBoard.fret-diagram-details.number-type = #'arabic
    \once \override FretBoard.fret-diagram-details.orientation = #'landscape
    \once \override FretBoard.fret-diagram-details.mute-string = #"M"
    \once \override FretBoard.fret-diagram-details.label-dir = #LEFT
    \once \override FretBoard.fret-diagram-details.dot-color = #'black
```

`c'`

```
    \once \override FretBoard.fret-diagram-details.finger-code = #'below-string
    \once \override FretBoard.fret-diagram-details.dot-radius = #0.35
    \once \override FretBoard.fret-diagram-details.dot-position = #0.5
    \once \override FretBoard.fret-diagram-details.fret-count = #3
```

`d`


```
}
```

`}`

```
\new Voice {
    c'1 | c' | c' | d'
```

`}`

>>



Customizing markup fret diagrams

Fret diagram properties can be set through 'fret-diagram-details'. For markup fret diagrams, overrides can be applied to the `Voice.TextScript` object or directly to the markup.

<<

```
\chords { c1 | c | c | d }

\new Voice = "mel" {
    \textLengthOn
    % Set global properties of fret diagram
    \override TextScript.size = #'1.2
    \override TextScript.fret-diagram-details.finger-code = #'in-dot
    \override TextScript.fret-diagram-details.dot-color = #'white

    %% C major for guitar, no barre, using defaults
    % terse style
    c'1^markup { \fret-diagram-terse #"x;3-3;2-2;o;1-1;o;" }

    %% C major for guitar, barred on third fret
    % verbose style
    % size 1.0
    % roman fret label, finger labels below string, straight barre
    c'1^markup {
        % standard size
        \override #'(size . 1.0) {
            \override #'(fret-diagram-details . (
                (number-type . roman-lower)
                (finger-code . in-dot)
                (barre-type . straight))) {
                \fret-diagram-verbose #'((mute 6)
                    (place-fret 5 3 1)
                    (place-fret 4 5 2)
                    (place-fret 3 5 3)
                    (place-fret 2 5 4)
                    (place-fret 1 3 1)
                    (barre 5 1 3))
            }
        }
    }

    %% C major for guitar, barred on third fret
    % verbose style
    % landscape orientation, arabic numbers, M for mute string
    % no barre, fret label down or left, small mute label font
    c'1^markup {
        \override #'(fret-diagram-details . (
            (finger-code . below-string)
```


```

  (number-type . arabic)
  (label-dir . -1)
  (mute-string . "M")
  (orientation . landscape)
  (barre-type . none)
  (xo-font-magnification . 0.4)
  (xo-padding . 0.3))) {
\fret-diagram-verbose #'((mute 6)
  (place-fret 5 3 1)
  (place-fret 4 5 2)
  (place-fret 3 5 3)
  (place-fret 2 5 4)
  (place-fret 1 3 1)
  (barre 5 1 3))
}

}
}

%% simple D chord
% terse style
% larger dots, centered dots, fewer frets
% label below string
d'1^markup {
\override #'(fret-diagram-details . (
  (finger-code . below-string)
  (dot-radius . 0.35)
  (dot-position . 0.5)
  (fret-count . 3))) {
\fret-diagram-terse #"x;x;o;2-1;3-2;2-3;"
}
}
}
>>

```



Defining predefined fretboards for other instruments

Predefined fret diagrams can be added for new instruments in addition to the standards used for guitar. This file shows how this is done by defining a new string-tuning and a few predefined fretboards for the Venezuelan cuatro.

This file also shows how fingerings can be included in the chords used as reference points for the chord lookup, and displayed in the fret diagram and the TabStaff, but not the music.

These fretboards are not transposable because they contain string information. This is planned to be corrected in the future.

```
% add FretBoards for the Cuatro
% Note: This section could be put into a separate file
```

```
%      predefined-cuatro-fretboards.ly
%      and \included into each of your compositions

cuatroTuning = #`((ly:make-pitch 0 6 0)
                  ,(ly:make-pitch 1 3 SHARP)
                  ,(ly:make-pitch 1 1 0)
                  ,(ly:make-pitch 0 5 0))

dSix = { <a\4 b\1 d\3 fis\2> }
dMajor = { <a\4 d\1 d\3 fis \2> }
aMajSeven = { <a\4 cis\1 e\3 g\2> }
dMajSeven = { <a\4 c\1 d\3 fis\2> }
gMajor = { <b\4 b\1 d\3 g\2> }

\storePredefinedDiagram #default-fret-table \dSix
                        #cuatroTuning
                        #"o;o;o;o;" 
\storePredefinedDiagram #default-fret-table \dMajor
                        #cuatroTuning
                        #"o;o;o;3-3;" 
\storePredefinedDiagram #default-fret-table \aMajSeven
                        #cuatroTuning
                        #"o;2-2;1-1;2-3;" 
\storePredefinedDiagram #default-fret-table \dMajSeven
                        #cuatroTuning
                        #"o;o;o;1-1;" 
\storePredefinedDiagram #default-fret-table \gMajor
                        #cuatroTuning
                        #"2-2;o;1-1;o;" 

% end of potential include file /predefined-cuatro-fretboards.ly

#(set-global-staff-size 16)

primerosNames = \chordmode {
  d:6 d a:maj7 d:maj7
  g
}
primeros = {
  \dSix \dMajor \aMajSeven \dMajSeven
  \gMajor
}

\score {
  <<
  \new ChordNames {
    \set chordChanges = ##t
    \primerosNames
  }
  \new Staff {
```

```

\new Voice \with {
    \remove "New_fingering_engraver"
}
\relative c' {
    \primeros
}
}

\new FretBoards {
    \set Staff.stringTunings = #cuatroTuning
%
    \override FretBoard
        #'(fret-diagram-details string-count) = #'4
    \override FretBoard.fret-diagram-details.finger-code = #'in-dot
    \primeros
}


\new TabStaff \relative c' {
    \set TabStaff.stringTunings = #cuatroTuning
    \primeros
}

>>

\layout {
    \context {
        \Score
        \override SpacingSpanner.base-shortest-duration = #(ly:make-moment 1/16)
    }
}
\midi { }

}


```




Faking a hammer in tablatures

A hammer in tablature can be faked with slurs.

```

\score {
    \new TabStaff {
        \relative c' {
            \tabFullNotation
            c4( d) d( d)
            d2( c)
        }
    }
}
```




Fingerings string indications and right-hand fingerings

This example combines left-hand fingering, string indications, and right-hand fingering.

```
#(define RH rightHandFinger)
```

```
\relative c {
  \clef "treble_8"
  <c-3\5-\RH #1 >4
  <e-2\4-\RH #2 >4
  <g-0\3-\RH #3 >4
  <c-1\2-\RH #4 >4
}
```



Flamenco notation

For flamenco guitar, special notation is used:

- * a golpe symbol to indicate a slap on the guitar body with the nail of the ring finger *
- an arrow to indicate (the direction of) strokes *
- different letters for fingering ("p": thumb, "i": index finger, "m": middle finger, "a": ring finger and "x": little finger) *
- 3- and 4-finger rasgueados; stroke upwards with all fingers, ending with an up- and down using the index finger
- * abanicos: strokes (in tuples) with thumb (down), little and index finger (both up). There's also an abanico 2 where middle and ring finger are used instead of the little finger.
- * alza pua: fast playing with the thumb

Most figures use arrows in combination with fingering; with abanicos and rasgueados, note-heads are printed only for the first chord.

This snippet contains some header-like code that can be copied as 'flamenco.ly' and included in source files.

```
%%%%%%%%%%%%%
%%% Cut here ----- Start 'flamenco.ly'
```

```
% Text indicators
abanico = \markup { \italic Abanico }
rasgueaso = \markup { \italic Ras. }
alzapua = \markup { \italic Alzapua }

% Finger stroke symbols
strokeUp = \markup { \postscript #"
  0.1      setlinewidth
```

```

0.5 0    moveto
0.5 2    lineto
0.2 1.4 lineto
0.5 2    moveto
0.8 1.4 lineto
stroke
"}

strokeDown = \markup { \postscript #
  0.1      setlinewidth
  0.5 2    moveto
  0.5 0    lineto
  0.2 0.6 lineto
  0.5 0    moveto
  0.8 0.6 lineto
stroke
}

% Golpe symbol
golpe = \markup { \postscript #
  0.2 setlinewidth
  0 0 moveto
  1 0 lineto
  1 1 lineto
stroke
"\postscript #"
  0.1      setlinewidth
  -0.6 -0.1 moveto
  -0.6 1.0 lineto
  0.5 1.0 lineto
stroke
}

strokeUpGolpe = \markup { \column { \golpe \line { \strokeUp } } }
iUpGolpe = \markup { \column { \golpe \line { \small i } \line { \strokeUp } } }

% Strokes for all fingers
pUp   = \markup { \column { \small p \line { \strokeUp } } }
pDown = \markup { \column { \small p \line { \strokeDown } } }
iUp   = \markup { \column { \small i \line { \strokeUp } } }
iDown = \markup { \column { \small i \line { \strokeDown } } }
mUp   = \markup { \column { \small m \line { \strokeUp } } }
mDown = \markup { \column { \small m \line { \strokeDown } } }
aUp   = \markup { \column { \small a \line { \strokeUp } } }
aDown = \markup { \column { \small a \line { \strokeDown } } }
xUp   = \markup { \column { \small x \line { \strokeUp } } }
xDown = \markup { \column { \small x \line { \strokeDown } } }

% Just handy :)
tupleOff = {
  \once \omit TupletNumber

```

```

\once \omit TupletBracket
}

tupletsOff = {
  \omit TupletNumber
  \override TupletBracket.bracket-visibility = #'if-no-beam
}

tupletsOn = {
  \override TupletBracket.bracket-visibility = #'default
  \undo \omit TupletNumber
}

headsOff = {
  \hide TabNoteHead
  \hide NoteHead
  \override NoteHead.no-ledgers = ##t
}

headsOn = {
  \override TabNoteHead.transparent = ##f
  \override NoteHead.transparent = ##f
  \override NoteHead.no-ledgers = ##f
}

%%%%%%%% Cut here ----- End 'flamenco.ly'
%%%%%%%%%%%%%%

part = \relative c' {
  <a, e' a cis e>8^\iUp
  <a e' a cis e>8^\iDown
  r4
  r2^\golpe

  <a e' a cis e>8^\iUp
  <a e' a cis e>8^\iDown
  <a e' a cis e>8^\iUpGolpe
  <a e' a cis e>8^\iDown
  r2

  <a e' a cis e>16^\aUp
  \headsOff
  <a e' a cis e>^\mUp
  <a e' a cis e>^\iUp
  <a e' a cis e>^\iDown^
  \headsOn
  <a e' a cis e>2
  r4

  \tupletOff
  \tuplet 5/4 {
    <a e' a cis e>16^\xUp
  }
}

```

```

\headsOff
<a e' a cis e>^aUp
<a e' a cis e>^mUp
<a e' a cis e>^iUp
<a e' a cis e>^iDown~
\headsOn
}
<a e' a cis e>2
r4

\tupletsOff
\tuplet 3/2 {
<a e' a cis e>8^pDown
\headsOff
<a e' a cis e>^xUp
<a e' a cis e>^iUp
\headsOn
}

\tuplet 3/2 {
<a e' a cis e>8^pDown
\headsOff
<a e' a cis e>^xUp
<a e' a cis e>^iUp
\headsOn
}

\tuplet 3/2 {
<a e' a cis e>8^pDown
\headsOff
<a e' a cis e>^xUp
<a e' a cis e>^iUp
\headsOn
}
\tuplet 3/2 {
<a e' a cis e>8^pDown
\headsOff
<a e' a cis e>^xUp
<a e' a cis e>^iUp
\headsOn
}

\tupletsOff
\override Beam.positions = #'(2 . 2)
\tuplet 3/2 {
a8^\markup{ \small p }
<e' a>^\strokeUpGolpe
<e a>^\strokeDown
}
\tuplet 3/2 {
a,8^\markup{ \small p }
<e' a>^\strokeUpGolpe

```

```


<e a>^\strokeDown
}
\tuplet 3/2 {
  a,8^\markup{ \small p }
  <e' a>^\strokeUpGolpe
  <e a>^\strokeDown
}
\tuplet 3/2 {
  a,8^\markup{ \small p }
  <e' a>^\strokeUpGolpe
  <e a>^\strokeDown
}
\tupletsOn

\once \override TextScript.extra-offset = #'(0 . -1)
<g, b f'>1_\golpe^\mUp
\bar "|."
}

\score {
  \new StaffGroup <<
    \context Staff = "part" <<
      \clef G
      \transpose c c'
    {
      \part
    }
  >>
    \context TabStaff {
      \part
    }
  >>
    \layout {
      ragged-right = ##t
    }
}

```

<img alt="A musical score for fretted strings (guitar) in common time, key of C major (two sharps). The score consists of four measures. Measure 1: A power chord (B5, D6) is followed by a rest. Measure 2: An eighth-note stroke (down) on the B string (B5), followed by three eighth-note strokes (up) on the B string (B5), D5, and B5. Measure 3: An eighth-note stroke (up) on the B string (B5), followed by three eighth-note strokes (down) on the B string (B5), D5, and B5. Measure 4: An eighth-note stroke (up) on the B string (B5), followed by three eighth-note strokes (down) on the B string (B5), D5, and B5. Below the staff is a tablature showing fingerings: measure 1, index (i) and middle (m); measure 2, index (i), index (i), index (i); measure 3, index (i), middle (m), index (i); measure 4, index (x), index (a), middle (m), index (i). The tablature shows six strings (B, G, D, A, E, B) with fret numbers: 0, 0, 0, 0, 0, 0; 2, 2, 2, 2, 2, 2; 2, 2, 2, 2, 2, 2; 0, 0, 0, 0, 0, 0.</div>



Fret diagrams explained and developed

This snippet shows many possibilities for obtaining and tweaking fret diagrams.

<<

```
\chords {
    a2 a
    \repeat unfold 3 {
        c c c d d
    }
}

\new Voice = "mel" {
    \textLengthOn
    % Set global properties of fret diagram
    \override TextScript.size = #1.2
    \override TextScript.fret-diagram-details.finger-code = #'below-string
    \override TextScript.fret-diagram-details.dot-color = #'black

    %% A chord for ukulele
    a'2^markup {
        \override #'(fret-diagram-details . (
            (string-count . 4)
            (dot-color . white)
            (finger-code . in-dot))) {
            \fret-diagram #"4-2-2;3-1-1;2-o;1-o;"
        }
    }

    %% A chord for ukulele, with formatting defined in definition string
    % 1.2 * size, 4 strings, 4 frets, fingerings below string
    % dot radius .35 of fret spacing, dot position 0.55 of fret spacing
    a'2^markup {
        \override #'(fret-diagram-details . (
            (dot-color . white)
            (open-string . "o"))) {
            \fret-diagram #"s:1.2;w:4;h:3;f:2;d:0.35;p:0.55;4-2-2;3-1-1;2-o;1-o;"
        }
    }

    %% These chords will be in normal orientation

    %% C major for guitar, barred on third fret
    % verbose style
    % roman fret label, finger labels below string, straight barre
    c'2^markup {
```

```
% 110% of default size
\override #'(size . 1.1) {
  \override #'(fret-diagram-details . (
    (number-type . roman-lower)
    (finger-code . below-string)
    (barre-type . straight))) {
    \fret-diagram-verbose #'((mute 6)
      (place-fret 5 3 1)
      (place-fret 4 5 2)
      (place-fret 3 5 3)
      (place-fret 2 5 4)
      (place-fret 1 3 1)
      (barre 5 1 3))
  }
}

%% C major for guitar, barred on third fret
%% Double barre used to test barre function
% verbose style
c'2^markup {
  % 110% of default size
  \override #'(size . 1.1) {
    \override #'(fret-diagram-details . (
      (number-type . arabic)
      (dot-label-font-mag . 0.9)
      (finger-code . in-dot)
      (fret-label-font-mag . 0.6)
      (fret-label-vertical-offset . 0)
      (label-dir . -1)
      (mute-string . "M")
      (xo-font-magnification . 0.4)
      (xo-padding . 0.3))) {
      \fret-diagram-verbose #'((mute 6)
        (place-fret 5 3 1)
        (place-fret 4 5 2)
        (place-fret 3 5 3)
        (place-fret 2 5 4)
        (place-fret 1 3 1)
        (barre 4 2 5)
        (barre 5 1 3))
    }
  }
}

%% C major for guitar, with capo on third fret
% verbose style
c'2^markup {
  % 110% of default size
  \override #'(size . 1.1) {
    \override #'(fret-diagram-details . (
      (number-type . roman-upper)
```

```

        (dot-label-font-mag . 0.9)
        (finger-code . none)
        (fret-label-vertical-offset . 0.5)
        (xo-font-magnification . 0.4)
        (xo-padding . 0.3))) {
    \fret-diagram-verbose #'((mute 6)
        (capo 3)
        (open 5)
        (place-fret 4 5 1)
        (place-fret 3 5 2)
        (place-fret 2 5 3)
        (open 1))
    }
}
}

%% simple D chord
d'2^markup {
    \override #'(fret-diagram-details . (
        (finger-code . below-string)
        (dot-radius . 0.35)
        (string-thickness-factor . 0.3)
        (dot-position . 0.5)
        (fret-count . 3))) {
    \fret-diagram-terse #"x;x;o;2-1;3-2;2-3;"
}
}

%% simple D chord, large top fret thickness
d'2^markup {
    \override #'(fret-diagram-details . (
        (finger-code . below-string)
        (dot-radius . 0.35)
        (dot-position . 0.5)
        (top-fret-thickness . 7)
        (fret-count . 3))) {
    \fret-diagram-terse #"x;x;o;2-1;3-2;2-3;"
}
}

% These chords will be in landscape orientation
\override TextScript.fret-diagram-details.orientation = #'landscape

%% C major for guitar, barred on third fret
% verbose style
% roman fret label, finger labels below string, straight barre
c'2^markup {
    % 110% of default size
    \override #'(size . 1.1) {
        \override #'(fret-diagram-details . (
            (number-type . roman-lower)
            (finger-code . below-string)

```

```

        (barre-type . straight))) {
\fret-diagram-verbose #'((mute 6)
                           (place-fret 5 3 1)
                           (place-fret 4 5 2)
                           (place-fret 3 5 3)
                           (place-fret 2 5 4)
                           (place-fret 1 3 1)
                           (barre 5 1 3))
}
}
}

%% C major for guitar, barred on third fret
%% Double barre used to test barre function
% verbose style
c'2^markup {
% 110% of default size
\override #'(size . 1.1) {
\override #'(fret-diagram-details . (
  (number-type . arabic)
  (dot-label-font-mag . 0.9)
  (finger-code . in-dot)
  (fret-label-font-mag . 0.6)
  (fret-label-vertical-offset . 0)
  (label-dir . -1)
  (mute-string . "M")
  (xo-font-magnification . 0.4)
  (xo-padding . 0.3))) {
\fret-diagram-verbose #'((mute 6)
                           (place-fret 5 3 1)
                           (place-fret 4 5 2)
                           (place-fret 3 5 3)
                           (place-fret 2 5 4)
                           (place-fret 1 3 1)
                           (barre 4 2 5)
                           (barre 5 1 3))
}
}
}

%% C major for guitar, with capo on third fret
% verbose style
c'2^markup {
% 110% of default size
\override #'(size . 1.1) {
\override #'(fret-diagram-details . (
  (number-type . roman-upper)
  (dot-label-font-mag . 0.9)
  (finger-code . none)
  (fret-label-vertical-offset . 0.5)
  (xo-font-magnification . 0.4)
  (xo-padding . 0.3))) {

```

```

\fret-diagram-verbose #'((mute 6)
                          (capo 3)
                          (open 5)
                          (place-fret 4 5 1)
                          (place-fret 3 5 2)
                          (place-fret 2 5 3)
                          (open 1))
}
}

}

%% simple D chord
d'2^markup {
\override #'(fret-diagram-details . (
  (finger-code . below-string)
  (dot-radius . 0.35)
  (dot-position . 0.5)
  (fret-count . 3))) {
\fret-diagram-terse #"x;x;o;2-1;3-2;2-3;"
}
}

%% simple D chord, large top fret thickness
d'2^markup {
\override #'(fret-diagram-details . (
  (finger-code . below-string)
  (dot-radius . 0.35)
  (dot-position . 0.5)
  (top-fret-thickness . 7)
  (fret-count . 3))) {
\fret-diagram-terse #"x;x;o;2-1;3-2;2-3;"
}
}

% These chords will be in opposing-landscape orientation
\override TextScript.fret-diagram-details.orientation = #'opposing-landscape

%% C major for guitar, barred on third fret
% verbose style
% roman fret label, finger labels below string, straight barre
c'2^markup {
% 110% of default size
\override #'(size . 1.1) {
\override #'(fret-diagram-details . (
  (number-type . roman-lower)
  (finger-code . below-string)
  (barre-type . straight))) {
\fret-diagram-verbose #'((mute 6)
                          (place-fret 5 3 1)
                          (place-fret 4 5 2)
                          (place-fret 3 5 3)
                          (place-fret 2 5 4)

```

```

        (place-fret 1 3 1)
        (barre 5 1 3))
    }
}
}

%% C major for guitar, barred on third fret
%% Double barre used to test barre function
% verbose style
c'2^markup {
    % 110% of default size
    \override #'(size . 1.1) {
        \override #'(fret-diagram-details . (
            (number-type . arabic)
            (dot-label-font-mag . 0.9)
            (finger-code . in-dot)
            (fret-label-font-mag . 0.6)
            (fret-label-vertical-offset . 0)
            (label-dir . -1)
            (mute-string . "M")
            (xo-font-magnification . 0.4)
            (xo-padding . 0.3))) {
            \fret-diagram-verbose #'((mute 6)
                (place-fret 5 3 1)
                (place-fret 4 5 2)
                (place-fret 3 5 3)
                (place-fret 2 5 4)
                (place-fret 1 3 1)
                (barre 4 2 5)
                (barre 5 1 3))
        }
    }
}

%% C major for guitar, with capo on third fret
% verbose style
c'2^markup {
    % 110% of default size
    \override #'(size . 1.1) {
        \override #'(fret-diagram-details . (
            (number-type . roman-upper)
            (dot-label-font-mag . 0.9)
            (finger-code . none)
            (fret-label-vertical-offset . 0.5)
            (xo-font-magnification . 0.4)
            (xo-padding . 0.3))) {
            \fret-diagram-verbose #'((mute 6)
                (capo 3)
                (open 5)
                (place-fret 4 5 1)
                (place-fret 3 5 2)
                (place-fret 2 5 3)

```

```

        }                                     (open 1))
    }
}
}


%% simple D chord
d'2^markup {
\override #'(fret-diagram-details . (
(finger-code . below-string)
(dot-radius . 0.35)
(dot-position . 0.5)
(fret-count . 3))) {
\fret-diagram-terse #";x;x;o;2-1;3-2;2-3;"}
}

%% simple D chord, large top fret thickness
d'2^markup {
\override #'(fret-diagram-details . (
(finger-code . below-string)
(dot-radius . 0.35)
(dot-position . 0.5)
(top-fret-thickness . 7)
(fret-count . 3))) {
\fret-diagram-terse #";x;x;o;2-1;3-2;2-3;"}
}

}

>>

```



Fretboards alternate tables

Alternate fretboard tables can be created. These would be used in order to have alternate fretboards for a given chord.

In order to use an alternate fretboard table, the table must first be created. Fretboards are then added to the table.

The created fretboard table can be blank, or it can be copied from an existing table.

The table to be used in displaying predefined fretboards is selected by the property \predefinedDiagramTable.

```
\include "predefined-guitar-fretboards.ly"

% Make a blank new fretboard table
#(define custom-fretboard-table-one (make-fretboard-table))


% Make a new fretboard table as a copy of default-fret-table
#(define custom-fretboard-table-two (make-fretboard-table default-fret-table))

% Add a chord to custom-fretboard-table-one
\storePredefinedDiagram #custom-fretboard-table-one
    \chordmode{c}
    #guitar-tuning
    "3-(;3;5;5;5;3-);"

% Add a chord to custom-fretboard-table-two
\storePredefinedDiagram #custom-fretboard-table-two
    \chordmode{c}
    #guitar-tuning
    "x;3;5;5;5;o;"

<<
\chords {
    c1 | d1 |
    c1 | d1 |
    c1 | d1 |
}
\new FretBoards {
    \chordmode {
        \set predefinedDiagramTable = #default-fret-table
        c1 | d1 |
        \set predefinedDiagramTable = #custom-fretboard-table-one
        c1 | d1 |
        \set predefinedDiagramTable = #custom-fretboard-table-two
        c1 | d1 |
    }
}
\new Staff {
    \clef "treble_8"
<<
    \chordmode {
        c1 | d1 |
        c1 | d1 |
        c1 | d1 |
    }
{
    s1_\markup "Default table" | s1 |
    s1_\markup \column {"New table" "from empty"} | s1 |
    s1_\markup \column {"New table" "from default"} | s1 |
}
```

```
>>
}
>>
```



Fretted-string harmonics in tablature

Demonstrates fretted-string harmonics in tablature

```
pinchedHarmonics = {
    \textSpannerDown
    \override TextSpanner.bound-details.left.text =
        \markup {\halign #-0.5 \teeny "PH" }
    \override TextSpanner.style =
        #'dashed-line
    \override TextSpanner.dash-period = #0.6
    \override TextSpanner.bound-details.right.attach-dir = #1
    \override TextSpanner.bound-details.right.text =
        \markup { \draw-line #'(0 . 1) }
    \override TextSpanner.bound-details.right.padding = #-0.5
}

harmonics = {
    %artificial harmonics (AH)
    \textLengthOn
    <\parenthesize b b'\harmonic>4_\markup{ \teeny "AH 16" }
    <\parenthesize g g'\harmonic>4_\markup{ \teeny "AH 17" }
    <\parenthesize d' d''\harmonic>2_\markup{ \teeny "AH 19" }
    %pinched harmonics (PH)
    \pinchedHarmonics
    <a'\harmonic>2\startTextSpan
    <d''\harmonic>4
    <e'\harmonic>4\stopTextSpan
    %tapped harmonics (TH)
    <\parenthesize g\4 g'\harmonic>4_\markup{ \teeny "TH 17" }
    <\parenthesize a\4 a'\harmonic>4_\markup{ \teeny "TH 19" }
    <\parenthesize c'\3 c''\harmonic>2_\markup{ \teeny "TH 17" }
    %touch harmonics (TCH)
    a4( <e''\harmonic>2. )_\markup{ \teeny "TCH" }
}

frettedStrings = {
    %artificial harmonics (AH)
    \harmonicByFret #4 g4\3
```

```
\harmonicByFret #5 d4\4
\harmonicByFret #7 g2\3
%pinched harmonics (PH)
\harmonicByFret #7 d2\4
\harmonicByFret #5 d4\4
\harmonicByFret #7 a4\5
%tapped harmonics (TH)
\harmonicByFret #5 d4\4
\harmonicByFret #7 d4\4
\harmonicByFret #5 g2\3
%touch harmonics (TCH)
a4 \harmonicByFret #9 g2.\3
}
```

```
\score {
<<
  \new Staff {
    \new Voice {
      \clef "treble_8"
      \harmonics
    }
  }
  \new TabStaff {
    \new TabVoice {
      \frettedStrings
    }
  }
>>
}
```

The musical score consists of two staves. The top staff is a standard musical notation staff with a treble clef, a C major key signature, and an 8th note time signature. It contains several notes with diamond-shaped stems, each labeled with a number indicating a specific harmonic technique: AH 16, AH 17, PH, TH 17, TH 19, TH 17, and TCH. The bottom staff is a tablature staff with four vertical columns. The first column has three horizontal lines with the numbers (4), (5), and (7) above them. The second column has two horizontal lines with the numbers (7) and (5) above them. The third column has two horizontal lines with the numbers (5) and (7) above them. The fourth column has two horizontal lines with the numbers (5) and 2 (9) above them.

Guitar slides

Unlike glissandos, slides may go from an imprecise point of the fretboard to a specific fret. A good way to do that is to add a grace hidden note before the note which is actually played, as demonstrated in the following example.


```
%% Hide fret number: useful to draw slide into/from a casual point of
%% the fretboard.
hideFretNumber = {
  \once \hide TabNoteHead
  \once \hide NoteHead
  \once \hide Stem
  \once \override NoteHead.no-ledgers = ##t
  \once \override Glissando.bound-details.left.padding = #0.3
```

```
}
```

```
music= \relative c' {
    \grace { \hideFretNumber d8\2 \glissando s2 } g2\2
    \grace { \hideFretNumber g8\2 \glissando s2 } d2 |

    \grace { \hideFretNumber c,8 \glissando s } f4\5^\markup \tiny { Slide into }
    \grace { \hideFretNumber f8 \glissando s } a4\4
    \grace { \hideFretNumber e'8\3 \glissando s } b4\3^\markup \tiny { Slide from }
    \grace { \hideFretNumber b'8 \glissando s2 } g4 |
}

\score {
  <<
  \new Staff {
    \clef "G_8"
    \music
  }
  \new TabStaff {
    \music
  }
  >>
}
```



Guitar strum rhythms

For guitar music, it is possible to show strum rhythms, along with melody notes, chord names and fret diagrams.

```
\include "predefined-guitar-fretboards.ly"
<<
\new ChordNames {
  \chordmode {
    c1 | f | g | c
  }
}
\new FretBoards {
  \chordmode {
    c1 | f | g | c
  }
}
\new Voice \with {
  \consists "Pitch_squash_engraver"
}
```

```
\relative c'' {
    \improvisationOn
    c4 c8 c c4 c8 c
    f4 f8 f f4 f8 f
    g4 g8 g g4 g8 g
    c4 c8 c c4 c8 c
}
}


\new Voice = "melody" {
    \relative c'' {
        c2 e4 e4
        f2. r4
        g2. a4
        e4 c2.
    }
}
\new Lyrics {
    \lyricsto "melody" {
        This is my song.
        I like to sing.
    }
}
>>
```

The image shows a musical score consisting of two staves. The top staff is a guitar tablature (TAB) staff, and the bottom staff is a standard musical staff with a treble clef. The TAB staff shows four chords: C (x o o), F (134211), G (o o o), and C (x o o). The musical staff has a common time signature and shows corresponding notes for each chord. Below the staffs, the lyrics "This is my song. I like to sing." are written.

Hammer on and pull off using chords

When using hammer-on or pull-off with chorded notes, only a single arc is drawn. However 'double arcs' are possible by setting the `doubleSlurs` property to `#t`.


```
\new TabStaff {
    \relative c' {
        % chord hammer-on and pull-off
        \set doubleSlurs = ##t
        <g' b>8( <a c> <g b>)
    }
}
```



Hammer on and pull off using voices

The arc of hammer-on and pull-off is upwards in voices one and three and downwards in voices two and four:


```
\new TabStaff {
  \relative c' {
    << { \voiceOne g2( a) }
    \\ { \voiceTwo a,( b) }
    >> \oneVoice
  }
}
```



Hammer on and pull off

Hammer-on and pull-off can be obtained using slurs.

```
\new TabStaff {
  \relative c' {
    d4( e\2)
    a( g)
  }
}
```



How to change fret diagram position

If you want to move the position of a fret diagram, for example, to avoid collision, or to place it between two notes, you have various possibilities:


- 1) modify #'padding or #'extra-offset values (as shown in the first snippet)
- 2) you can add an invisible voice and attach the fret diagrams to the invisible notes in that voice (as shown in the second example).

If you need to move the fret according with a rythmic position inside the bar (in the example, the third beat of the measure) the second example is better, because the fret is aligned with the third beat itself.

```
harmonies = \chordmode
{
  a8:13
  % THE FOLLOWING IS THE COMMAND TO MOVE THE CHORD NAME
  \once \override ChordNames.ChordName.extra-offset = #'(10 . 0)
  b8:13 s2.
  % THIS LINE IS THE SECOND METHOD
  s4 s4 b4:13
}

\score
```

```
{
  <<
    \context ChordNames \harmonies
    \context Staff
    {a8^\markup { \fret-diagram #"6-x;5-0;4-2;3-0;2-0;1-2;"} }
% THE FOLLOWING IS THE COMMAND TO MOVE THE FRET DIAGRAM
    \once \override TextScript.extra-offset = #'(10 . 0)
    b4.^~^\markup { \fret-diagram #"6-x;5-2;4-4;3-2;2-2;1-4;"} b4. a8\break
% HERE IS THE SECOND METHOD
    <<
      { a8 b4.^~ b4. a8}
      { s4 s4 s4^\markup { \fret-diagram #"6-x;5-2;4-4;3-2;2-2;1-4;"} }
    }
    >>
  }
  >>
}
```



Jazz combo template

This is quite an advanced template, for a jazz ensemble. Note that all instruments are notated in `\key c \major`. This refers to the key in concert pitch; the key will be automatically transposed if the music is within a `\transpose` section.

```
\header {
  title = "Song"
  subtitle = "(tune)"
  composer = "Me"
  meter = "moderato"
  piece = "Swing"
  tagline = \markup {
    \column {
      "LilyPond example file by Amelie Zapf,"
      "Berlin 07/07/2003"
    }
  }
}
```

```
%#(set-global-staff-size 16)
\include "english.ly"

%%%%%%%%%%%%% Some macros %%%%%%%%%%%%%%
sl = {
  \override NoteHead.style = #'slash
  \hide Stem
}
ns1 = {
  \revert NoteHead.style
  \undo \hide Stem
}
crOn = \override NoteHead.style = #'cross
crOff = \revert NoteHead.style

%% insert chord name style stuff here.

jazzChords = { }

%%%%%%%%%%%%% Keys'n'thangs %%%%%%%%%%%%%%
global = { \time 4/4 }

Key = { \key c \major }

% ##### Horns #####
% ----- Trumpet -----
trpt = \transpose c d \relative c' {
  \Key
  c1 | c | c |
}
trpHarmony = \transpose c' d {
  \jazzChords
}
trumpet = {
  \global
  \set Staff.instrumentName = #Trumpet"
  \clef treble
  <<
  \trpt
  >>
}

% ----- Alto Saxophone -----
alto = \transpose c a \relative c' {
  \Key
  c1 | c | c |
}
altoHarmony = \transpose c' a {
  \jazzChords
```

```
}

altoSax = {
    \global
    \set Staff.instrumentName = #"Alto Sax"
    \clef treble
    <<
        \alto
    >>
}

% ----- Baritone Saxophone -----
bari = \transpose c a' \relative c {
    \Key
    c1
    c1
    \sl
    d4^"Solo" d d d
    \nsl
}
bariHarmony = \transpose c' a \chordmode {
    \jazzChords s1 s d2:maj e:m7
}
bariSax = {
    \global
    \set Staff.instrumentName = #"Bari Sax"
    \clef treble
    <<
        \bari
    >>
}

% ----- Trombone -----
tbone = \relative c {
    \Key
    c1 | c | c
}
tboneHarmony = \chordmode {
    \jazzChords
}
trombone = {
    \global
    \set Staff.instrumentName = #"Trombone"
    \clef bass
    <<
        \tbone
    >>
}

% ##### Rhythm Section #####
% ----- Guitar -----
gtr = \relative c' {
```

```
\Key
c1
\sl
b4 b b b
\nsl
c1
}
gtrHarmony = \chordmode {
    \jazzChords
    s1 c2:min7+ d2:maj9
}
guitar = {
    \global
    \set Staff.instrumentName = #"Guitar"
    \clef treble
    <<
        \gtr
    >>
}

%% ----- Piano -----
rhUpper = \relative c' {
    \voiceOne
    \Key
    c1 | c | c
}
rhLower = \relative c' {
    \voiceTwo
    \Key
    e1 | e | e
}

lhUpper = \relative c' {
    \voiceOne
    \Key
    g1 | g | g
}
lhLower = \relative c {
    \voiceTwo
    \Key
    c1 | c | c
}

PianoRH = {
    \clef treble
    \global
    \set Staff.midiInstrument = #"acoustic grand"
    <<
        \new Voice = "one" \rhUpper
        \new Voice = "two" \rhLower
    >>
}
```

```
PianoLH = {
    \clef bass
    \global
    \set Staff.midiInstrument = #"acoustic grand"
    <<
        \new Voice = "one" \lhUpper
        \new Voice = "two" \lhLower
    >>
}

piano = {
<<
    \set PianoStaff.instrumentName = #"Piano"
    \new Staff = "upper" \PianoRH
    \new Staff = "lower" \PianoLH
>>
}

% ----- Bass Guitar -----
Bass = \relative c {
    \Key
    c1 | c | c
}
bass = {
    \global
    \set Staff.instrumentName = #"Bass"
    \clef bass
    <<
        \Bass
    >>
}

% ----- Drums -----
up = \drummode {
    \voiceOne
    hh4 <hh sn> hh <hh sn>
    hh4 <hh sn> hh <hh sn>
    hh4 <hh sn> hh <hh sn>
}
down = \drummode {
    \voiceTwo
    bd4 s bd s
    bd4 s bd s
    bd4 s bd s
}

drumContents = {
    \global
    <<
        \set DrumStaff.instrumentName = #"Drums"
        \new DrumVoice \up
        \new DrumVoice \down
    >>
}
```

```

>>
}

%%% It All Goes Together Here %%%%%%%

\score {
<<
\new StaffGroup = "horns" <<
\new Staff = "trumpet" \trumpet
\new Staff = "altosax" \altoSax
\new ChordNames = "barichords" \bariHarmony
\new Staff = "barisax" \bariSax
\new Staff = "trombone" \trombone
>>

\new StaffGroup = "rhythm" <<
\new ChordNames = "chords" \gtrHarmony
\new Staff = "guitar" \guitar
\new PianoStaff = "piano" \piano
\new Staff = "bass" \bass
\new DrumStaff \drumContents
>>
>>
\layout {
\context { \Staff \RemoveEmptyStaves }
\context {
\Score
\override BarNumber.padding = #3
\override RehearsalMark.padding = #2
skipBars = ##t
}
}
\midi { }
}

```

Song (tune)

moderato

Swing

Me

Trumpet

Alto Sax

Bari Sax

Trombone

Guitar

Piano

Bass

Drums

Laissez vibrer ties

Laissez vibrer ties have a fixed size. Their formatting can be tuned using 'tie-configuration'.

```
\relative c' {
    <c e g>4\laissezVibrer r <c f g>\laissezVibrer r
    <c d f g>4\laissezVibrer r <c d f g>4.\laissezVibrer r8

    <c d e f>4\laissezVibrer r
    \override LaissezVibrerTieColumn.tie-configuration
        = #`((-7 . ,DOWN)
              (-5 . ,DOWN)
              (-3 . ,UP)
              (-1 . ,UP))
    <c d e f>4\laissezVibrer r
}
```




Letter tablature formatting

Tablature can be formatted using letters instead of numbers.

```
music = \relative c {
    c4 d e f
    g4 a b c
    d4 e f g
}

<<
\new Staff {
    \clef "G_8"
    \music
}
\new TabStaff \with {
    tablatureFormat = #fret-letter-tablature-format
}
{
    \music
}
>>
```



Open string harmonics in tablature

This snippet demonstrates open-string harmonics

```

\harmonicByFret #9 e,\6
\harmonicByRatio #2/5 e,\6
\harmonicByFret #16 e,\6
\harmonicByRatio #3/5 e,\6
%fifth harmonic
\harmonicByFret #3 e,\6_\markup{"5th harm."}
\harmonicByRatio #1/6 e,\6
\break
%sixth harmonic
\harmonicByFret #2.7 e,\6_\markup{"6th harm."}
\harmonicByRatio #1/7 e,\6
%seventh harmonic
\harmonicByFret #2.3 e,\6_\markup{"7th harm."}
\harmonicByRatio #1/8 e,\6
%eighth harmonic
\harmonicByFret #2 e,\6_\markup{"8th harm."}
\harmonicByRatio #1/9 e,\6
}

\score {
  <<
  \new Staff {
    \new Voice {
      \clef "treble_8"
      \openStringHarmonics
    }
  }
  \new TabStaff {
    \new TabVoice {
      \openStringHarmonics
    }
  }
  >>
}

```

6

C

1st harm. 2nd harm. 3rd harm.

(12) (12) (7) (7) (19) (19) (5) (5) (24) (24)

6

#

4th harm. 5th harm.

(4) (4) (9) (9) (16) (16) (3) (3)

Placement of right-hand fingerings

It is possible to exercise greater control over the placement of right-hand fingerings by setting a specific property, as demonstrated in the following example. Note: you must use a chord construct


```
#(define RH rightHandFinger)
```

```
\relative c {
    \clef "treble_8"

    \set strokeFingerOrientations = #'(up down)
    <c-\RH #1 e-\RH #2 g-\RH #3 c-\RH #4 >4

    \set strokeFingerOrientations = #'(up right down)
    <c-\RH #1 e-\RH #2 g-\RH #3 c-\RH #4 >4

    \set strokeFingerOrientations = #'(left)
    <c-\RH #1 e-\RH #2 g-\RH #3 c-\RH #4 >2
}
```



Polyphony in tablature

Polyphony is created the same way in a TabStaff as in a regular staff.

```
upper = \relative c' {
    \time 12/8
    \key e \minor
    \voiceOne
    r4. r8 e, fis g16 b g e e' b c b a g fis e
}

lower = \relative c {
    \key e \minor
    \voiceTwo
    r16 e d c b a g4 fis8 e fis g a b c
}

\score {
    <<
    \new StaffGroup = "tab with traditional" <<
```

```
\new Staff = "guitar traditional" <<
    \clef "treble_8"
    \context Voice = "upper" \upper
    \context Voice = "lower" \lower
>>
\new TabStaff = "guitar tab" <<
    \context TabVoice = "upper" \upper
    \context TabVoice = "lower" \lower
>>
>>
>>
}
```

Slides in tablature

Slides can be typeset in both Staff and TabStaff contexts:

```
slides = {
    c'8\3(\glissando d'8\3)
    c'8\3\glissando d'8\3
    \hideNotes
    \grace { g16\glissando }
    \unHideNotes
    c'4\3
    \afterGrace d'4\3\glissando {
        \stemDown \hideNotes
        g16 }
    \unHideNotes
}

\score {
    <<
        \new Staff { \clef "treble_8" \slides }
        \new TabStaff { \slides }
    >>
    \layout {
        \context {
            \Score
            \override Glissando.minimum-length = #4
            \override Glissando.springs-and-rods =
                #ly:spanner::set-spacing-rods
            \override Glissando.thickness = #2
        }
    }
}
```

```

}
}

\new TabStaff {
    \relative c {
        \tabFullNotation
        g16 b d g b d g b
        \stemDown
        \override Beam.concaveness = #10000
        g,,16 b d g b d g b
    }
}

```

Stem and beam behavior in tablature

The direction of stems is controlled the same way in tablature as in traditional notation. Beams can be made horizontal, as shown in this example.

```

\new TabStaff {
    \relative c {
        \tabFullNotation
        g16 b d g b d g b
        \stemDown
        \override Beam.concaveness = #10000
        g,,16 b d g b d g b
    }
}

```

String number extender lines

Make an extender line for string number indications, showing that a series of notes is supposed to be played all on the same string.

```


stringNumberSpanner =
#(define-music-function (parser location StringNumber) (string?))
#{

    \override TextSpanner.style = #'solid
    \override TextSpanner.font-size = #-5
    \override TextSpanner.bound-details.left.stencil-align-dir-y = #CENTER
    \override TextSpanner.bound-details.left.text = \markup { \circle \number #StringNumber
#})

\relative c {
    \clef "treble_8"
    \stringNumberSpanner "5"
    \textSpannerDown
    a8\startTextSpan
    b c d e f\stopTextSpan
    \stringNumberSpanner "4"
}

```

```
g\startTextSpan a  
bes4 a g2\stopTextSpan  
}
```



Unfretted strings

Section “Unfretted string instruments” in *Notation Reference*


Changing \flageolet mark size

To make the \flageolet circle smaller use the following Scheme function.

```
smallFlageolet =
#(let ((m (make-articulation "flageolet")))
  (set! (ly:music-property m 'tweaks)
        (acons 'font-size -3
              (ly:music-property m 'tweaks)))
  m)

\layout { ragged-right = ##f }

\relative c' {
  d4^{\smallFlageolet_\markup { default size } d_\flageolet}
  c4^{\smallFlageolet_\markup { smaller } c_\smallFlageolet}
}
```



Creating slurs across voices

In some situations, it may be necessary to create slurs between notes from different voices.

The solution is to add invisible notes to one of the voices, using \hideNotes.

This example is measure 235 of the Ciaconna from Bach’s 2nd Partita for solo violin, BWV 1004.

```
\relative c' {
  <<
  {
    d16( a') s a s a[ s a] s a[ s a]
  }
  \\
  {
    \slurUp
    bes,16[ s e]( \hideNotes a)
    \unHideNotes f[( \hideNotes a)
    \unHideNotes fis]( \hideNotes a)
    \unHideNotes g[( \hideNotes a)
    \unHideNotes gis]( \hideNotes a)
  }
  >>
```

}



Dotted harmonics

Artificial harmonics using \harmonic do not show dots. To override this behavior, set the context property `harmonicDots`.


```
\relative c''' {
    \time 3/4
    \key f \major
    \set harmonicDots = ##t
    <bes f'\harmonic>2. ~
    <bes f'\harmonic>4. <a e'\harmonic>8( <gis dis'\harmonic> <g d'\harmonic>)
    <fis cis'\harmonic>2.
    <bes f'\harmonic>2.
}
```



Snap-pizzicato or Bartok pizzicato

A snap-pizzicato (also known as “Bartok pizzicato”) is a “strong pizzicato where the string is plucked vertically by snapping and rebounds off the fingerboard of the instrument” (Wikipedia). It is denoted by a circle with a vertical line going from the center upwards outside the circle.

```
\relative c' {
    c4\snappizzicato
    <c' e g>4\snappizzicato
    <c' e g>4^{\snappizzicato}
    <c, e g>4_\snappizzicato
}
```



String quartet template (simple)

This template demonstrates a simple string quartet. It also uses a \global section for time and key signatures

```
global= {
    \time 4/4
    \key c \major
}
```

```
violinOne = \new Voice \relative c' {
    \set Staff.instrumentName = #"Violin 1"

    c2 d
    e1

    \bar "|."
}

violinTwo = \new Voice \relative c' {
    \set Staff.instrumentName = #"Violin 2"

    g2 f
    e1

    \bar "|."
}

viola = \new Voice \relative c' {
    \set Staff.instrumentName = #"Viola"
    \clef alto

    e2 d
    c1

    \bar "|."
}

cello = \new Voice \relative c' {
    \set Staff.instrumentName = #"Cello"
    \clef bass

    c2 b
    a1

    \bar "|."
}

\score {
    \new StaffGroup <<
        \new Staff << \global \violinOne >>
        \new Staff << \global \violinTwo >>
        \new Staff << \global \viola >>
        \new Staff << \global \cello >>
    >>
    \layout { }
    \midi { }
}
```

String quartet template with separate parts

The “String quartet template” snippet produces a nice string quartet, but what if you needed to print parts? This new template demonstrates how to use the `\tag` feature to easily split a piece into individual parts.

You need to split this template into separate files; the filenames are contained in comments at the beginning of each file. `piece.ly` contains all the music definitions. The other files – `score.ly`, `vn1.ly`, `vn2.ly`, `vla.ly`, and `vlc.ly` – produce the appropriate part.

Do not forget to remove specified comments when using separate files!

```
%%%%% piece.ly
%%%%% (This is the global definitions file)
```

```
global= {
    \time 4/4
    \key c \major
}

Violinone = \new Voice { \relative c' {
    \set Staff.instrumentName = #"Violin 1 "
    c2 d e1

    \bar "|."
} %*****}
Violintwo = \new Voice { \relative c' {
    \set Staff.instrumentName = #"Violin 2 "
    g2 f e1

    \bar "|."
} %*****}
Viola = \new Voice { \relative c' {
    \set Staff.instrumentName = #"Viola "
    \clef alto
    e2 d c1

    \bar "|."
} %*****}
Cello = \new Voice { \relative c' {
    \set Staff.instrumentName = #"Cello "
    \clef bass
```

```
c2 b a1

\bar "|."} %*****  
  
music = {  
  <<  
    \tag #'score \tag #'vn1 \new Staff { << \global \Violinone >> }  
    \tag #'score \tag #'vn2 \new Staff { << \global \Violintwo>> }  
    \tag #'score \tag #'vla \new Staff { << \global \Viola>> }  
    \tag #'score \tag #'vlc \new Staff { << \global \Cello>> }  
  >>  
}  
  
%%% These are the other files you need to save on your computer  
  
%%%%% score.ly  
%%%%% (This is the main file)  
  
%%% uncomment the line below when using a separate file  
\include "piece.ly"  
#(set-global-staff-size 14)  
\score {  
  \new StaffGroup \keepWithTag #'score \music  
  \layout { }  
  \midi { }  
}  
  
%{ Uncomment this block when using separate files  
  
%%%%% vn1.ly  
%%%%% (This is the Violin 1 part file)  
  
\include "piece.ly"  
\score {  
  \keepWithTag #'vn1 \music  
  \layout { }  
}  
  
%%%%% vn2.ly  
%%%%% (This is the Violin 2 part file)  
  
\include "piece.ly"  
\score {  
  \keepWithTag #'vn2 \music  
  \layout { }  
}  
  
%%%%% vla.ly  
%%%%% (This is the Viola part file)
```

```
\include "piece.ly"
\score {
    \keepWithTag #'vla \music
    \layout { }
}

%%%%% vlc.ly
%%%%% (This is the Cello part file)

\include "piece.ly"
\score {
    \keepWithTag #'vlc \music
    \layout { }
}
%}
```

A musical score for four string instruments: Violin 1, Violin 2, Viola, and Cello. The score consists of four staves. Violin 1 (G clef) plays a eighth note followed by a quarter note. Violin 2 (G clef) plays a half note. Viola (F clef) plays a eighth note followed by a quarter note. Cello (C clef) plays a eighth note followed by a quarter note.

Winds


Section “Wind instruments” in *Notation Reference*

Changing the size of woodwind diagrams

The size and thickness of woodwind diagrams can be changed.

```
\relative c' {
  \textLengthOn
  c1^markup
    \woodwind-diagram
      #'piccolo
      #'()

  c^markup
    \override #'(size . 1.5) {
      \woodwind-diagram
        #'piccolo
        #'()
    }
  c^markup
    \override #'(thickness . 0.15) {
      \woodwind-diagram
        #'piccolo
        #'()
    }
}
```



Fingering symbols for wind instruments


Special symbols can be achieved by combining existing glyphs, which is useful for wind instruments.

```
centermarkup = {
  \once \override TextScript.self-alignment-X = #CENTER
  \once \override TextScript.X-offset =#(ly:make-simple-closure
    `(+,
     ,(ly:make-simple-closure (list
```

```

    ly:self-alignment-interface::centered-on-x-parent))
  ,(ly:make-simple-closure (list
    ly:self-alignment-interface::x-aligned-on-self))))
}
\score
{\relative c'
{
  g\open
  \once \override TextScript.staff-padding = #-1.0 \centermarkup
  g^\markup{\combine \musicglyph #"scripts.open" \musicglyph
  #"scripts.tenuto"}
  \centermarkup g^\markup{\combine \musicglyph #"scripts.open"
  \musicglyph #"scripts.stopped"}
  g\stopped
}
}

```



Flute slap notation

It is possible to indicate special articulation techniques such as a flute “tongue slap” by replacing the note head with the appropriate glyph.

```

slap =
#(define-music-function (parser location music) (ly:music?))
#{
  \override NoteHead.stencil =
  #(lambda (grob)
    (grob-interpret-markup grob
      (markup #:musicglyph "scripts.sforzato")))
  \override NoteHead.stem-attachment =
  #(lambda (grob)
    (let* ((thickness (ly:staff-symbol-line-thickness grob))
           (stem (ly:grob-object grob 'stem))
           (dir (ly:grob-property stem 'direction UP)))
      (cons 1 (+ (if (= dir DOWN)
                    0.5
                    0)
                  (/ thickness 2)))))

$music
\revert NoteHead.stencil
\revert NoteHead.stem-attachment
#})

\relative c' {
  c4 \slap c d r
  \slap { g4 a } b r
}

```




Graphical and text woodwind diagrams

In many cases, the keys other than the central column can be displayed by key name as well as by graphical means.

```
\relative c' {
    \textLengthOn
    c1^\markup
        \woodwind-diagram
            #'piccolo
            #'((cc . (one three))
                (lh . (gis))
                (rh . (ees)))

    c^\markup
        \override #'(graphical . #f) {
            \woodwind-diagram
                #'piccolo
                #'((cc . (one three))
                    (lh . (gis))
                    (rh . (ees)))
        }
    }
}
```



Recorder fingering chart

The following example demonstrates how fingering charts for wind instruments can be realized.

```
% range chart for paetzold contrabass recorder
```


```
centermarkup = {
    \once \override TextScript.self-alignment-X = #CENTER
    \once \override TextScript.X-offset =#(ly:make-simple-closure
        `(+,
        ,(ly:make-simple-closure (list
            ly:self-alignment-interface::centered-on-x-parent))
        ,(ly:make-simple-closure (list
            ly:self-alignment-interface::x-aligned-on-self)))))
}

\score {
    \new Staff \with {
```

```

\remove "Time_signature_engraver"
\omit Stem
\omit Flag
\consists "Horizontal_bracket_engraver"
}
{
\clef bass
\set Score.timing = ##f
f,1*1/4 \glissando
\clef violin
gis'1*1/4
\stemDown a'4^{\markup{1}}
\centermarkup
\once \override TextScript.padding = #2
bes'1*1/4_ {\markup{\override #'(baseline-skip . 1.7) \column
{ \fontsize #-5 \slashed-digit #0 \finger 1 \finger 2 \finger 3 \finger 4
\finger 5 \finger 6 \finger 7 } }
b'1*1/4
c''4^{\markup{1}}
\centermarkup
\once \override TextScript.padding = #2
cis''1*1/4
deh''1*1/4
\centermarkup
\once \override TextScript.padding = #2
\once \override Staff.HorizontalBracket.direction = #UP
e'''1*1/4_ {\markup{\override #'(baseline-skip . 1.7) \column
{ \fontsize #-5 \slashed-digit #0 \finger 1 \finger 2 \finger 4
\finger 5 } }\startGroup
f'''1*1/4^{\markup{2}}}\stopGroup
}
}

```



Woodwind diagrams key lists

The snippet below produces a list of all possible keys and key settings for woodwind diagrams as defined in ‘scm/define-woodwind-diagrams.scm’. The list will be displayed in the log file, but not in the music. If output to the console is wanted, omit the (current-error-port) from the commands.

```

#(print-keys-verbose 'piccolo (current-error-port))
#(print-keys-verbose 'flute (current-error-port))
#(print-keys-verbose 'flute-b-extension (current-error-port))

```

```

#(print-keys-verbose 'tin-whistle (current-error-port))
#(print-keys-verbose 'oboe (current-error-port))
#(print-keys-verbose 'clarinet (current-error-port))
#(print-keys-verbose 'bass-clarinet (current-error-port))
#(print-keys-verbose 'low-bass-clarinet (current-error-port))
#(print-keys-verbose 'saxophone (current-error-port))
#(print-keys-verbose 'soprano-saxophone (current-error-port))
#(print-keys-verbose 'alto-saxophone (current-error-port))
#(print-keys-verbose 'tenor-saxophone (current-error-port))
#(print-keys-verbose 'baritone-saxophone (current-error-port))
#(print-keys-verbose 'bassoon (current-error-port))
#(print-keys-verbose 'contrabassoon (current-error-port))

```

Woodwind diagrams listing

The following music shows all of the woodwind diagrams currently defined in LilyPond.

```

\relative c' {
    \textLengthOn
    c1^
    \markup {
        \center-column {
            'tin-whistle
            " "
            \woodwind-diagram
                #'tin-whistle
                #'()
        }
    }
}

c1^
\markup {
    \center-column {
        'piccolo
        " "
        \woodwind-diagram
            #'piccolo
            #'()
    }
}

c1^
\markup {
    \center-column {
        'flute
        " "
        \woodwind-diagram
            #'flute
            #'()
    }
}
c1^ \markup {
    \center-column {

```

```
' oboe
"
\woodwind-diagram
# ' oboe
# '()
}

}


c1^markup {
\center-column {
' clarinet
"
\woodwind-diagram
# ' clarinet
# '()
}
}

c1^markup {
\center-column {
'bass-clarinet
"
\woodwind-diagram
# 'bass-clarinet
# '()
}
}

c1^markup {
\center-column {
'saxophone
"
\woodwind-diagram
# 'saxophone
# '()
}
}

c1^markup {
\center-column {
'bassoon
"
\woodwind-diagram
# 'bassoon
# '()
}
}

c1^markup {
\center-column {
'contrabassoon
"
}
```



Ancient notation

Section “Ancient notation” in *Notation Reference*

Adding a figured bass above or below the notes

When writing a figured bass, you can place the figures above or below the bass notes, by defining the `BassFigureAlignmentPositioning.direction` property (exclusively in a `Staff` context). Choices are `#UP` (or `#1`), `#CENTER` (or `#0`) and `#DOWN` (or `#-1`).

This property can be changed as many times as you wish. Use `\once \override` if you don’t want the override to apply to the whole score.

```
bass = {
    \clef bass
    g4 b, c d
    e d8 c d2
}
continuo = \figuremode {
    <_>4 <6>4 <5/>4
    \override Staff.BassFigureAlignmentPositioning.direction = #UP
    \%bassFigureStaffAlignmentUp
    < _+ >4 <6>
    \set Staff.useBassFigureExtenders = ##t
    \override Staff.BassFigureAlignmentPositioning.direction = #DOWN
    \%bassFigureStaffAlignmentDown
    <4>4. <4>8 <_+>4
}
\score {
    <<
        \new Staff = bassStaff \bass
        \context Staff = bassStaff \continuo
    >>
}
```



Ancient fonts

Shown here are many (all?) of the symbols that are included in LilyPond’s support for ancient notation.

```
upperStaff = \new VaticanaStaff = "upperStaff" <<
    \context VaticanaVoice <<
        \transpose c c {
            \override NoteHead.style = #'vaticana.punctum
            \key es \major
            \clef "vaticana-fa2"
            c1 des e f ges
        }
        \override NoteHead.style = #'vaticana.inclinatum
    >>
}>>
```

```

a! b ces'
\bar "|"
% \break % 1 (8*1)

\override NoteHead.style = #'vaticana.quilisma
b! des'! ges! fes!
\breathe
\clef "vaticana-fa1"
\override NoteHead.style = #'vaticana.plica
es d
\override NoteHead.style = #'vaticana.reverse.plica
c d
\bar "|"
% \break %2 (8*1)

\override NoteHead.style = #'vaticana.punctum.cavum
es f
\override NoteHead.style = #'vaticana.lpes
g as
\override NoteHead.style = #'vaticana.upes
bes as
\override NoteHead.style = #'vaticana.vupes
g f
\override NoteHead.style = #'vaticana.linea.punctum
\once \override Staff.BarLine.bar-extent = #'(-1 . 1) \bar "|"
% \break % 3 (8*1)

es d
\override NoteHead.style = #'vaticana.epiphonus
c d
\override NoteHead.style = #'vaticana.cephalicus
es f

\override Staff.KeySignature.glyph-name-alist = #alteration-medicaea-glyph-name-alist
\override Staff.Accidental.glyph-name-alist = #alteration-medicaea-glyph-name-alist
\override Staff.Custos.style = #'medicaea
\override NoteHead.style = #'medicaea.punctum
\clef "medicaea-fa2"
ces des
\bar "|"
% \break % 4 (8*1)

e! f! ges
\clef "medicaea-do2"
\override NoteHead.style = #'medicaea.inclinatum
a! b! ces'
\override NoteHead.style = #'medicaea.virga
b! a!
\bar "|"
% \break % 5 (8*1)

ges fes

```

```

\clef "medicaea-fa1"
\override NoteHead.style = #'medicaea.rvirga
e des ces

\override Staff.KeySignature.glyph-name-alist = #alteration-hufnagel-glyph-name-alist
\override Staff.Accidental.glyph-name-alist = #alteration-hufnagel-glyph-name-alist
\override Staff.Custos.style = #'hufnagel
\override NoteHead.style = #'hufnagel.punctum
\clef "hufnagel-fa2"
ces des es
\bar "|"
% \break % 6 (8*1)

fes ges
\clef "hufnagel-do2"
\override NoteHead.style = #'hufnagel.lpes
as! bes! ces'
\override NoteHead.style = #'hufnagel.virga
bes! as!
\bar "|"
% \break % 7 (8*1)

ges! fes!
\clef "hufnagel-do-fa"
\override NoteHead.style = #'hufnagel.punctum
es! des ces des! es! fes!
\bar "||"
% \break % 8 (8*1)

s32*1
% \break % 12 (32*1)
}

>>
>>

lowerStaff = \new MensuralStaff = "lowerStaff" <-
\context MensuralVoice <-
\transpose c c {

\key a \major
cis'1 d'\breve gis'\breve e'\breve e \[ e'\longa fis'\longa \]
\set Staff.forceClef = ##t
\clef "neomensural-c2"
cis1
\bar "|"
% \break % 2 (16*1)

\[ g\breve dis''\longa \]
b\breve e \[ a\longa d\longa \]
\clef "petrucci-c2"
% \break % 4 (16*1)

```

```
fis1 ces1
\clef "petrucci-c2"
r\longa
\set Staff.forceClef = ##t
\clef "mensural-c2"
r\breve
\bar "|"
% \break % 5 (8*1)

r2
\clef "mensural-g"
r4 r8 r16 r16
\override NoteHead.style = #'mensural
\override Rest.style = #'mensural
\clef "petrucci-f"
c8 b, c16 b, c32 b, c64 b, c64 b,
d8 e d16 e d32 e d64 e d64 e
r\longa
\set Staff.forceClef = ##t
\clef "petrucci-f"
r\breve
\bar "|"
% \break % 6 (8*1)

r\breve
\clef "mensural-f"
r2 r4 r8 r16 r16

\set Staff.forceClef = ##t
\clef "mensural-f"
e\breve f g a1
\clef "mensural-g"
% \break % 7 (8*1)

\[ bes'!\longa a'!\longa c'!\longa \
e'1 d' c' d' \bar "|"
\bar "|"
% \break % 9 (16*1)


bes'!\longa fis'!1 as'!1 ges'!\longa % lig
\set Staff.forceClef = ##t
\clef "mensural-g"
e'2 d' c' \bar "|"
% \break % 11 (16*1)

\set Staff.forceClef = ##t
\clef "petrucci-g"
c'2 d' e' f'
\clef "petrucci-g"
g' as'! bes'! cis'!
bes'! as'! gis'! fis'!
\set Staff.forceClef = ##t
```

```
\clef "mensural-g"
es'! des'! cis'!1 \bar "||"
% \break % 12 (8*1)
}
>>
>>

\paper {
    line-thickness = #(/ staff-space 5.0)
}

\score {
    <<
        \upperStaff
        \lowerStaff
    >>
    \layout {
        indent = 0.0
        line-width = 17.25\cm
        \context {
            \Score
            timing = ##f
        }
        \context {
            \MensuralVoice
            \override NoteHead.style = #'neomensural
            \override Rest.style = #'neomensural
            \override Flag.style = #'mensural
            \override Stem.thickness = #1.0
        }
        \context {
            \MensuralStaff
            \revert BarLine.transparent
            \override KeySignature.glyph-name-alist = #alteration-mensural-glyph-name-alist
            clefGlyph = #"clefs.petrucci.c2"
        }
        \context {
            \VaticanaStaff
            \revert BarLine.transparent
            \override StaffSymbol.thickness = #2.0
            \override KeySignature.glyph-name-alist = #alteration-vaticana-glyph-name-alist
            \override Custos.neutral-position = #4
        }
    }
}
```



Ancient notation template – modern transcription of gregorian music

This example demonstrates how to do modern transcription of Gregorian music. Gregorian music has no measure, no stems; it uses only half and quarter note heads, and special marks, indicating rests of different length.

```
\include "gregorian.ly"
```

```
chant = \relative c' {
  \set Score.timing = ##f
  f4 a2 \divisioMinima
  g4 b a2 f2 \divisioMaior
  g4( f) f( g) a2 \finalis
}

verba = \lyricmode {
  Lo -- rem ip -- sum do -- lor sit a -- met
}

\score {
```

```
\new Staff <<
    \new Voice = "melody" \chant
    \new Lyrics = "one" \lyricsto melody \verba
>>
\layout {
    \context {
        \Staff
        \remove "Time_signature_engraver"
        \remove "Bar_engraver"
        \hide Stem
    }
    \context {
        \Voice
        \override Stem.length = #0
    }
    \context {
        \Score
        barAlways = ##t
    }
}
}
```



Ancient notation template – modern transcription of mensural music

When transcribing mensural music, an incipit at the beginning of the piece is useful to indicate the original key and tempo. While today musicians are used to bar lines in order to faster recognize rhythmic patterns, bar lines were not yet invented during the period of mensural music; in fact, the meter often changed after every few notes. As a compromise, bar lines are often printed between the staves rather than on the staves.

```
global = {
    \set Score.skipBars = ##t

    % incipit
    \once \hide Score.SystemStartBracket
    % Set tight spacing
    \override Score.SpacingSpanner.spacing-increment = #1.0
    \key f \major
    \time 2/2
    \once \override Staff.TimeSignature.style = #'neomensural
    \override Voice.NoteHead.style = #'neomensural
    \override Voice.Rest.style = #'neomensural
    \set Staff.printKeyCancellation = ##f
    \codaOn % turn off bar lines
    \skip 1*10
    \once \override Staff.BarLine.transparent = ##f
    \bar "||"
```

```

\skip 1*1 % need this extra \skip such that clef change comes
          % after bar line
\bar ""

% main
\cadenzaOff % turn bar lines on again
\once \override Staff.Clef.full-size-change = ##t
\set Staff.forceClef = ##t
\key g \major
\time 4/4
\override Voice.NoteHead.style = #'default
\override Voice.Rest.style = #'default

% Setting printKeyCancellation back to #t must not
% occur in the first bar after the incipit. Dto. for forceClef.
% Therefore, we need an extra \skip.
\skip 1*1
\set Staff.printKeyCancellation = ##t
\set Staff.forceClef = ##f

\skip 1*7 % the actual music

% let finis bar go through all staves
\override Staff.BarLine.transparent = ##f

% finis bar
\bar "|."
}

discantusNotes = {
\transpose c' c'' {
  \set Staff.instrumentName = #"Discantus"
  % incipit
  \clef "neomensural-c1"
  c'1. s2 % two bars
  \skip 1*8 % eight bars
  \skip 1*1 % one bar

  % main
  \clef "treble"
  d'2. d'4 |
  b e' d'2 |
  c'4 e'4.( d'8 c' b |
  a4) b a2 |
  b4.( c'8 d'4) c'4 |
  \once \hide NoteHead c'1 |
  b\breve |
}
}

discantusLyrics = \lyricmode {

```

```
% incipit
IV-

% main
Ju -- bi -- |
la -- te De -- |
o, om --
nis ter -- |
ra, __ om- |
"..." |
-us. |

}

altusNotes = {
  \transpose c' c'' {
    \set Staff.instrumentName = #"Altus"

    % incipit
    \clef "neomensural-c3"
    r1      % one bar
    f1. s2  % two bars
    \skip 1*7 % seven bars
    \skip 1*1 % one bar

    % main
    \clef "treble"
    r2 g2. e4 fis g | % two bars
    a2 g4 e |
    fis g4.( fis16 e fis4) |
    g1 |
    \once \hide NoteHead g1 |
    g\breve |
  }
}

altusLyrics = \lyricmode {
  % incipit
  IV-

  % main
  Ju -- bi -- la -- te | % two bars
  De -- o, om -- |
  nis ter -- ra, |
  "..." |
  -us. |

tenorNotes = {
  \transpose c' c' {
    \set Staff.instrumentName = #"Tenor"

    % incipit
  }
}
```

```

\clef "neomensural-c4"
r\longa    % four bars
r\breve    % two bars
r1         % one bar
c'1. s2    % two bars
\skip 1*1 % one bar
\skip 1*1 % one bar

% main
\clef "treble_8"
R1 |
R1 |
R1 |
r2 d'2. d'4 b e' | % two bars
\once \hide NoteHead e'1 |
d'\breve |
}
}

tenorLyrics = \lyricmode {
  % incipit
  IV-

  % main
  Ju -- bi -- la -- te | % two bars
  "... |"
  -us. |
}

bassusNotes = {
  \transpose c' c' {
    \set Staff.instrumentName = #"Bassus"

    % incipit
    \clef "bass"
    r\maxima % eight bars
    f1. s2    % two bars
    \skip 1*1 % one bar

    % main
    \clef "bass"
    R1 |
    R1 |
    R1 |
    R1 |
    g2. e4 |
    \once \hide NoteHead e1 |
    g\breve |
  }
}

bassusLyrics = \lyricmode {

```

```
% incipit
IV-
% main
Ju -- bi- |
"..." |
-us. |
}

\score {
  \new StaffGroup = choirStaff <<
    \new Voice =
      "discantusNotes" << \global \discantusNotes >>
    \new Lyrics =
      "discantusLyrics" \lyricsto discantusNotes { \discantusLyrics }
  \new Voice =
    "altusNotes" << \global \altusNotes >>
  \new Lyrics =
    "altusLyrics" \lyricsto altusNotes { \altusLyrics }
  \new Voice =
    "tenorNotes" << \global \tenorNotes >>
  \new Lyrics =
    "tenorLyrics" \lyricsto tenorNotes { \tenorLyrics }
  \new Voice =
    "bassusNotes" << \global \bassusNotes >>
  \new Lyrics =
    "bassusLyrics" \lyricsto bassusNotes { \bassusLyrics }
  >>
  \layout {
    \context {
      \Score
        % no bars in staves
        \hide BarLine
        % incipit should not start with a start delimiter
        \remove "System_start_delimiter_engraver"
    }
    \context {
      \Voice
        % no slurs
        \hide Slur
        % The command below can be commented out in
        % short scores, but especially for large scores you
        % will typically yield better line breaking and improve
        % overall spacing if you do not comment the command out.
        \remove "Forbid_line_break_engraver"
    }
}
}
```

}

Discantus Altus Tenor Bassus

IV- IV- IV- IV-

Ju - bi - la - te De -
Ju - bi - la - te
- - - -

3

o, om - nis ter - ra, om- ... -us.
De - o, om - nis ter - ra, ... -us.
Ju - bi - la - te ... -us.

Ju - bi - ... -us.

Ancient time signatures

Time signatures may also be engraved in an old style.

{

```
\override Staff.TimeSignature.style = #'neomensural
s1
```

}



Chant or psalms notation

This form of notation is used for the chant of the Psalms, where verses aren't always the same length.

```
stemOff = \hide Staff.Stem
stemOn = \undo \stemOff
```

```
\score {
  \new Staff \with { \remove "Time_signature_engraver" }
  {
    \key g \minor
    \cadenzaOn
    \stemOff a'\breve bes'4 g'4
    \stemOn a'2 \bar "||"
    \stemOff a'\breve g'4 a'4
    \stemOn f'2 \bar "||"
    \stemOff a'\breve \markup { \italic flexe }
    \stemOn g'2 \bar "||"
  }
}
```



Custodes

Custodes may be engraved in various styles.

```
\layout { ragged-right = ##t }



\new Staff \with { \consists "Custos_engraver" } \relative c' {
  \override Staff.Custos.neutral-position = #4


  \override Staff.Custos.style = #'hufnagel
  c1^"hufnagel" \break
  <d a' f'>1

  \override Staff.Custos.style = #'medicaea
  c1^"medicaea" \break
  <d a' f'>1

  \override Staff.Custos.style = #'vaticana
  c1^"vaticana" \break
  <d a' f'>1

  \override Staff.Custos.style = #'mensural
  c1^"mensural" \break
  <d a' f'>1
}
```





Incipit

Incipits can be added using the instrument name grob, but keeping separate the instrument name definition and the incipit definition.

```
\set Score.skipBars = ##t
\key g \major
\time 4/4

% the actual music
\skip 1*8

% let finis bar go through all staves
\override Staff.BarLine.transparent = ##f

% finis bar
\bar "|."
}

discantusIncipit = <<
  \new MensuralVoice = "discantusIncipit" <<
    \repeat unfold 9 { s1 \noBreak }
  {
    \clef "neomensural-c1"
    \key f \major
    \time 2/2
    c''1.
  }
>>
  \new Lyrics \lyricsto discantusIncipit { IV- }
>>

discantusNotes = {
  \transpose c' c'' {
    \clef "treble"
    d'2. d'4 |
    b e' d'2 |
    c'4 e'4.( d'8 c' b |
    a4) b a2 |
    b4.( c'8 d'4) c'4 |
    \once \hide NoteHead
    c'1 |
    b\breve |
  }
}

discantusLyrics = \lyricmode {
  Ju -- bi -- |
  la -- te De -- |
  o, om --
  nis ter -- |
  ra, __ om- |
  "... |
  -us. |
}

altusIncipit = <<
```

```

\new MensuralVoice = "altusIncipit" <<
  \repeat unfold 9 { s1 \noBreak }
{
  \clef "neomensural-c3"
  \key f \major
  \time 2/2
  r1 f'1.
}
>>
\new Lyrics \lyricsto altusIncipit { IV- }
>>

altusNotes = {
  \transpose c' c'' {
    \clef "treble"
    % two measures
    r2 g2. e4 fis g |
    a2 g4 e |
    fis g4.( fis16 e fis4) |
    g1 |
    \once \hide NoteHead
    g1 |
    g\breve |
  }
}

altusLyrics = \lyricmode {
  % two measures
  Ju -- bi -- la -- te |
  De -- o, om -- |
  nis ter -- ra, |
  "... |
  -us. |
}

tenorIncipit = <<
\new MensuralVoice = "tenorIncipit" <<
  \repeat unfold 9 { s1 \noBreak }
{
  \clef "neomensural-c4"
  \key f \major
  \time 2/2
  r\longa
  r\breve
  r1 c'1.
}
>>
\new Lyrics \lyricsto tenorIncipit { IV- }
>>

tenorNotes = {
  \transpose c' c' {

```

```
\clef "treble_8"
R1 |
R1 |
R1 |
% two measures
r2 d'2. d'4 b e' |
\once \hide NoteHead
e'1 |
d'\breve |
}
}

tenorLyrics = \lyricmode {
% two measures
Ju -- bi -- la -- te |
"..." |
-us.
}

bassusIncipit = <<
\new MensuralVoice = "bassusIncipit" <<
\repeat unfold 9 { s1 \noBreak }
{
\clef "bass"
\key f \major
\time 2/2
%% incipit
r\maxima
f1.
}
>>
\new Lyrics \lyricsto bassusIncipit { IV- }
>>

bassusNotes = {
\transpose c' c' {
\clef "bass"
R1 |
R1 |
R1 |
R1 |
g2. e4 |
\once \hide NoteHead
e1 |
g\breve |
}
}

bassusLyrics = \lyricmode {
Ju -- bi- |
"..." |
-us.
```

```

}

\score {
  <<
  \new StaffGroup = choirStaff <<
    \new Voice = "discantusNotes" <<
      \global
      \set Staff.instrumentName = #"Discantus"
      \incipit \discantusIncipit
      \discantusNotes
    >>
    \new Lyrics = "discantusLyrics" \lyricsto discantusNotes { \discantusLyrics }■
  \new Voice = "altusNotes" <<
    \global
    \set Staff.instrumentName = #"Altus"
    \incipit \altusIncipit
    \altusNotes
  >>
  \new Lyrics = "altusLyrics" \lyricsto altusNotes { \altusLyrics }
  \new Voice = "tenorNotes" <<
    \global
    \set Staff.instrumentName = #"Tenor"
    \incipit \tenorIncipit
    \tenorNotes
  >>
  \new Lyrics = "tenorLyrics" \lyricsto tenorNotes { \tenorLyrics }
  \new Voice = "bassusNotes" <<
    \global
    \set Staff.instrumentName = #"Bassus"
    \incipit \bassusIncipit
    \bassusNotes
  >>
  \new Lyrics = "bassusLyrics" \lyricsto bassusNotes { \bassusLyrics }
>>
>>
\layout {
  \context {
    \Score
    %% no bar lines in staves or lyrics
    \hide BarLine
  }
  %% the next two instructions keep the lyrics between the bar lines
  \context {
    \Lyrics
    \consists "Bar_engraver"
    \consists "Separating_line_group_engraver"
  }
  \context {
    \Voice
    %% no slurs
    \hide Slur
    %% Comment in the below "\remove" command to allow line
  }
}

```

```
%% breaking also at those bar lines where a note overlaps
%% into the next measure. The command is commented out in this
%% short example score, but especially for large scores, you
%% will typically yield better line breaking and thus improve
%% overall spacing if you comment in the following command.
%%\remove "Forbid_line_break_engraver"
}

indent = 6\cm
incipit-width = 4\cm
}

}
```


The musical score consists of four staves representing different voices: Discantus (top), Altus, Tenor, and Bassus (bottom). The score is divided into two systems by a vertical brace. In the first system, the Discantus staff begins with a common time signature (C) and moves to a 2/4 time signature. The lyrics 'Ju - bi - la - te' are written above the notes. The Altus, Tenor, and Bassus staves also follow this pattern. In the second system, the Discantus staff begins with a common time signature (C) and moves to a 2/4 time signature. The lyrics 'o, om - nis ter - ra,' are written above the notes. The Altus, Tenor, and Bassus staves also follow this pattern. Vertical bar lines are placed between the staves to indicate measures.

Mensurstriche layout (bar lines between the staves)

The mensurstriche-layout where the bar lines do not show on the staves but between staves can be achieved with a `StaffGroup` instead of a `ChoirStaff`. The bar line on staves is blanked out by setting the `transparent` property.

```
global = {
  \hide Staff.BarLine
  s1 s
  % the final bar line is not interrupted
```

```
\undo \hide Staff.BarLine
\bar "|."
}
\new StaffGroup \relative c' {
  <<
    \new Staff { << \global { c1 c } >> }
    \new Staff { << \global { c c } >> }
  >>
}
```



Rest styles

Rests may be used in various styles.

```
\layout {
  indent = 0
  \context {
    \Staff
    \remove "Time_signature_engraver"
  }
}

\new Staff \relative c {
  \cadenzaOn
  \override Staff.Rest.style = #'mensural
  r\maxima^\markup \typewriter { mensural }
  r\longa r\breve r1 r2 r4 r8 r16 s32 s64 s128 s128
  \bar ""

  \override Staff.Rest.style = #'neomensural
  r\maxima^\markup \typewriter { neomensural }
  r\longa r\breve r1 r2 r4 r8 r16 s32 s64 s128 s128
  \bar ""

  \override Staff.Rest.style = #'classical
  r\maxima^\markup \typewriter { classical }
  r\longa r\breve r1 r2 r4 r8 r16 r32 r64 r128 s128
  \bar ""

  \override Staff.Rest.style = #'default
  r\maxima^\markup \typewriter { default }
  r\longa r\breve r1 r2 r4 r8 r16 r32 r64 r128 s128
}
```

The image shows four staves of music notation, each with a treble clef and four horizontal lines representing a staff. The first staff, labeled 'mensural', contains vertical bar lines and short horizontal dashes of varying lengths. The second staff, labeled 'neomensural', contains vertical bar lines and short horizontal dashes. The third staff, labeled 'classical', contains vertical bar lines and various note heads (circles, triangles, diamonds) with stems. The fourth staff, labeled 'default', contains vertical bar lines and note heads with stems.

Transcription of Ancient music with incipit

As a workaround to get real incipits which are independent from the main score these are included as a markup into the field normally used for the instrument name. As for now lyrics can only be added as a direct markup. It doesn't unfortunately conform with the spacing of the main lyrics.

```
global = {
    \set Score.skipBars = ##t
    \key g \major
    \time 4/4
    %make the staff lines invisible on staves
    \hide Staff.BarLine
    \skip 1*8 % the actual music
    % let finis bar go through all staves
    \override Staff.BarLine.transparent = ##f
    % finis bar
    \bar "|."
}

discantusNotes = {
    \transpose c' c'' {
        \clef treble
        d'2. d'4 |
        b e' d'2 |
        c'4 e'4. ( d'8 c' b |
        a4) b a2 |
        b4. ( c'8 d'4) c'4 |
        \once \hide NoteHead c'1 |
        b\breve |
    }
}

discantusLyrics = \lyricmode {
    Ju -- bi -- |
    la -- te De -- |
    o, om --
    nis ter -- |
```

```
ra, -- om- |
"..." |
-us. |
}

altusNotes = {
  \transpose c' c'' {
    \clef treble
    r2 g2. e4 fis g | % two bars
    a2 g4 e |
    fis g4.( fis16 e fis4) |
    g1 |
    \once \hide NoteHead g1 |
    g\breve |
  }
}

altusLyrics = \lyricmode {
  Ju -- bi -- la -- te | % two bars
  De -- o, om -- |
  nis ter -- ra, |
  "..." |
  -us. |
}

tenorNotes = {
  \transpose c' c' {
    \clef "treble_8"
    R1 |
    R1 |
    R1 |
    r2 d'2. d'4 b e' | % two bars
    \once \hide NoteHead e'1 |
    d'\breve |
  }
}

tenorLyrics = \lyricmode {
  Ju -- bi -- la -- te | % two bars
  "..." |
  -us.
}

bassusNotes = {
  \transpose c' c' {
    \clef bass
    R1 |
    R1 |
    R1 |
    R1 |
    g2. e4 |
    \once \hide NoteHead e1 |
```

```
g\breve |  
}  
}  
  
bassusLyrics = \lyricmode {  
    Ju -- bi- |  
    "... " |  
    -us.  
}  
  
incipitDiscantus = \markup {  
    \score {  
        {  
            \set Staff.instrumentName = #"Discantus"  
            \override NoteHead.style = #'neomensural  
            \override Rest.style = #'neomensural  
            \override Staff.TimeSignature.style = #'neomensural  
            \cadenzaOn  
            \clef "neomensural-c1"  
            \key f \major  
            \time 2/2  
            c'1._"IV-" s2 %two bars  
            \skip 1*8 % eight bars  
        }  
        \layout {  
            \context {  
                \Voice  
                \remove "Ligature_bracket_engraver"  
                \consists "Mensural_ligature_engraver"  
            }  
            line-width = 4.5\cm  
        }  
    }  
}  
  
incipitAltus = \markup {  
    \score {  
        {  
            \set Staff.instrumentName = #"Altus"  
            \override NoteHead.style = #'neomensural  
            \override Rest.style = #'neomensural  
            \override Staff.TimeSignature.style = #'neomensural  
            \cadenzaOn  
            \clef "neomensural-c3"  
            \key f \major  
            \time 2/2  
            r1 % one bar  
            f'1._"IV-" s2 % two bars  
            \skip 1*7 % seven bars  
        }  
        \layout {  
            \context {
```

```
\Voice
  \remove "Ligature_bracket_engraver"
  \consists "Mensural_ligature_engraver"
}
line-width = 4.5\cm
}
}
}

incipitTenor = \markup {
  \score {
    {
      \set Staff.instrumentName = #"Tenor"
      \override NoteHead.style = #'neomensural
      \override Rest.style = #'neomensural
      \override Staff.TimeSignature.style = #'neomensural
      \cadenzaOn
      \clef "neomensural-c4"
      \key f \major
      \time 2/2
      r\longa % four bars
      r\breve % two bars
      r1 % one bar
      c'1._"IV-" s2 % two bars
      \skip 1 % one bar
    }
    \layout {
      \context {
        \Voice
        \remove "Ligature_bracket_engraver"
        \consists "Mensural_ligature_engraver"
      }
      line-width = 4.5\cm
    }
  }
}

incipitBassus = \markup {
  \score {
    {
      \set Staff.instrumentName = #"Bassus"
      \override NoteHead.style = #'neomensural
      \override Rest.style = #'neomensural
      \override Staff.TimeSignature.style = #'neomensural
      \cadenzaOn
      \clef "bass"
      \key f \major
      \time 2/2
      % incipit
      r\maxima % eight bars
      f1._"IV-" s2 % two bars
    }
  }
}
```

```

\layout {
  \context {
    \Voice
    \remove "Ligature_bracket_engraver"
    \consists "Mensural_ligature_engraver"
  }
  line-width = 4.5\cm
}
}

%StaffGroup is used instead of ChoirStaff to get bar lines between systems
\score {
  <<
  \new StaffGroup = choirStaff <<
  \new Voice = "discantusNotes" <<
  \global
  \set Staff.instrumentName = \incipitDiscantus
  \discantusNotes
  >>
  \new Lyrics = "discantusLyrics" \lyricsto discantusNotes { \discantusLyrics }■

  \new Voice = "altusNotes" <<
  \global
  \set Staff.instrumentName = \incipitAltus
  \altusNotes
  >>
  \new Lyrics = "altusLyrics" \lyricsto altusNotes { \altusLyrics }

  \new Voice = "tenorNotes" <<
  \global
  \set Staff.instrumentName = \incipitTenor
  \tenorNotes
  >>
  \new Lyrics = "tenorLyrics" \lyricsto tenorNotes { \tenorLyrics }

  \new Voice = "bassusNotes" <<
  \global
  \set Staff.instrumentName = \incipitBassus
  \bassusNotes
  >>
  \new Lyrics = "bassusLyrics" \lyricsto bassusNotes { \bassusLyrics }
  %Keep the bass lyrics outside of the staff group to avoid bar lines
  %between the lyrics.
  >>

  \layout {
    \context {
      \Score
      % no bars in staves
      \hide BarLine
    }
  }
}

```

```

}

% the next three instructions keep the lyrics between the bar lines
\context {
  \Lyrics
  \consists "Bar_engraver"
  \hide BarLine
}

\context {
  \StaffGroup
  \consists "Separating_line_group_engraver"
}

\context {
  \Voice
  % no slurs
  \hide Slur
  % Comment in the below "\remove" command to allow line
  % breaking also at those barlines where a note overlaps
  % into the next bar. The command is commented out in this
  % short example score, but especially for large scores, you
  % will typically yield better line breaking and thus improve
  % overall spacing if you comment in the following command.
  %\remove "Forbid_line_break_engraver"
}

indent = 5\cm
}
}
}

```

Discantus

Altus

Tenor

Bassus

Vertical line as a baroque articulation mark

This short vertical line placed above the note is commonly used in baroque music. Its meaning can vary, but generally indicates notes that should be played with more “weight”. The following example demonstrates how to achieve such a notation.

```
upline =
#(let ((m (make-articulation "stopped")))
  (set! (ly:music-property m 'tweaks)
        (acons 'font-size 3
              (acons 'stencil (lambda (grob)
                                (grob-interpret-markup
                                  grob
                                  (make-draw-line-markup '(0 . 1)))))
              (ly:music-property m 'tweaks))))
m)
```

```
\relative c' {
  a'4^ \upline a( c d')_ \upline
}
```



World music


Section “World music” in *Notation Reference*

Arabic improvisation

For improvisations or taqasim which are temporarily free, the time signature can be omitted and `\cadenzaOn` can be used. Adjusting the accidental style might be required, since the absence of bar lines will cause the accidental to be marked only once. Here is an example of what could be the start of a hijaz improvisation:

```
\include "arabic.ly"
```

```
\relative sol' {
    \key re \kurd
    \accidentalStyle forget
    \cadenzaOn
    sol4 sol sol sol fad mib sol1 fad8 mib re4. r8 mib1 fad sol
}
```



Makam example

Makam is a type of melody from Turkey using 1/9th-tone microtonal alterations. Consult the initialization file ‘ly/makam.ly’ for details of pitch names and alterations.

```
% Initialize makam settings
\include "makam.ly"
```

```
\relative c' {
    \set Staff.keySignature = #`((6 . ,(- KOMA)) (3 . ,BAKIYE))
    c4 cc db fk
    gbm4 gfc gfb efk
    fk4 db cc c
}
```




Printing text from right to left

It is possible to print text from right to left in a markup object, as demonstrated here.

```
{
  b1^markup {
    \line { i n g i r u m i m u s n o c t e }
  }
  f'_markup {
    \override #'(text-direction . -1)
    \line { i n g i r u m i m u s n o c t e }
  }
}
```

{



Contexts and engravers

Section “Changing defaults” in *Notation Reference*

Section “Contexts and engravers” in *Learning Manual*

Adding a figured bass above or below the notes

When writing a figured bass, you can place the figures above or below the bass notes, by defining the `BassFigureAlignmentPositioning.direction` property (exclusively in a `Staff` context). Choices are `#UP` (or `#1`), `#CENTER` (or `#0`) and `#DOWN` (or `#-1`).

This property can be changed as many times as you wish. Use `\once \override` if you don’t want the override to apply to the whole score.

```
bass = {
    \clef bass
    g4 b, c d
    e d8 c d2
}
continuo = \figuremode {
    <_>4 <6>4 <5/>4
    \override Staff.BassFigureAlignmentPositioning.direction = #UP
    \%bassFigureStaffAlignmentUp
    < _+ >4 <6>
    \set Staff.useBassFigureExtenders = ##t
    \override Staff.BassFigureAlignmentPositioning.direction = #DOWN
    \%bassFigureStaffAlignmentDown
    <4>4. <4>8 <_+>4
}
\score {
    <<
        \new Staff = bassStaff \bass
        \context Staff = bassStaff \continuo
    >>
}
```






Adding an extra staff at a line break

When adding a new staff at a line break, some extra space is unfortunately added at the end of the line before the break (to fit in a key signature change, which will never be printed anyway). The workaround is to add a setting of `Staff.explicitKeySignatureVisibility` as is shown in the example.

```
\score {
    \new StaffGroup \relative c' {
        \new Staff
        \key f \major
        c1 c^"Unwanted extra space" \break
        << { c1 | c }
```

```
\new Staff {
    \key f \major
    \once \omit Staff.TimeSignature
    c1 | c
}
>>
c1 | c^"Fixed here" \break
<< { c1 | c }
\new Staff {
    \once \set Staff.explicitKeySignatureVisibility = #end-of-line-invisible
    \key f \major
    \once \omit Staff.TimeSignature
    c1 | c
}
>>
}
}
```



Adding an extra staff


An extra staff can be added (possibly temporarily) after the start of a piece.

```
\score {
<<
\new Staff \relative c' {
    c1 | c | c | c | c
}
\new StaffGroup \relative c' {
    \new Staff {
        c1 | c
        <<
        {
            c1 | d
    }
}
}
```

```

}
\new Staff {
    \once \omit Staff.TimeSignature
    c1 | b
}
>>
c1
}
}
>>
}
}

```



Automatically changing the stem direction of the middle note based on the melody

LilyPond can alter the stem direction of the middle note on a staff so that it follows the melody, by adding the `Melody_engraver` to the `Voice` context and overriding the `neutral-direction` of Stem.

```

\relative c' {
    \time 3/4
    \autoBeamOff
    a8 b g f b g |
    c b d c b c
}

\layout {
    \context {
        \Voice
        \consists "Melody_engraver"
        \override Stem.neutral-direction = #'()
    }
}

```



Centered measure numbers


Scores of large ensemble works often have bar numbers placed beneath the system, centered horizontally on the measure's extent. This snippet shows how the `Measure_counter_engraver`

may be used to simulate this notational practice. Here, the engraver has been added to a `Dynamics` context.

```
\layout {
  \context {
    \Dynamics
    \consists #Measure_counter_engraver
    \override MeasureCounter.direction = #DOWN
    \override MeasureCounter.font-encoding = #'latin1
    \override MeasureCounter.font-shape = #'italic
    % to control the distance of the Dynamics context from the staff:
    \override VerticalAxisGroup.nonstaff-relatedstaff-spacing.padding = #2
  }
  \context {
    \Score
    \remove "Bar_number_engraver"
  }
}

pattern = \repeat unfold 7 { c'4 d' e' f' }

\new StaffGroup <<
  \new Staff {
    \pattern
  }
  \new Staff {
    \pattern
  }
  \new Dynamics {
    \startMeasureCount
    s1*7
    \stopMeasureCount
  }
>>
```



Centering markup on note heads automatically

For technical reasons, text scripts attached to note heads cannot easily be centered on a note head's width, unlike articulations.

Instead of using trial-and-error offset tweaks, this snippet uses a Scheme engraver to reset the horizontal parent of each markup to a `NoteColumn`. This also allows text to follow note heads which have been shifted via `force-hshift`.

```
 #(define (Text_align_engraver ctx)
  (let ((scripts '()))
```


```

(note-column #f))
(make-engraver
(acknowledgers
((note-column-interface trans grob source)
;; cache NoteColumn in this Voice context
(set! note-column grob))
((text-script-interface trans grob source)
;; whenever a TextScript is acknowledged,
;; add it to `scripts' list
(set! scripts (cons grob scripts)))
((stop-translation-timestep trans)
;; if any TextScript grobs exist,
;; set NoteColumn as X-parent
(for-each (lambda (script)
            (set! (ly:grob-parent script X) note-column))
          scripts)
;; clear scripts ready for next timestep
(set! scripts '()))))

\layout {
\context {
\Voice
\consists #Text_align_engraver
\override TextScript.X-offset =
#ly:self-alignment-interface::aligned-on-x-parent
\override TextScript.self-alignment-X = #CENTER
}
}

\new Staff <<
\relative c' {
\override NoteColumn.force-hshift = #3
c1-\markup { \arrow-head #Y #DOWN ##t }
}
\\
\relative c' {
a4 a-\markup { \huge ^ } a a
}
>>

```



Changing MIDI output to one channel per voice

When outputting MIDI, the default behavior is for each staff to represent one MIDI channel, with all the voices on a staff amalgamated. This minimizes the risk of running out of MIDI channels, since there are only 16 available per MIDI port, and most devices support only one port.

However, by moving the `Staff_performer` to the `Voice` context, each voice on a staff can have its own MIDI channel, as is demonstrated by the following example: despite being on the same staff, two MIDI channels are created, each with a different `midiInstrument`.

```
\score {
  \new Staff <<
    \new Voice \relative c''' {
      \set midiInstrument = #"flute"
      \voiceOne
      \key g \major
      \time 2/2
      r2 g-"Flute" ~
      g fis ~
      fis4 g8 fis e2 ~
      e4 d8 cis d2
    }
    \new Voice \relative c' {
      \set midiInstrument = #"clarinet"
      \voiceTwo
      b1-"Clarinet"
      a2. b8 a
      g2. fis8 e
      fis2 r
    }
  >>
  \layout { }
  \midi {
    \context {
      \Staff
      \remove "Staff_performer"
    }
    \context {
      \Voice
      \consists "Staff_performer"
    }
    \tempo 2 = 72
  }
}
```



Changing time signatures inside a polymetric section using `\scaleDurations`

```
\layout {
  \context {
    \Score
    \remove "Timing_translator"
    \remove "Default_bar_line_engraver"
```

```

}
\context {
  \Staff
  \consists "Timing_translator"
  \consists "Default_bar_line_engraver"
}
}

<<
\new Staff {
  \scaleDurations 8/5 {
    \time 6/8
    \set Timing.measureLength = #(ly:make-moment 6/5)
    b8 b b b b b
    \time 2/4
    \set Timing.measureLength = #(ly:make-moment 4/5)
    b4 b
  }
}
\new Staff {
  \clef bass
  \time 2/4
  c2 d e f
}
>>

```



Chant or psalms notation

This form of notation is used for the chant of the Psalms, where verses aren't always the same length.

```

stemOff = \hide Staff.Stem
stemOn  = \undo \stemOff

\score {
  \new Staff \with { \remove "Time_signature_engraver" }
  {
    \key g \minor
    \cadenzaOn
    \stemOff a'\breve bes'4 g'4
    \stemOn a'2 \bar "||"
    \stemOff a'\breve g'4 a'4
    \stemOn f'2 \bar "||"
    \stemOff a'\breve^\markup { \italic flexe }
    \stemOn g'2 \bar "||"
  }
}
```

```
}
```




Creating blank staves

To create blank staves, generate empty measures then remove the `Bar_number_engraver` from the `Score` context, and the `Time_signature_engraver`, `Clef_engraver` and `Bar_engraver` from the `Staff` context.

```
#(set-global-staff-size 20)
```

```
\score {
{
  \repeat unfold 12 { s1 \break }
}
\layout {
  indent = 0\in
  \context {
    \Staff
    \remove "Time_signature_engraver"
    \remove "Clef_engraver"
    \remove "Bar_engraver"
  }
  \context {
    \Score
    \remove "Bar_number_engraver"
  }
}
}

\paper {
  #(set-paper-size "letter")
  ragged-last-bottom = ##f
  line-width = 7.5\in
  left-margin = 0.5\in
  bottom-margin = 0.25\in
  top-margin = 0.25\in
}
```






Cross staff stems

This snippet shows the use of the `Span_stem_engraver` and `\crossStaff` to connect stems across staves automatically. The stem length need not be specified, as the variable distance between noteheads and staves is calculated automatically.

```
\layout {
  \context {
    \PianoStaff
    \consists #Span_stem_engraver
  }
}

{
  \new PianoStaff <<
    \new Staff {
      <b d'>4 r d'16> e'8. g8 r\!
      e'8 f' g'4 e'2
    }
    \new Staff {
      \clef bass
      \voiceOne
      \autoBeamOff
      \crossStaff { <e g>4 e, g16 a8. c8} d
      \autoBeamOn
      g8 f g4 c2
    }
  >>
}
```



Defining an engraver in Scheme: ambitus engraver

This example demonstrates how the ambitus engraver may be defined on the user side, with a Scheme engraver.

This is basically a rewrite in Scheme of the code from ‘lily/ambitus-engraver.cc’.

```
#(use-modules (oop goops))

%%%  
%%% Grob utilities  
%%%  
%%% These are literal rewrites of some C++ methods used by the ambitus engraver.

#(define (ly:separation-item::add-conditional-item grob grob-item)
  "Add @var{grobs-item} to the array of conditional elements of @var{grobs}.
Rewrite of @code{Separation_item::add_conditional_item} from @file{lily/separation-item.cc}
  (ly:pointer-group-interface::add-grob grob 'conditional-elements grob-item))

#(define (ly:accidental-placement::accidental-pitch accidental-grob)
  "Get the pitch from the grob cause of @var{accidental-grob}.
Rewrite of @code{accidental_pitch} from @file{lily/accidental-placement.cc}."
  (ly:event-property (ly:grob-property (ly:grob-parent accidental-grob Y) 'cause)
    'pitch))

#(define (ly:accidental-placement::add-accidental grob accidental-grob)
  "Add @var{accidental-grob}, an @code{Accidental} grob, to the
list of the accidental grobs of @var{grobs}, an @code{AccidentalPlacement}
grob.
Rewrite of @code{Accidental_placement::add_accidental} from @file{lily/accidental-placement}
  (let ((pitch (ly:accidental-placement::accidental-pitch accidental-grob)))
    (set! (ly:grob-parent accidental-grob X) grob)
    (set! (ly:grob-property accidental-grob 'X-offset)
      ly:grob::x-parent-positioning)
    (let* ((accidentals (ly:grob-object grob 'accidental-grobs))
      (handle (assq (ly:pitch-notename pitch) accidentals))
      (entry (if handle (cdr handle) '())))
      (set! (ly:grob-object grob 'accidental-grobs)
        (assq-set! accidentals
          (ly:pitch-notename pitch)
          (cons accidental-grob entry)))))

%%%  
%%% Ambitus data structure  
%%%  
%%% The <ambitus> class holds the various grobs that are created
%%% to print an ambitus:
```

```

%%% - ambitus-group: the grob that groups all the components of an ambitus
%%% (Ambitus grob);
%%% - ambitus-line: the vertical line between the upper and lower ambitus
%%% notes (AmbitusLine grob);
%%% - ambitus-up-note and ambitus-down-note: the note head and accidental
%%% for the lower and upper note of the ambitus (see <ambitus-note> class
%%% below).
%%% The other slots define the key and clef context of the engraver:
%%% - start-c0: position of middle c at the beginning of the piece. It
%%% is used to place the ambitus notes according to their pitch;
%%% - start-key-sig: the key signature at the beginning of the piece. It
%%% is used to determine if accidentals shall be printed next to ambitus
%%% notes.

#(define-class <ambitus> ()
  (ambitus-group #:accessor ambitus-group)
  (ambitus-line #:accessor ambitus-line)
  (ambitus-up-note #:getter ambitus-up-note
    #:init-form (make <ambitus-note>))
  (ambitus-down-note #:getter ambitus-down-note
    #:init-form (make <ambitus-note>))
  (start-c0 #:accessor ambitus-start-c0
    #:init-value #f)
  (start-key-sig #:accessor ambitus-start-key-sig
    #:init-value '()))

%%% Accessor for the lower and upper note data of an ambitus
#(define-method (ambitus-note (ambitus <ambitus>) direction)
  "If @var{direction} is @code{UP}, then return the upper ambitus note
of @var{ambitus}, otherwise return the lower ambitus note."
  (if (= direction UP)
    (ambitus-up-note ambitus)
    (ambitus-down-note ambitus)))

%%% The <ambitus-note> class holds the grobs that are specific to ambitus
%%% (lower and upper) notes:
%%% - head: an AmbitusNoteHead grob;
%%% - accidental: an AmbitusAccidental grob, to be possibly printed next
%%% to the ambitus note head.
%%% Moreover:
%%% - pitch is the absolute pitch of the note
%%% - cause is the note event that causes this ambitus note, i.e. the lower
%%% or upper note of the considered music sequence.

#(define-class <ambitus-note> ()
  (head #:accessor ambitus-note-head
    #:init-value #f)
  (accidental #:accessor ambitus-note-accidental
    #:init-value #f)
  (cause #:accessor ambitus-note-cause
    #:init-value #f)
  (pitch #:accessor ambitus-note-pitch
    #:init-value #f))

```

```

  #:init-value #f))

%%%  

%%% Ambitus engraving logics  

%%%  

%%% Rewrite of the code from @file{lily/ambitus-engraver.cc}.

#(define (make-ambitus translator)
  "Build an ambitus object: initialize all the grobs and their relations.

```

The Ambitus grob contain all other grobs:

```

Ambitus
|- AmbitusLine
|- AmbitusNoteHead  for upper note
|- AmbitusAccidental for upper note
|- AmbitusNoteHead  for lower note
|- AmbitusAccidental for lower note

```

The parent of an accidental is the corresponding note head,
 and the accidental is set as the 'accidental-grob of the note head
 so that is printed by the function that prints notes."

```

;; make the ambitus object
(let ((ambitus (make <ambitus>)))
  ;; build the Ambitus grob, which will contain all other grobs
  (set! (ambitus-group ambitus) (ly:engraver-make-grob translator 'Ambitus '()))
  ;; build the AmbitusLine grob (line between lower and upper note)
  (set! (ambitus-line ambitus) (ly:engraver-make-grob translator 'AmbitusLine '()))
  ;; build the upper and lower AmbitusNoteHead and AmbitusAccidental
  (for-each (lambda (direction)
    (let ((head (ly:engraver-make-grob translator 'AmbitusNoteHead '()))
          (accidental (ly:engraver-make-grob translator 'AmbitusAccidental '())
                      (group (ambitus-group ambitus))))
      ;; The parent of the AmbitusAccidental grob is the
      ;; AmbitusNoteHead grob
      (set! (ly:grob-parent accidental) head)
      ;; The AmbitusAccidental grob is set as the accidental-grob
      ;; object of the AmbitusNoteHead. This is later used by the
      ;; function that prints notes.
      (set! (ly:grob-object head) 'accidental-grob) accidental)
      ;; both the note head and the accidental grobs are added
      ;; to the main ambitus grob.
      (ly:axis-group-interface::add-element group head)
      (ly:axis-group-interface::add-element group accidental)
      ;; the note head and the accidental grobs are added to the
      ;; ambitus object
      (set! (ambitus-note-head (ambitus-note ambitus direction))
            head)
      (set! (ambitus-note-accidental (ambitus-note ambitus direction))■
            accidental)))
    (list DOWN UP))
  ;; The parent of the ambitus line is the lower ambitus note head
  (set! (ly:grob-parent (ambitus-line ambitus)) X)

```

```

        (ambitus-note-head (ambitus-note ambitus DOWN)))
;; the ambitus line is added to the ambitus main grob
(ly:axis-group-interface::add-element (ambitus-group ambitus) (ambitus-line ambitus))■

#(define-method (initialize-ambitus-state (ambitus <ambitus>) translator)
  "Initialize the state of @var{ambitus}, by getting the starting
position of middle C and key signature from @var{translator}'s context."
  (if (not (ambitus-start-c0 ambitus))
      (begin
        (set! (ambitus-start-c0 ambitus)
              (ly:context-property (ly:translator-context translator)
                  'middleCPosition
                  0))
        (set! (ambitus-start-key-sig ambitus)
              (ly:context-property (ly:translator-context translator)
                  'keySignature)))))

#(define-method (update-ambitus-notes (ambitus <ambitus>) note-grob)
  "Update the upper and lower ambitus pithes of @var{ambitus}, using
@var{note-grob}."

;; Get the event that caused the note-grob creation
;; and check that it is a note-event.
(let ((note-event (ly:grob-property note-grob 'cause)))
  (if (ly:in-event-class? note-event 'note-event)
      ;; get the pitch from the note event
      (let ((pitch (ly:event-property note-event 'pitch)))
          ;; if this pitch is lower than the current ambitus lower
          ;; note pitch (or it has not been initialized yet),
          ;; then this pitch is the new ambitus lower pitch,
          ;; and conversely for upper pitch.
          (for-each (lambda (direction pitch-compare)
                      (if (or (not (ambitus-note-pitch (ambitus-note ambitus direction)))
                              (pitch-compare pitch
                                              (ambitus-note-pitch (ambitus-note ambitus direction)))
                            (begin
                              (set! (ambitus-note-pitch (ambitus-note ambitus direction))■
                                    pitch)
                              (set! (ambitus-note-cause (ambitus-note ambitus direction))■
                                    note-event)))))
                    (list DOWN UP)
                    (list ly:pitch<? (lambda (p1 p2)
                                         (ly:pitch<? p2 p1))))))))))

#(define-method (typeset-ambitus (ambitus <ambitus>) translator)
  "Typeset the ambitus:
- place the lower and upper ambitus notes according to their pitch and
the position of the middle C;
- typeset or delete the note accidentals, according to the key signature.
An accidental, if it is to be printed, is added to an AccidentalPlacement
grob (a grob dedicated to the placement of accidentals near a chord);
- both note heads are added to the ambitus line grob, so that a line should

```

```

be printed between them."
;; check if there are lower and upper pitches
(if (and (ambitus-note-pitch (ambitus-note ambitus UP))
          (ambitus-note-pitch (ambitus-note ambitus DOWN)))
      ;; make an AccidentalPlacement grob, for placement of note accidentals
      (let ((accidental-placement (ly:engraver-make-grob
                                    translator
                                    'AccidentalPlacement
                                    (ambitus-note-accidental (ambitus-note ambitus DOWN)))))

;; For lower and upper ambitus notes:
(for-each (lambda (direction)
            (let ((pitch (ambitus-note-pitch (ambitus-note ambitus direction))))
              ;; set the cause and the staff position of the ambitus note
              ;; according to the associated pitch
              (set! (ly:grob-property (ambitus-note-head (ambitus-note ambitus direction
                                                               'cause)
                                         (ambitus-note-cause (ambitus-note ambitus direction)))))

              (set! (ly:grob-property (ambitus-note-head (ambitus-note ambitus direction
                                                               'staff-position)
                                         (+ (ambitus-start-c0 ambitus)
                                            (ly:pitch-steps pitch))))
                ;; determine if an accidental shall be printed for this note,
                ;; according to the key signature
                (let* ((handle (or (assoc (cons (ly:pitch-octave pitch)
                                                (ly:pitch-notename pitch))
                                           (ambitus-start-key-sig ambitus))
                               (assoc (ly:pitch-notename pitch)
                                     (ambitus-start-key-sig ambitus))))
                       (sig-alter (if handle (cdr handle) 0)))
                  (cond ((= (ly:pitch-alteration pitch) sig-alter)
                         ;; the note alteration is in the key signature
                         ;; => it does not have to be printed
                         (ly:grob-suicide!
                           (ambitus-note-accidental (ambitus-note ambitus direction)))
                         (set! (ly:grob-object (ambitus-note-head (ambitus-note ambitus direction
                                                               'accidental-grob)
                                                 '())))
                         '())
                     (else
                       ;; otherwise, the accidental shall be printed
                       (set! (ly:grob-property (ambitus-note-accidental
                                                 (ambitus-note ambitus direction))
                                               'alteration)
                         (ly:pitch-alteration pitch)))))

                ;; add the AccidentalPlacement grob to the
                ;; conditional items of the AmbitusNoteHead
                (ly:separation-item::add-conditional-item
                  (ambitus-note-head (ambitus-note ambitus direction))
                  accidental-placement)
                ;; add the AmbitusAccidental to the list of the
                ;; AccidentalPlacement grob accidentals
                (ly:accidental-placement::add-accidental
                  accidental-placement)

```

```

        (ambitus-note-accidental (ambitus-note ambitus direction)))■
        ;; add the AmbitusNoteHead grob to the AmbitusLine grob
        (ly:pointer-group-interface::add-grob
         (ambitus-line ambitus)
         'note-heads
         (ambitus-note-head (ambitus-note ambitus direction))))))
        (list DOWN UP))
    ;; add the AccidentalPlacement grob to the main Ambitus grob
    (ly:axis-group-interface::add-element (ambitus-group ambitus) accidental-placement)
    ;; no notes ==> suicide the grobs
    (begin
      (for-each (lambda (direction)
                  (ly:grob-suicide! (ambitus-note-accidental (ambitus-note ambitus direction)))
                  (ly:grob-suicide! (ambitus-note-head (ambitus-note ambitus direction))))
                  (list DOWN UP))
                (ly:grob-suicide! ambitus-line)))))

%%%%%
%%% Ambitus engraver definition
%%%%%
#(define ambitus-engraver
  (lambda (context)
    (let ((ambitus #f)
          ;; when music is processed: make the ambitus object, if not already built
          (make-engraver
            ((process-music translator)
             (if (not ambitus)
                 (set! ambitus (make-ambitus translator))))
            ;; set the ambitus clef and key signature state
            ((stop-translation-timestep translator)
             (if ambitus
                 (initialize-ambitus-state ambitus translator)))
            ;; when a note-head grob is built, update the ambitus notes
            (acknowledgers
              ((note-head-interface engraver grob source-engraver)
               (if ambitus
                   (update-ambitus-notes ambitus grob))))
            ;; finally, typeset the ambitus according to its upper and lower notes
            ;; (if any).
            ((finalize translator)
             (if ambitus
                 (typeset-ambitus ambitus translator)))))))

   %%%%%
%%% Example
%%%%%
\score {
  \new StaffGroup <<
    \new Staff { c'4 des' e' fis' gis' }
    \new Staff { \clef "bass" c4 des ~ des ees b, }
  >>
}
```

```
\layout { \context { \Staff \consists #ambitus-engraver } }
}
```



Displaying a whole GrandStaff system if only one of its staves is alive

In orchestral scores sometimes single or groups of instruments are silent for a while and their staves can be removed for that time (with `\removeEmptyStaves`).

When they play again it is often preferred to show the staves of all instruments of such a group. this can be done adding the `Keep_alive_together_engraver` in the grouper (e.g. a GrandStaff or a StaffGroup)

In the example the violins are silent in the 2nd system and in the 3rd system. Only the first violin plays the last measure but the staff of the second violin is also displayed.

```
\score {
  <<
  \new StaffGroup = "StaffGroup_woodwinds"
  <<
    \new Staff = "Staff_flute" \with {
      instrumentName = "Flute"
      shortInstrumentName = "Fl"
      \relative c' { \repeat unfold 3 { c'4 c c c | c c c c | c c c c | \break } }
    }
  >>
  \new StaffGroup = "StaffGroup.Strings"
  <<
    \new GrandStaff = "GrandStaff_violins"
    <<
      \new Staff = "StaffViolinI" \with {
        instrumentName = "Violin I"
        shortInstrumentName = "Vi I"
      }
      \relative c'' {
        a1 \repeat unfold 7 { s1 } \repeat unfold 12 a16 a4
      }
      \new Staff = "StaffViolinII" \with {
        instrumentName = "Violin II"
        shortInstrumentName = "Vi II"
      }
      \relative c' { e1 \repeat unfold 8 { s1 } }
    >>
    \new Staff = "Staff_cello" \with {
      instrumentName = "Cello"
      shortInstrumentName = "Ce"
    }
  >>
}
```

```

\relative c {
  \clef bass
  \repeat unfold 9 {
    c1
  }
}

>>
>>
}

\layout {
  \context {
    \GrandStaff
    \consists Keep_alive_together_engraver
  }
  \context {
    \Staff
    \RemoveEmptyStaves
  }
}
}

```

Flute

Violin I

Violin II

Cello

4

Fl

Ce

7

Fl

Vi I

Vi II

Ce

Engravers one-by-one

The notation problem, creating a certain symbol, is handled by plugins. Each plugin is called an Engraver. In this example, engravers are switched on one by one, in the following order:

- note heads,
- staff symbol,
- clef,
- stem,
- beams, slurs, accents,
- accidentals, bar lines, time signature and key signature.

Engravers are grouped. For example, note heads, slurs, beams etc. form a **Voice** context. Engravers for key signature, accidentals, bar line, etc. form a **Staff** context.

```
%% sample music
topVoice = \relative c' {
    \key d \major
    es8([ g] a[ fis])
    b4
    b16[-. b-. b-. cis-.]
    d4->
}

botVoice = \relative c' {
    \key d \major
    c8[( f] b[ a])
    es4
    es16[-. es-. es-. fis-.]
    b4->
}

hoom = \relative c {
    \key d \major
    \clef bass
    g8-. r
    r4
    fis8-.
    r8
    r4
    b'4->
}

pah = \relative c' {
    r8 b-.
    r4
    r8 g8-.
    r16 g-. r8
    \clef treble
    fis'4->
}

%
% setup for Request->Element conversion. Guru-only
```

```
%
```

```
MyStaff = \context {
    \type "Engraver_group"
    \name Staff

    \description "Handles clefs, bar lines, keys, accidentals. It can contain
@code{Voice} contexts."

    \consists "Output_property_engraver"

    \consists "Font_size_engraver"

    \consists "Volta_engraver"
    \consists "Separating_line_group_engraver"
    \consists "Dot_column_engraver"

    \consists "Ottava_spinner_engraver"
    \consists "Rest_collision_engraver"
    \consists "Piano_pedal_engraver"
    \consists "Piano_pedal_align_engraver"
    \consists "Instrument_name_engraver"
    \consists "Grob_pq_engraver"
    \consists "Forbid_line_break_engraver"
    \consists "Axis_group_engraver"

    \consists "Pitch_squash_engraver"

    localKeySignature = #'()

    % explicitly set instrumentName, so we don't get
    % weird effects when doing instrument names for
    % piano staves

    instrumentName = #'()
    shortInstrumentName = #'()

    \accepts "Voice"
    \defaultchild "Voice"
}

MyVoice = \context {
    \type "Engraver_group"
    \name Voice

    \description "
        Corresponds to a voice on a staff. This context handles the
        conversion of dynamic signs, stems, beams, super- and subscripts,
        slurs, ties, and rests.

        You have to instantiate this explicitly if you want to have
    "
}
```

```

multiple voices on the same staff."'

localKeySignature = #'()
\consists "Font_size_engraver"

% must come before all
\consists "Output_property_engraver"
\consists "Arpeggio_engraver"
\consists "Multi_measure_rest_engraver"
\consists "Text_spinner_engraver"
\consists "Grob_pq_engraver"
\consists "Note_head_line_engraver"
\consists "Glissando_engraver"
\consists "Ligature_bracket_engraver"
\consists "Breathing_sign_engraver"
% \consists "Rest_engraver"
\consists "Grace_beam_engraver"
\consists "New_fingering_engraver"
\consists "Chord_tremolo_engraver"
\consists "Percent_repeat_engraver"
\consists "Slash_repeat_engraver"

%{
    Must come before text_engraver, but after note_column_engraver.
%
\consists "Text_engraver"
\consists "Dynamic_engraver"
\consists "Dynamic_align_engraver"
\consists "Fingering_engraver"

\consists "Script_column_engraver"
\consists "Rhythmic_column_engraver"
\consists "Cluster_spinner_engraver"
\consists "Tie_engraver"
\consists "Tie_engraver"
\consists "Tuplet_engraver"
\consists "Note_heads_engraver"
\consists "Rest_engraver"
}

\score {
    \topVoice
    \layout {
        \context { \MyStaff }
        \context { \MyVoice }
    }
}

MyStaff = \context {
    \MyStaff
}
```

```
\consists "Staff_symbol_engraver"
}

\score {
    \topVoice
    \layout {
        \context { \MyStaff }
        \context { \MyVoice }
    }
}

MyStaff = \context {
    \MyStaff
    \consists "Clef_engraver"
    \remove "Pitch_squash_engraver"
}

\score {
    \topVoice
    \layout {
        \context { \MyStaff }
        \context { \MyVoice }
    }
}

MyVoice = \context {
    \MyVoice
    \consists "Stem_engraver"
}

\score {
    \topVoice
    \layout {
        \context { \MyStaff }
        \context { \MyVoice }
    }
}

MyVoice = \context {
    \MyVoice
    \consists "Beam_engraver"
}

\score {
    \topVoice
    \layout {
        \context { \MyStaff }
        \context { \MyVoice }
    }
}

MyVoice = \context {
```

```

\MyVoice
\consists "Phrasing_slur_engraver"
\consists "Slur_engraver"
\consists "Script_engraver"
}

\score {
\topVoice
\layout {
\context { \MyStaff }
\context { \MyVoice }
}
}

MyStaff = \context {
\MyStaff
\consists "Bar_engraver"
\consists "Time_signature_engraver"
}

\score {
\topVoice
\layout {
\context { \MyStaff }
\context { \MyVoice }
}
}

MyStaff = \context {
\MyStaff
\consists "Accidental_engraver"
\consists "Key_engraver"
}

\score {
\topVoice
\layout {
\context { \MyStaff }
\context { \MyVoice }
}
}
}

```






Mensurstriche layout (bar lines between the staves)

The mensurstriche-layout where the bar lines do not show on the staves but between staves can be achieved with a `StaffGroup` instead of a `ChoirStaff`. The bar line on staves is blanked out by setting the `transparent` property.

```
global = {
    \hide Staff.BarLine
    s1 s
    % the final bar line is not interrupted
    \undo \hide Staff.BarLine
    \bar "|."
}


\new StaffGroup \relative c' {
    <<
        \new Staff { << \global { c1 c } >> }
        \new Staff { << \global { c c } >> }
    >>
}
```



Nesting staves

The property `systemStartDelimiterHierarchy` can be used to make more complex nested staff groups. The command `\set StaffGroup.systemStartDelimiterHierarchy` takes an alphabetical list of the number of staves produced. Before each staff a system start delimiter can be given. It has to be enclosed in brackets and takes as much staves as the brackets enclose. Elements in the list can be omitted, but the first bracket takes always the complete number of staves. The possibilities are `SystemStartBar`, `SystemStartBracket`, `SystemStartBrace`, and `SystemStartSquare`.

```
\new StaffGroup
\relative c' <<
  \set StaffGroup.systemStartDelimiterHierarchy
    = #'(SystemStartSquare (SystemStartBrace (SystemStartBracket a
                                              (SystemStartSquare b) ) c ) d)
  \new Staff { c1 }
  \new Staff { c1 }
>>
```



Numbering groups of measures

This snippet demonstrates the use of the `Measure_counter_engraver` to number groups of successive measures. Any stretch of measures may be numbered, whether consisting of repetitions or not.

The engraver must be added to the appropriate context. Here, a `Staff` context is used; another possibility is a `Dynamics` context.

The counter is begun with `\startMeasureCount` and ended with `\stopMeasureCount`. Numbering will start by default with 1, but this behavior may be modified by overriding the `count-from` property.

When a measure extends across a line break, the number will appear twice, the second time in parentheses.

```
\layout {
```

```
\context {
    \Staff
    \consists #Measure_counter_engraver
}
}

\new Staff {
    \startMeasureCount
    \repeat unfold 7 {
        c'4 d' e' f'
    }
    \stopMeasureCount
    \bar "||"
    g'4 f' e' d'
    \override Staff.MeasureCounter.count-from = #2
    \startMeasureCount
    \repeat unfold 5 {
        g'4 f' e' d'
    }
    g'4 f'
    \bar ""
    \break
    e'4 d'
    \repeat unfold 7 {
        g'4 f' e' d'
    }
    \stopMeasureCount
}
```


The image shows a musical score with three staves. The top staff has bar numbers 1 through 7 above the notes. The middle staff starts at bar 8 and has bar numbers 8 through 7 above the notes. The bottom staff starts at bar 7 and has bar numbers 7 through 14 above the notes. All staves are in common time (indicated by 'C') and have a treble clef. The music consists of eighth-note patterns.

Removing bar numbers from a score

Bar numbers can be removed entirely by removing the `Bar_number_engraver` from the `Score` context.

```
\layout {
    \context {
        \Score
        \remove "Bar_number_engraver"
    }
}
```

```
\relative c' {
  c4 c c c \break
  c4 c c c
}
```



Use square bracket at the start of a staff group

The system start delimiter `SystemStartSquare` can be used by setting it explicitly in a `StaffGroup` or `ChoirStaff` context.

```
\score {
  \new StaffGroup { <<
    \set StaffGroup.systemStartDelimiter = #'SystemStartSquare
    \new Staff { c'4 d' e' f' }
    \new Staff { c'4 d' e' f' }
  >> }
}
```



Vocal ensemble template with lyrics aligned below and above the staves

This template is basically the same as the simple “Vocal ensemble” template, with the exception that here all the lyrics lines are placed using `alignAboveContext` and `alignBelowContext`.

```
global = {
  \key c \major
  \time 4/4
}

sopMusic = \relative c'' {
  c4 c c8[( b)] c4
}
sopWords = \lyricmode {
  hi hi hi hi
}

altoMusic = \relative c' {
```

```

e4 f d e
}
altoWords = \lyricmode {
    ha ha ha ha
}

tenorMusic = \relative c' {
    g4 a f g
}
tenorWords = \lyricmode {
    hu hu hu hu
}

bassMusic = \relative c {
    c4 c g c
}
bassWords = \lyricmode {
    ho ho ho ho
}

\score {
    \new ChoirStaff <<
        \new Staff = "women" <<
            \new Voice = "sopranos" { \voiceOne << \global \sopMusic >> }
            \new Voice = "altos" { \voiceTwo << \global \altoMusic >> }
        >>
        \new Lyrics \with { alignAboveContext = #"women" }
            \lyricsto "sopranos" \sopWords
        \new Lyrics \with { alignBelowContext = #"men" }
            \lyricsto "altos" \altoWords
        % we could remove the line about this with the line below, since
        % we want the alto lyrics to be below the alto Voice anyway.
        % \new Lyrics \lyricsto "altos" \altoWords

        \new Staff = "men" <<
            \clef bass
            \new Voice = "tenors" { \voiceOne << \global \tenorMusic >> }
            \new Voice = "basses" { \voiceTwo << \global \bassMusic >> }
        >>
        \new Lyrics \with { alignAboveContext = #"men" }
            \lyricsto "tenors" \tenorWords
        \new Lyrics \with { alignBelowContext = #"men" }
            \lyricsto "basses" \bassWords
        % again, we could replace the line above this with the line below.
        % \new Lyrics \lyricsto "basses" \bassWords
    >>
}

```



Vocal ensemble template with verse and refrain

This template creates a score which starts with a solo verse and continues into a refrain for two voices. It also demonstrates the use of spacer rests within the \global variable to define meter changes (and other elements common to all parts) throughout the entire score.

```
global = {
    \key g \major

    % verse
    \time 3/4
    s2.*2
    \break

    % refrain
    \time 2/4
    s2*2
    \bar "| ."
}

SoloNotes = \relative g' {
    \clef "treble"

    % verse
    g4 g g |
    b4 b b |

    % refrain
    R2*2 |
}

SoloLyrics = \lyricmode {
    One two three |
    four five six |
}

SopranoNotes = \relative c'' {
    \clef "treble"

    % verse
    R2.*2 |

    % refrain
    c4 c |
}
```

```

g4 g |
}

SopranoLyrics = \lyricmode {
    la la |
    la la |
}

BassNotes = \relative c {
    \clef "bass"

    % verse
    R2.*2 |

    % refrain
    c4 e |
    d4 d |
}

BassLyrics = \lyricmode {
    dum dum |
    dum dum |
}


\score {
    <<
        \new Voice = "SoloVoice" << \global \SoloNotes >>
        \new Lyrics \lyricsto "SoloVoice" \SoloLyrics

        \new ChoirStaff <<
            \new Voice = "SopranoVoice" << \global \SopranoNotes >>
            \new Lyrics \lyricsto "SopranoVoice" \SopranoLyrics

            \new Voice = "BassVoice" << \global \BassNotes >>
            \new Lyrics \lyricsto "BassVoice" \BassLyrics
        >>
    >>
    \layout {
        ragged-right = ##t
        \context { \Staff
            % these lines prevent empty staves from being printed
            \RemoveEmptyStaves
            \override VerticalAxisGroup.remove-first = ##t
        }
    }
}

```





Tweaks and overrides


Section “Changing defaults” in *Notation Reference*

Section “Tweaking output” in *Learning Manual*

Adding an ottava marking to a single voice

If you have more than one voice on the staff, setting octavation in one voice will transpose the position of notes in all voices for the duration of the ottava bracket. If the ottavation is only intended to apply to one voice, the middleCPosition and ottava bracket may be set explicitly. In this snippet, the bass clef usually has middleCPosition set to 6, six positions above the center line, so in the 8va portion middleCPosition is 7 positions (one octave) higher still.

```
{
  \clef bass
  << { <g d'>1~ q2 <c' e'> }
  \\
  {
    r2.
    \set Staff.ottavation = #"8vb"
    \once \override Staff.OttavaBracket.direction = #DOWN
    \set Voice.middleCPosition = #(+ 6 7)
    <b,,, b,,,>4 ~ |
    q2
    \unset Staff.ottavation
    \unset Voice.middleCPosition
    <c e>2
  }
  >>
}
```



Adding links to objects

To add a link to a grob-stencil you could use `add-link` as defined here. Works with `\override` and `\tweak`. Drawback: `point-and-click` will be disturbed for the linked grobs.

Limitation: Works for PDF only.

The linked objects are colored with a separate command.

```
% Code by Thomas Morley
% Contributed by harm6
% Tested with 2.14.2 up to 2.17.9

#(define (add-link url-strg)
  (lambda (grob)
    (let* ((stil (ly:grob-property grob 'stencil)))
      (if (ly:stencil? stil)
```

```

(begin
  (let* (
    (x-ext (ly:stencil-extent stil X))
    (y-ext (ly:stencil-extent stil Y))
    (url-expr (list 'url-link url-strg `(quote ,x-ext) `(quote ,y-ext)))
    (new-stil (ly:stencil-add (ly:make-stencil url-expr x-ext y-ext) stil)))
  (ly:grob-set-property! grob 'stencil new-stil)))
#f)))))

%%% test

urlI =
"http://lilypond.org/doc/v2.14/Documentation/notation/writing-pitches"

urlII =
"http://lilypond.org/doc/v2.14/Documentation/notation/rhythms"

urlIII =
"http://lilypond.org/doc/v2.14/Documentation/notation/note-heads"

urlIV =
"http://lilypond.org/doc/v2.14/Documentation/notation/beams"

urlV =
"http://lilypond.org/doc/v2.14/Documentation/notation/note-head-styles"

\relative c' {
  \key cis \minor

  \once \override Staff.Clef.color = #green
  \once \override Staff.Clef.after-line-breaking =
    #(add-link urlI)

  \once \override Staff.TimeSignature.color = #green
  \once \override Staff.TimeSignature.after-line-breaking =
    #(add-link urlII)

  \once \override NoteHead.color = #green
  \once \override NoteHead.after-line-breaking =
    #(add-link urlIII)

  cis'1
  \once \override Beam.color = #green
  \once \override Beam.after-line-breaking =
    #(add-link urlIV)
  cis8 dis e fis gis2
  <gis,
  % With 2.17.9 you could use the command below to address the Accidental.
  % \tweak Accidental.before-line-breaking #(add-link url)
  \tweak color #green
  \tweak after-line-breaking #(add-link urlV)
  \tweak style #'harmonic
}

```

```

bis
dis
fis
>1
<cis, cis' e>
}

```



Adding timing marks to long glissandi

Skipped beats in very long glissandi are sometimes indicated by timing marks, often consisting of stems without noteheads. Such stems can also be used to carry intermediate expression markings.

If the stems do not align well with the glissando, they may need to be repositioned slightly.

```

glissandoSkipOn = {
    \override NoteColumn.glissando-skip = ##t
    \hide NoteHead
    \override NoteHead.no-ledgers = ##t
}

glissandoSkipOff = {
    \revert NoteColumn.glissando-skip
    \undo \hide NoteHead
    \revert NoteHead.no-ledgers
}

\relative c' {
    r8 f8\glissando
    \glissandoSkipOn
    f4 g a a8\noBeam
    \glissandoSkipOff
    a8

    r8 f8\glissando
    \glissandoSkipOn
    g4 a8
    \glissandoSkipOff
    a8 |

    r4 f\glissando \l
    \glissandoSkipOn
    a4\f \r
    \glissandoSkipOff
    b8!\r |
}

```



Adjusting grace note spacing

The space given to grace notes can be adjusted using the `spacing-increment` property of `Score.GraceSpacing`.

```
graceNotes = {
    \grace { c4 c8 c16 c32 }
    c8
}


\relative c' {
    c8
    \graceNotes
    \override Score.GraceSpacing.spacing-increment = #2.0
    \graceNotes
    \revert Score.GraceSpacing.spacing-increment
    \graceNotes
}
```



Altering the length of beamed stems

Stem lengths on beamed notes can be varied by overriding the `beamed-lengths` property of the `details` of the `Stem`. If a single value is used as an argument, the length applies to all stems. When multiple arguments are used, the first applies to eighth notes, the second to sixteenth notes and so on. The final argument also applies to all notes shorter than the note length of the final argument. Non-integer arguments may also be used.

```
\relative c' {
    \override Stem.details.beamed-lengths = #'(2)
    a8[ a] a16[ a] a32[ a]
    \override Stem.details.beamed-lengths = #'(8 10 12)
    a8[ a] a16[ a] a32[ a] r8
    \override Stem.details.beamed-lengths = #'(8)
    a8[ a]
    \override Stem.details.beamed-lengths = #'(8.5)
    a8[ a]
    \revert Stem.details
    a8[ a] a16[ a] a32[ a] r16
}
```



Alternative bar numbering

Two alternative methods for bar numbering can be set, especially for when using repeated music.

```
\relative c'{
  \set Score.alternativeNumberingStyle = #'numbers
  \repeat volta 3 { c4 d e f | }
  \alternative {
    { c4 d e f | c2 d \break }
    { f4 g a b | f4 g a b | f2 a | \break }
    { c4 d e f | c2 d }
  }
  c1 \break
  \set Score.alternativeNumberingStyle = #'numbers-with-letters
  \repeat volta 3 { c,4 d e f | }
  \alternative {
    { c4 d e f | c2 d \break }
    { f4 g a b | f4 g a b | f2 a | \break }
    { c4 d e f | c2 d }
  }
  c1
}
```

The image shows five staves of musical notation. Each staff consists of a treble clef, a common time signature, and a key signature of one sharp. The notation includes quarter notes and eighth notes. Measure numbers are placed above each staff: 1, 2, 3, 1, and 2 respectively. The first staff starts with a measure of c4 d e f followed by a c2 d measure. The second staff starts with a f4 g a b measure followed by another f4 g a b measure. The third staff starts with a f2 a measure. The fourth staff starts with a c4 d e f measure followed by a c2 d measure. The fifth staff starts with a f4 g a b measure followed by another f4 g a b measure. The measure numbers 1, 2, 3, 1, and 2 are placed above the staves respectively.

Analysis brackets above the staff

Simple horizontal analysis brackets are added below the staff by default. The following example shows a way to place them above the staff instead.

```
\layout {
  \context {
    \Voice
    \consists "Horizontal_bracket_engraver"
  }
}

\relative c' {
  \once \override HorizontalBracket.direction = #UP
  c2\startGroup
  d2\stopGroup
}
```



Asymmetric slurs

Slurs can be made asymmetric to match an asymmetric pattern of notes better.

```
slurNotes = { d,8( a' d f a f' d, a) }
```

```
\relative c' {
  \stemDown
  \slurUp
  \slurNotes
  \once \override Slur.eccentricity = #3.0
  \slurNotes
}
```



Avoiding collisions with chord fingerings

Fingerings and string numbers applied to individual notes will automatically avoid beams and stems, but this is not true by default for fingerings and string numbers applied to the individual notes of chords. The following example shows how this default behavior can be overridden.

```
\relative c' {
  \set fingeringOrientations = #'(up)
  \set stringNumberOrientations = #'(up)
  \set strokeFingerOrientations = #'(up)


  % Default behavior
  r8
  <f c'-5>8
```

```

<f c'\5>8
<f c'-'rightHandFinger #2 >8

% Corrected to avoid collisions
r8
\override Fingering.add-stem-support = ##t
<f c'-5>8
\override StringNumber.add-stem-support = ##t
<f c'\5>8
\override StrokeFinger.add-stem-support = ##t
<f c'-'rightHandFinger #2 >8
}

```



Caesura ("railtracks") with fermata

A caesura is sometimes denoted by a double “railtracks” breath mark with a fermata sign positioned above. This snippet shows an optically pleasing combination of railtracks and fermata.

```

\relative c' {
  c2.
  % construct the symbol
  \override BreathingSign.text = \markup {
    \line {
      \musicglyph #"scripts.caesura.curved"
      \translate #'(-1.75 . 1.6)
      \musicglyph #"scripts.ufermata"
    }
  }
  \breathe c4
  % set the breathe mark back to normal
  \revert BreathingSign.text
  c2. \breathe c4
  \bar "|."
}

```



Centering markup on note heads automatically

For technical reasons, text scripts attached to note heads cannot easily be centered on a note head’s width, unlike articulations.

Instead of using trial-and-error offset tweaks, this snippet uses a Scheme engraver to reset the horizontal parent of each markup to a `NoteColumn`. This also allows text to follow note heads which have been shifted via `force-hshift`.

```

#define (Text_align_engraver ctx)
(let ((scripts '())

```


```

(note-column #f))
(make-engraver
(acknowledgers
((note-column-interface trans grob source)
;; cache NoteColumn in this Voice context
(set! note-column grob))
((text-script-interface trans grob source)
;; whenever a TextScript is acknowledged,
;; add it to `scripts' list
(set! scripts (cons grob scripts)))
((stop-translation-timestep trans)
;; if any TextScript grobs exist,
;; set NoteColumn as X-parent
(for-each (lambda (script)
            (set! (ly:grob-parent script X) note-column))
          scripts)
;; clear scripts ready for next timestep
(set! scripts '())))
}

\layout {
\context {
\Voice
\consists #Text_align_engraver
\override TextScript.X-offset =
#ly:self-alignment-interface::aligned-on-x-parent
\override TextScript.self-alignment-X = #CENTER
}
}

\new Staff <<
\relative c' {
\override NoteColumn.force-hshift = #3
c1-\markup { \arrow-head #Y #DOWN ##t }
}
\\
\relative c' {
a4 a-\markup { \huge ^ } a a
}
>>

```




Changing a single note's size in a chord

Individual note heads in a chord can be modified with the `\tweak` command inside a chord, by altering the `font-size` property.

Inside the chord (within the brackets `< >`), before the note to be altered, place the `\tweak` command, followed by `#'font-size` and define the proper size like `#-2` (a tiny note head).


```
\relative c' {
  <\tweak font-size #+2 c e g c \tweak font-size #-2 e>1^{\markup { A tiny e }}_ {\markup { A big e}}
}
```



Changing form of multi-measure rests

If there are ten or fewer measures of rests, a series of longa and breve rests (called in German “Kirchenpausen” - church rests) is printed within the staff; otherwise a simple line is shown. This default number of ten may be changed by overriding the `expand-limit` property.

```
\relative c'' {
  \compressFullBarRests
  R1*2 | R1*5 | R1*9
  \override MultiMeasureRest.expand-limit = #3
  R1*2 | R1*5 | R1*9
}
```



Changing properties for individual grobs

The `\applyOutput` command allows the tuning of any layout object, in any context. It requires a Scheme function with three arguments.

```
#(define (mc-squared grob grob-origin context)
  (let ((sp (ly:grob-property grob 'staff-position)))
    (if (grob::has-interface grob 'note-head-interface)
        (begin
          (ly:grob-set-property! grob 'stencil
          (grob-interpret-markup grob
          (make-lower-markup 0.5
            (case sp
              ((-5) "m")
              ((-3) "c ")
              ((-2) (make-smaller-markup (make-bold-markup "2")))
              (else "bla")))))))))
```

```
\relative c' {
  <d f g b>2
  \applyOutput #'Voice #'mc-squared
  <d f g b>2
}
```



Changing text and spanner styles for text dynamics

The text used for crescendos and decrescendos can be changed by modifying the context properties `crescendoText` and `decrescendoText`.

The style of the spanner line can be changed by modifying the `'style` property of `DynamicTextSpanner`. The default value is `'dashed-line`, and other possible values include `'line`, `'dotted-line` and `'none`.

```
\relative c' {
    \set crescendoText = \markup { \italic { cresc. poco } }
    \set crescendoSpanner = #'text
    \override DynamicTextSpanner.style = #'dotted-line
    a2< a
    a2 a
    a2 a
    a2 a\mf
}
```



Changing the default text font family

The default font families for text can be overridden with `make-pango-font-tree`.

```
\paper {
    % change for other default global staff size.
    myStaffSize = #20
    %{
        run
            lilypond -dshow-available-fonts blabla
            to show all fonts available in the process log.
    %}

    #(define fonts
        (make-pango-font-tree "Times New Roman"
            "Nimbus Sans"
            "Luxi Mono"
        ;;
            "Helvetica"
            "Courier"
        ; (/ myStaffSize 20)))
    }

\relative c' {
    c4^\markup {
        roman: foo \bold bla \italic bar \italic \bold baz
    }
    c'4_^\markup {
        \override #'(font-family . sans)
    {
        sans: foo \bold bla \italic bar \italic \bold baz
    }
}
```

```

}
c'2^markup {
  \override #'(font-family . typewriter)
{
  mono: foo \bold bla \italic bar \italic \bold baz
}
}
}

```

mono: foo **bla** *bar* **baz**
 roman: foo **bla** *bar* **baz**

sans: foo **bla** *bar* **baz**

Changing the staff size

Though the simplest way to resize staves is to use `#(set-global-staff-size xx)`, an individual staff's size can be changed by scaling the properties `'staff-space` and `fontSize`.

```

<<
\new Staff {
  \relative c' {
    \dynamicDown
    c8\ff c c c c c c c
  }
}
\new Staff \with {
  fontSize = #-3
  \override StaffSymbol.staff-space = #(magstep -3)
} {
  \clef bass
  c8 c c c c\f c c c
}
>>

```

Changing the tempo without a metronome mark

To change the tempo in MIDI output without printing anything, make the metronome mark invisible.

```

\score {
  \new Staff \relative c' {
    \tempo 4 = 160
    c4 e g b
  }
}

```

```
c4 b d c
\set Score.tempoHideNote = ##t
\tempo 4 = 96
d,4 fis a cis
d4 cis e d
}
\layout { }
\midi { }
}
```




Changing the text for sustain markings

`Staff.pedalSustainStrings` can be used to set the text used for pedal down and up. Note that the only valid strings are those found in the list of pedal glyphs - the values used this snippet constitute an exhaustive list.

```
sustainNotes = { c4\sustainOn d e\sustainOff\sustainOn f\sustainOff }
```

```
\relative c' {
  \sustainNotes
  \set Staff.pedalSustainStrings = #'("P" "P-" "-")
  \sustainNotes
  \set Staff.pedalSustainStrings = #'("d" "de" "e")
  \sustainNotes
  \set Staff.pedalSustainStrings = #'("M" "M-" "-")
  \sustainNotes
  \set Staff.pedalSustainStrings = #'("Ped" "*Ped" "*")
  \sustainNotes
}
```



Controlling spanner visibility after a line break

The visibility of spanners which end on the first note following a line break is controlled by the `after-line-breaking` callback `ly:spanner::kill-zero-spanned-time`.

For objects such as glissandos and hairpins, the default behaviour is to hide the spanner after a break; disabling the callback will allow the left-broken span to be shown.

Conversely, spanners which are usually visible, such as text spans, can be hidden by enabling the callback.

```
\paper { ragged-right = ##t }

\relative c'' {
  \override Hairpin.to-barline = ##f
  \override Glissando.breakable = ##t
```

```
% show hairpin
\override Hairpin.after-line-breaking = ##t
% hide text span
\override TextSpanner.after-line-breaking =
#ly:spanner::kill-zero-spanned-time
e2\<\startTextSpan
% show glissando
\override Glissando.after-line-breaking = ##t
f2\glissando
\break
f,1\!\stopTextSpan
}
```



Controlling the vertical ordering of scripts

The vertical ordering of scripts is controlled with the 'script-priority' property. The lower this number, the closer it will be put to the note. In this example, the `TextScript` (the sharp symbol) first has the lowest priority, so it is put lowest in the first example. In the second, the prall trill (the `Script`) has the lowest, so it is on the inside. When two objects have the same priority, the order in which they are entered determines which one comes first.

```
\relative c''' {
  \once \override TextScript.script-priority = #-100
  a2^\prall^\markup { \sharp }

  \once \override Script.script-priority = #-100
  a2^\prall^\markup { \sharp }
}
```



Controlling tuplet bracket visibility

The default behavior of tuplet-bracket visibility is to print a bracket unless there is a beam of the same length as the tuplet. To control the visibility of tuplet brackets, set the property 'bracket-visibility' to either `#t` (always print a bracket), `#f` (never print a bracket) or `#'if-no-beam` (only print a bracket if there is no beam).

```
music = \relative c'' {
  \tuplet 3/2 { c16[ d e ] f8]
  \tuplet 3/2 { c8 d e }
  \tuplet 3/2 { c4 d e }
```

```
}
```

```
\new Voice {
  \relative c' {
    << \music s4^"default" >>
    \override TupletBracket.bracket-visibility = #'if-no-beam
    << \music s4^"'if-no-beam" >>
    \override TupletBracket.bracket-visibility = ##t
    << \music s4^"#t" >>
    \override TupletBracket.bracket-visibility = ##f
    << \music s4^"#f" >>
  }
}
```

The image contains two musical staves. The top staff is in common time (C) and shows a sequence of six eighth notes grouped into three pairs by a single horizontal brace. The first pair is underlined with a '3' below it, and the second pair is also underlined with a '3'. The third pair is underlined with a '3' and has a bracket above it labeled 'if-no-beam'. The bottom staff is in 3/4 time (3) and shows a sequence of nine eighth notes grouped into three sets of three. The first two sets each have a single underline with a '3' below it. The third set has a bracket above it labeled '#f', indicating that the third note of the set is not bracketed.

Creating a delayed turn

Creating a delayed turn, where the lower note of the turn uses the accidental, requires several overrides. The `outside-staff-priority` property must be set to `#f`, as otherwise this would take precedence over the `avoid-slur` property. Changing the fractions `2/3` and `1/3` adjusts the horizontal position.


```
\relative c'' {
  c2*2/3 ( s2*1/3\turn d4) r
  <<
  { c4.( d8) }
  { s4 s\turn }
  >>
  \transpose c d \relative c'' <<
  { c4.( d8) }
  {
    s4
    \once \set suggestAccidentals = ##t
    \once \override AccidentalSuggestion #'outside-staff-priority = ##f
    \once \override AccidentalSuggestion #'avoid-slur = #'inside
    \once \override AccidentalSuggestion #'font-size = #-3
    \once \override AccidentalSuggestion #'script-priority = #-1
    \single \hideNotes
    b8-\turn \noBeam
    s8
  }
  >>
}
```



Creating double-digit fingerings

Creating fingerings larger than 5 is possible.

```
\relative c' {
    c1-10
    c1-50
    c1-36
    c1-29
}
```



Creating simultaneous rehearsal marks

Unlike text scripts, rehearsal marks cannot be stacked at a particular point in a score: only one `RehearsalMark` object is created. Using an invisible measure and bar line, an extra rehearsal mark can be added, giving the appearance of two marks in the same column. This method may also prove useful for placing rehearsal marks at both the end of one system and the start of the following system.

```
{
    \key a \major
    \set Score.markFormatter = #format-mark-box-letters
    \once \override Score.RehearsalMark.outside-staff-priority = #5000
    \once \override Score.RehearsalMark.self-alignment-X = #LEFT
    \once \override Score.RehearsalMark.break-align-symbols = #'(key-signature)
    \mark \markup { \bold { Senza denti } }

    % the hidden measure and bar line
    % \cadenzaOn turns off automatic calculation of bar numbers
    \cadenzaOn
    \once \omit Score.TimeSignature
    \time 1/16
    s16 \bar ""
    \cadenzaOff

    \time 4/4
    \once \override Score.RehearsalMark.self-alignment-X = #LEFT
    \mark \markup { \box \bold Intro }
    d'1
    \mark \default
    d'1
}
```



Creating text spanners

The `\startTextSpan` and `\stopTextSpan` commands allow the creation of text spanners as easily as pedal indications or octavations. Override some properties of the `TextSpanner` object to modify its output.

```
\paper { ragged-right = ##f }


\relative c' {
    \override TextSpanner.bound-details.left.text = #"bla"
    \override TextSpanner.bound-details.right.text = #"blu"
    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan

    \override TextSpanner.style = #'line
    \once \override TextSpanner.bound-details.left.stencil-align-dir-y = #CENTER
    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan

    \override TextSpanner.style = #'dashed-line
    \override TextSpanner.bound-details.left.text =
        \markup { \draw-line #'(0 . 1) }
    \override TextSpanner.bound-details.right.text =
        \markup { \draw-line #'(0 . -2) }
    \once \override TextSpanner.bound-details.right.padding = #-2

    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan


    \set Staff.middleCPosition = #-13
    \override TextSpanner.dash-period = #10
    \override TextSpanner.dash-fraction = #0.5
    \override TextSpanner.thickness = #10
    a4 \startTextSpan
    b4 c
    a4 \stopTextSpan
}
```



Cross-staff chords - beaming problems workaround

Sometimes it is better to use stems from the upper staff for creating cross-staff chords, because no problems with automatic beam collision avoidance then arise. If the stems from the lower staff were used in the following example, it would be necessary to change the automatic beam collision avoidance settings so that it doesn't detect collisions between staves using `\override Staff.Beam.collision-voice-only = ##t`

```
\new PianoStaff <<
  \new Staff = up
    \relative c' {
      <<
        { r4
          \override Stem.cross-staff = ##t
          \override Stem.length = #19 % this is in half-spaces,
            % so it makes stems 9.5 staffspaces long
          \override Stem.Y-offset = #-6 % stems are normally lengthened
            % upwards, so here we must lower the stem by the amount
            % equal to the lengthening - in this case (19 - 7) / 2
            % (7 is default stem length)
          e e e }
        { s4
          \change Staff = "bottom"
          \override NoteColumn.ignore-collision = ##t
          c, c c
        }
      >>
    }
  \new Staff = bottom
  \relative c' {
    \clef bass
    \voiceOne
    g8 a g a g a g a
  }
>>
```



Cross staff stems

This snippet shows the use of the `Span_stem_engraver` and `\crossStaff` to connect stems across staves automatically. The stem length need not be specified, as the variable distance between noteheads and staves is calculated automatically.


```
\layout {
  \context {
    \PianoStaff
    \consists #Span_stem_engraver
  }
}

{
  \new PianoStaff <<
    \new Staff {
      <b d'>4 r d'16\> e'8. g8 r\!
      e'8 f' g'4 e'2
    }
  >>
```

```

}
\new Staff {
    \clef bass
    \voiceOne
    \autoBeamOff
    \crossStaff { <e g>4 e, g16 a8. c8} d
    \autoBeamOn
    g8 f g4 c2
}
>>
}

```



Custodes

Custodes may be engraved in various styles.

```

\layout { ragged-right = ##t }

\new Staff \with { \consists "Custos_engraver" } \relative c' {
    \override Staff.Custos.neutral-position = #4


    \override Staff.Custos.style = #'hufnagel
    c1^"hufnagel" \break
    <d a' f'>1



    \override Staff.Custos.style = #'medicaea
    c1^"medicaea" \break
    <d a' f'>1

    \override Staff.Custos.style = #'vaticana
    c1^"vaticana" \break
    <d a' f'>1

    \override Staff.Custos.style = #'mensural
    c1^"mensural" \break
    <d a' f'>1
}

```






Customizing fretboard fret diagrams

Fret diagram properties can be set through 'fret-diagram-details'. For FretBoard fret diagrams, overrides are applied to the `FretBoards.FretBoard` object. Like `Voice`, `FretBoards` is a bottom level context, therefore can be omitted in property overrides.

```
\include "predefined-guitar-fretboards.ly"
\storePredefinedDiagram #default-fret-table \chordmode { c' }
                        #guitar-tuning
                        #"x;1-1-(;3-2;3-3;3-4;1-1-);

<<
\new ChordNames {
    \chordmode { c1 | c | c | d }
}
\new FretBoards {
    % Set global properties of fret diagram
    \override FretBoards.FretBoard.size = #'1.2
    \override FretBoard.fret-diagram-details.finger-code = #'in-dot
    \override FretBoard.fret-diagram-details.dot-color = #'white
    \chordmode {
        c
        \once \override FretBoard.size = #'1.0
        \once \override FretBoard.fret-diagram-details.barre-type = #'straight
        \once \override FretBoard.fret-diagram-details.dot-color = #'black
        \once \override FretBoard.fret-diagram-details.finger-code = #'below-string
        c'
        \once \override FretBoard.fret-diagram-details.barre-type = #'none
        \once \override FretBoard.fret-diagram-details.number-type = #'arabic
        \once \override FretBoard.fret-diagram-details.orientation = #'landscape
        \once \override FretBoard.fret-diagram-details.mute-string = #"M"
        \once \override FretBoard.fret-diagram-details.label-dir = #LEFT
        \once \override FretBoard.fret-diagram-details.dot-color = #'black
        c'
        \once \override FretBoard.fret-diagram-details.finger-code = #'below-string
        \once \override FretBoard.fret-diagram-details.dot-radius = #0.35
        \once \override FretBoard.fret-diagram-details.dot-position = #0.5
        \once \override FretBoard.fret-diagram-details.fret-count = #3
        d
    }
}
\new Voice {
    c'1 | c' | c' | d'
```

```
}
>>
```



Customizing markup fret diagrams

Fret diagram properties can be set through 'fret-diagram-details'. For markup fret diagrams, overrides can be applied to the `Voice.TextScript` object or directly to the markup.

```
<<
```

```
\chords { c1 | c | c | d }

\new Voice = "mel" {
    \textLengthOn
    % Set global properties of fret diagram
    \override TextScript.size = #'1.2
    \override TextScript.fret-diagram-details.finger-code = #'in-dot
    \override TextScript.fret-diagram-details.dot-color = #'white


    %% C major for guitar, no barre, using defaults
    % terse style
    c'1^markup { \fret-diagram-terse #"x;3-3;2-2;o;1-1;o;" }

    %% C major for guitar, barred on third fret
    % verbose style
    % size 1.0
    % roman fret label, finger labels below string, straight barre
    c'1^markup {
        % standard size
        \override #'(size . 1.0) {
            \override #'(fret-diagram-details . (
                (number-type . roman-lower)
                (finger-code . in-dot)
                (barre-type . straight))) {
                \fret-diagram-verbose #'((mute 6)
                    (place-fret 5 3 1)
                    (place-fret 4 5 2)
                    (place-fret 3 5 3)
                    (place-fret 2 5 4)
                    (place-fret 1 3 1)
                    (barre 5 1 3))
            }
        }
    }

    %% C major for guitar, barred on third fret
```

```
% verbose style
% landscape orientation, arabic numbers, M for mute string
% no barre, fret label down or left, small mute label font
c'1`\markup {
  \override #'(fret-diagram-details . (
    (finger-code . below-string)
    (number-type . arabic)
    (label-dir . -1)
    (mute-string . "M")
    (orientation . landscape)
    (barre-type . none)
    (xo-font-magnification . 0.4)
    (xo-padding . 0.3))) {
  \fret-diagram-verbose #'((mute 6)
    (place-fret 5 3 1)
    (place-fret 4 5 2)
    (place-fret 3 5 3)
    (place-fret 2 5 4)
    (place-fret 1 3 1)
    (barre 5 1 3))
}
}

%% simple D chord
% terse style
% larger dots, centered dots, fewer frets
% label below string
d'1`\markup {
  \override #'(fret-diagram-details . (
    (finger-code . below-string)
    (dot-radius . 0.35)
    (dot-position . 0.5)
    (fret-count . 3))) {
  \fret-diagram-terse #"\x;x;o;2-1;3-2;2-3;"
}
}
}
>>
```



Display bracket with only one staff in a system

If there is only one staff in one of the staff types `ChoirStaff` or `StaffGroup`, by default the bracket and the starting bar line will not be displayed. This can be changed by overriding `collapse-height` to set its value to be less than the number of staff lines in the staff.

Note that in contexts such as `PianoStaff` and `GrandStaff` where the systems begin with a brace instead of a bracket, another property has to be set, as shown on the second system in the example.

```
\score {
    \new StaffGroup <<
        % Must be lower than the actual number of staff lines
        \override StaffGroup.SystemStartBracket.collapse-height = #4
        \override Score.SystemStartBar.collapse-height = #4
        \new Staff {
            c'1
        }
    >>
}
\score {
    \new PianoStaff <<
        \override PianoStaff.SystemStartBrace.collapse-height = #4
        \override Score.SystemStartBar.collapse-height = #4
        \new Staff {
            c'1
        }
    >>
}
```



Displaying grob ancestry

When working with grob callbacks, it can be helpful to understand a grob's "ancestry". Most grobs have "parents" which influence the positioning of the grob. X- and Y-parents influence the horizontal and vertical positions for the grob, respectively. Additionally, each parent may have parents of its own.

Unfortunately, there are several aspects of a grob's ancestry that can lead to confusion:

- * The types of parents a grob has may depend on context.
- * For some grobs, the X- and Y-parents are the same.
- * A particular "ancestor" may be related to a grob in multiple ways.
- * The concept of "generations" is misleading.

For example, the `System` grob can be both parent (on the Y-side) and grandparent (twice on the X-side) to a `VerticalAlignment` grob.

This macro prints (to the console) a textual representation of a grob's ancestry.

When called this way

```
{ \once \override NoteHead.before-line-breaking = #display-ancestry c }
```

The following output is generated:

NoteHead X,Y: NoteColumn X: PaperColumn X,Y: System Y: VerticalAxisGroup X: NonMusicalPaperColumn X,Y: System Y: VerticalAlignment X: NonMusicalPaperColumn X,Y: System Y: System

```

#(define (grob-name grob)
  (if (ly:grob? grob)
      (assoc-ref (ly:grob-property grob 'meta) 'name)
      #f))

#(define (get-ancestry grob)
  (if (not (null? (ly:grob-parent grob X)))
      (list (grob-name grob)
            (get-ancestry (ly:grob-parent grob X))
            (get-ancestry (ly:grob-parent grob Y)))
      (grob-name grob)))

#(define (format-ancestry lst padding)
  (string-append
   (symbol->string (car lst))
   "\n"
   (let ((X-ancestry
          (if (list? (cadr lst))
              (format-ancestry (cadr lst) (+ padding 3))
              (symbol->string (cadr lst))))
         (Y-ancestry
          (if (list? (caddr lst))
              (format-ancestry (caddr lst) (+ padding 3))
              (symbol->string (caddr lst))))))
     (if (equal? X-ancestry Y-ancestry)
         (string-append
          (format #f "~&")
          (make-string padding #\space)
          "X,Y: "
          (if (list? (cadr lst))
              (format-ancestry (cadr lst) (+ padding 5))
              (symbol->string (cadr lst))))
         (string-append
          (format #f "~&")
          (make-string padding #\space)
          "X: " X-ancestry
          "\n"
          (make-string padding #\space)
          "Y: " Y-ancestry
          (format #f "~&"))))
        (format #f "~&")))
    (format #f "~&"))

#(define (display-ancestry grob)
  (format (current-error-port)
          "~~3&~a~~2%~a~&"
          (make-string 36 #\_)
          (format-ancestry (get-ancestry grob) 0)))

\relative c' {
  \once \override NoteHead.before-line-breaking = #display-ancestry
  f4
  \once \override Accidental.before-line-breaking = #display-ancestry
}

```

```
\once \override Arpeggio.before-line-breaking = #display-ancestry
<f as c>4\arpeggio
}
```



Dotted harmonics

Artificial harmonics using `\harmonic` do not show dots. To override this behavior, set the context property `harmonicDots`.

```
\relative c''' {
    \time 3/4
    \key f \major
    \set harmonicDots = ##t
    <bes f'\harmonic>2. ~
    <bes f'\harmonic>4. <a e'\harmonic>8( <gis dis'\harmonic> <g d'\harmonic>)
    <fis cis'\harmonic>2.
    <bes f'\harmonic>2.
}
```



Drawing boxes around grobs


The `print`-function can be overridden to draw a box around an arbitrary grob.

```
\relative c'' {
    \override TextScript.stencil =
        #(make-stencil-boxer 0.1 0.3 ly:text-interface::print)
    c'4^"foo"

    \override Stem.stencil =
        #(make-stencil-boxer 0.05 0.25 ly:stem::print)
    \override Score.RehearsalMark.stencil =
        #(make-stencil-boxer 0.15 0.3 ly:text-interface::print)
    b8

    \revert Stem.stencil

    \revert Flag.stencil
    c4. c4
    \mark "F"
    c1
}
```




Drawing circles around various objects

The `\circle` markup command draws circles around various objects, for example fingering indications. For other objects, specific tweaks may be required: this example demonstrates two strategies for rehearsal marks and measure numbers.

```
\relative c' {
    c1
    \set Score.markFormatter =
        #(lambda (mark context)
            (make-circle-markup (format-mark-numbers mark context)))
    \mark \default

    c2 d^{\markup {
        \override #'(thickness . 3) {
            \circle \finger 2
        }
    }}
    \override Score.BarNumber.break-visibility = #all-visible
    \override Score.BarNumber.stencil =
        #(make-stencil-circler 0.1 0.25 ly:text-interface::print)
}
```



Dynamics custom text spanner postfix


Postfix functions for custom crescendo text spanners. The spanners should start on the first note of the measure. One has to use `-\mycresc`, otherwise the spanner start will rather be assigned to the next note.

```
% Two functions for (de)crescendo spanners where you can explicitly give the
% spanner text.
mycresc =
#(define-music-function (parser location mymarkup) (markup?))
  (make-music 'CrescendoEvent
              'span-direction START
              'span-type 'text
              'span-text mymarkup))

mydecresc =
#(define-music-function (parser location mymarkup) (markup?))
  (make-music 'DecrescendoEvent
              'span-direction START
              'span-type 'text
              'span-text mymarkup))

\relative c' {
    c4-\mycresc "custom cresc" c4 c4 c4 |
```

```
c4 c4 c4 c4 |
c4-\mydecresc "custom decresc" c4 c4 c4 |
c4 c4\! c4 c4
}
```



Dynamics text spanner postfix

Custom text spanners can be defined and used with hairpin and text crescendos. \< and \> produce hairpins by default, \cresc etc. produce text spanners by default.

```
% Some sample text dynamic spanners, to be used as postfix operators
crpoco =
```

```
#(make-music 'CrescendoEvent
    'span-direction START
    'span-type 'text
    'span-text "cresc. poco a poco")
```

```
\relative c' {
    c4\cresc d4 e4 f4 |
    g4 a4\! b4\crpoco c4 |
    c4 d4 e4 f4 |
    g4 a4\! b4\< c4 |
    g4\dim a4 b4\decresc c4\!
}
```

```
}
```



Extending glissandi across repeats

A glissando which extends into several \alternative blocks can be simulated by adding a hidden grace note with a glissando at the start of each \alternative block. The grace note should be at the same pitch as the note which starts the initial glissando. This is implemented here with a music function which takes the pitch of the grace note as its argument.

Note that in polyphonic music the grace note must be matched with corresponding grace notes in all other voices.



```
repeatGliss = #(define-music-function (parser location grace)
  (ly:pitch?)
  #{
    % the next two lines ensure the glissando is long enough
    % to be visible
    \once \override Glissando.springs-and-rods
      = #ly:spanner::set-spacing-rods
    \once \override Glissando.minimum-length = #3.5
    \once \hideNotes
    \grace $grace \glissando
```

```
#})

\score {
    \relative c' {
        \repeat volta 3 { c4 d e f\glissando }
        \alternative {
            { g2 d }
            { \repeatGliss f g2 e }
            { \repeatGliss f e2 d }
        }
    }
}

music = \relative c' {
    \voiceOne
    \repeat volta 2 {
        g a b c\glissando
    }
    \alternative {
        { d1 }
        { \repeatGliss c e1 }
    }
}
}

\score {
    \new StaffGroup <<
        \new Staff <<
            \context Voice { \clef "G_8" \music }
        >>
        \new TabStaff <<
            \context TabVoice { \clef "moderntab" \music }
        >>
    >>
}
}
```



Fine-tuning pedal brackets

The appearance of pedal brackets may be altered in different ways.

```
\paper { ragged-right = ##f }
\relative c' {
  c2\sostenutoOn c
  c2\sostenutoOff c
  \once \override Staff.PianoPedalBracket.shorten-pair = #'(-7 . -2)
  c2\sostenutoOn c
  c2\sostenutoOff c
  \once \override Staff.PianoPedalBracket.edge-height = #'(0 . 3)
  c2\sostenutoOn c
  c2\sostenutoOff c
}
}
```



Forcing horizontal shift of notes

When the typesetting engine cannot cope, the following syntax can be used to override typesetting decisions. The units of measure used here are staff spaces.

```
\relative c' <<
{
  <d g>2 <d g>
}
\\
{
  <b f'>2
  \once \override NoteColumn.force-hshift = #1.7
  <b f'>2
}
>>
```



Fret diagrams explained and developed

This snippet shows many possibilities for obtaining and tweaking fret diagrams.

```
<<
\chords {
  a2 a
  \repeat unfold 3 {
    c c c d d
  }
}

\new Voice = "mel" {
  \textLengthOn
  % Set global properties of fret diagram
```

```

\override TextScript.size = #1.2
\override TextScript.fret-diagram-details.finger-code = #'below-string
\override TextScript.fret-diagram-details.dot-color = #'black

%% A chord for ukulele
a'2^markup {
    \override #'(fret-diagram-details . (
        (string-count . 4)
        (dot-color . white)
        (finger-code . in-dot))) {
        \fret-diagram #"4-2-2;3-1-1;2-o;1-o;"
    }
}

%% A chord for ukulele, with formatting defined in definition string
% 1.2 * size, 4 strings, 4 frets, fingerings below string
% dot radius .35 of fret spacing, dot position 0.55 of fret spacing
a'2^markup {
    \override #'(fret-diagram-details . (
        (dot-color . white)
        (open-string . "o"))) {
        \fret-diagram #"s:1.2;w:4;h:3;f:2;d:0.35;p:0.55;4-2-2;3-1-1;2-o;1-o;"}
    }
}

%% These chords will be in normal orientation

%% C major for guitar, barred on third fret
% verbose style
% roman fret label, finger labels below string, straight barre
c'2^markup {
    % 110% of default size
    \override #'(size . 1.1) {
        \override #'(fret-diagram-details . (
            (number-type . roman-lower)
            (finger-code . below-string)
            (barre-type . straight))) {
            \fret-diagram-verbose #'((mute 6)
                (place-fret 5 3 1)
                (place-fret 4 5 2)
                (place-fret 3 5 3)
                (place-fret 2 5 4)
                (place-fret 1 3 1)
                (barre 5 1 3))
        }
    }
}

%% C major for guitar, barred on third fret
%% Double barre used to test barre function
% verbose style
c'2^markup {

```

```
% 110% of default size
\override #'(size . 1.1) {
  \override #'(fret-diagram-details . (
    (number-type . arabic)
    (dot-label-font-mag . 0.9)
    (finger-code . in-dot)
    (fret-label-font-mag . 0.6)
    (fret-label-vertical-offset . 0)
    (label-dir . -1)
    (mute-string . "M")
    (xo-font-magnification . 0.4)
    (xo-padding . 0.3))) {
    \fret-diagram-verbose #'((mute 6)
      (place-fret 5 3 1)
      (place-fret 4 5 2)
      (place-fret 3 5 3)
      (place-fret 2 5 4)
      (place-fret 1 3 1)
      (barre 4 2 5)
      (barre 5 1 3))
  }
}
}

%% C major for guitar, with capo on third fret
% verbose style
c'2^markup {
  % 110% of default size
  \override #'(size . 1.1) {
    \override #'(fret-diagram-details . (
      (number-type . roman-upper)
      (dot-label-font-mag . 0.9)
      (finger-code . none)
      (fret-label-vertical-offset . 0.5)
      (xo-font-magnification . 0.4)
      (xo-padding . 0.3))) {
      \fret-diagram-verbose #'((mute 6)
        (capo 3)
        (open 5)
        (place-fret 4 5 1)
        (place-fret 3 5 2)
        (place-fret 2 5 3)
        (open 1))
    }
  }
}

%% simple D chord
d'2^markup {
  \override #'(fret-diagram-details . (
    (finger-code . below-string)
    (dot-radius . 0.35)
```

```

        (string-thickness-factor . 0.3)
        (dot-position . 0.5)
        (fret-count . 3))) {
    \fret-diagram-terse #"x;x;o;2-1;3-2;2-3;"
}
}

%% simple D chord, large top fret thickness
d'2^markup {
    \override #'(fret-diagram-details . (
        (finger-code . below-string)
        (dot-radius . 0.35)
        (dot-position . 0.5)
        (top-fret-thickness . 7)
        (fret-count . 3))) {
    \fret-diagram-terse #"x;x;o;2-1;3-2;2-3;"
}
}

% These chords will be in landscape orientation
\override TextScript.fret-diagram-details.orientation = #'landscape

%% C major for guitar, barred on third fret
% verbose style
% roman fret label, finger labels below string, straight barre
c'2^markup {
    % 110% of default size
    \override #'(size . 1.1) {
        \override #'(fret-diagram-details . (
            (number-type . roman-lower)
            (finger-code . below-string)
            (barre-type . straight))) {
        \fret-diagram-verbose #'((mute 6)
            (place-fret 5 3 1)
            (place-fret 4 5 2)
            (place-fret 3 5 3)
            (place-fret 2 5 4)
            (place-fret 1 3 1)
            (barre 5 1 3))
        }
    }
}

%% C major for guitar, barred on third fret
%% Double barre used to test barre function
% verbose style
c'2^markup {
    % 110% of default size
    \override #'(size . 1.1) {
        \override #'(fret-diagram-details . (
            (number-type . arabic)
            (dot-label-font-mag . 0.9)

```

```

(finger-code . in-dot)
(fret-label-font-mag . 0.6)
(fret-label-vertical-offset . 0)
(label-dir . -1)
(mute-string . "M")
(xo-font-magnification . 0.4)
(xo-padding . 0.3))) {
\fret-diagram-verbose #'((mute 6)
  (place-fret 5 3 1)
  (place-fret 4 5 2)
  (place-fret 3 5 3)
  (place-fret 2 5 4)
  (place-fret 1 3 1)
  (barre 4 2 5)
  (barre 5 1 3))
}
}
}

%% C major for guitar, with capo on third fret
% verbose style
c'2^markup {
% 110% of default size
\override #'(size . 1.1) {
\override #'(fret-diagram-details . (
  (number-type . roman-upper)
  (dot-label-font-mag . 0.9)
  (finger-code . none)
  (fret-label-vertical-offset . 0.5)
  (xo-font-magnification . 0.4)
  (xo-padding . 0.3))) {
\fret-diagram-verbose #'((mute 6)
  (capo 3)
  (open 5)
  (place-fret 4 5 1)
  (place-fret 3 5 2)
  (place-fret 2 5 3)
  (open 1))
}
}
}

%% simple D chord
d'2^markup {
\override #'(fret-diagram-details . (
  (finger-code . below-string)
  (dot-radius . 0.35)
  (dot-position . 0.5)
  (fret-count . 3))) {
\fret-diagram-terse #"

```

```

%% simple D chord, large top fret thickness
d'2^markup {
    \override #'(fret-diagram-details . (
        (finger-code . below-string)
        (dot-radius . 0.35)
        (dot-position . 0.5)
        (top-fret-thickness . 7)
        (fret-count . 3))) {
        \fret-diagram-terse #"\x;x;o;2-1;3-2;2-3;"
    }
}

% These chords will be in opposing-landscape orientation
\override TextScript.fret-diagram-details.orientation = #'opposing-landscape

%% C major for guitar, barred on third fret
% verbose style
% roman fret label, finger labels below string, straight barre
c'2^markup {
    % 110% of default size
    \override #'(size . 1.1) {
        \override #'(fret-diagram-details . (
            (number-type . roman-lower)
            (finger-code . below-string)
            (barre-type . straight))) {
            \fret-diagram-verbose #'((mute 6)
                (place-fret 5 3 1)
                (place-fret 4 5 2)
                (place-fret 3 5 3)
                (place-fret 2 5 4)
                (place-fret 1 3 1)
                (barre 5 1 3))
        }
    }
}

%% C major for guitar, barred on third fret
%% Double barre used to test barre function
% verbose style
c'2^markup {
    % 110% of default size
    \override #'(size . 1.1) {
        \override #'(fret-diagram-details . (
            (number-type . arabic)
            (dot-label-font-mag . 0.9)
            (finger-code . in-dot)
            (fret-label-font-mag . 0.6)
            (fret-label-vertical-offset . 0)
            (label-dir . -1)
            (mute-string . "M")
            (xo-font-magnification . 0.4)

```

```

        (xo-padding . 0.3))) {
\fret-diagram-verbose #'((mute 6)
                           (place-fret 5 3 1)
                           (place-fret 4 5 2)
                           (place-fret 3 5 3)
                           (place-fret 2 5 4)
                           (place-fret 1 3 1)
                           (barre 4 2 5)
                           (barre 5 1 3))
}
}

%% C major for guitar, with capo on third fret
% verbose style
c'2^markup {
  % 110% of default size
  \override #'(size . 1.1) {
    \override #'(fret-diagram-details . (
      (number-type . roman-upper)
      (dot-label-font-mag . 0.9)
      (finger-code . none)
      (fret-label-vertical-offset . 0.5)
      (xo-font-magnification . 0.4)
      (xo-padding . 0.3))) {
      \fret-diagram-verbose #'((mute 6)
                                (capo 3)
                                (open 5)
                                (place-fret 4 5 1)
                                (place-fret 3 5 2)
                                (place-fret 2 5 3)
                                (open 1))
    }
  }
}


%% simple D chord
d'2^markup {
  \override #'(fret-diagram-details . (
    (finger-code . below-string)
    (dot-radius . 0.35)
    (dot-position . 0.5)
    (fret-count . 3))) {
    \fret-diagram-terse #"x;x;o;2-1;3-2;2-3;"
  }
}

%% simple D chord, large top fret thickness
d'2^markup {
  \override #'(fret-diagram-details . (
    (finger-code . below-string)
    (dot-radius . 0.35)
    
```

```

        (dot-position . 0.5)
        (top-fret-thickness . 7)
        (fret-count . 3))) {
    \fret-diagram-terse #"x;x;o;2-1;3-2;2-3;"
}
}
}
>>

```



Generating custom flags

The `stencil` property of the Flag grob can be set to a custom scheme function to generate the glyph for the flag.

```

#define-public (weight-flag grob)
(let* ((stem-grob (ly:grob-parent grob X))
      (log (- (ly:grob-property stem-grob 'duration-log) 2))
      (is-up? (eqv? (ly:grob-property stem-grob 'direction) UP))
      (yext (if is-up? (cons (* log -0.8) 0) (cons 0 (* log 0.8))))
      (flag-stencil (make-filled-box-stencil '(-0.4 . 0.4) yext))
      (stroke-style (ly:grob-property grob 'stroke-style))
      (stroke-stencil (if (equal? stroke-style "grace")
                           (make-line-stencil 0.2 -0.9 -0.4 0.9 -0.4)
                           empty-stencil)))
  (ly:stencil-add flag-stencil stroke-stencil)))

```

```

% Create a flag stencil by looking up the glyph from the font
#define (inverted-flag grob)
(let* ((stem-grob (ly:grob-parent grob X))
      (dir (if (eqv? (ly:grob-property stem-grob 'direction) UP) "d" "u"))
      (flag (retrieve-glyph-flag "" dir "" grob))
      (line-thickness (ly:staff-symbol-line-thickness grob))
      (stem-thickness (ly:grob-property stem-grob 'thickness))
      (stem-width (* line-thickness stem-thickness))
      (stroke-style (ly:grob-property grob 'stroke-style))
      (stencil (if (null? stroke-style)
                  flag

```

```

          (add-stroke-glyph flag stem-grob dir stroke-style ""))
  (rotated-flag (ly:stencil-rotate-absolute stencil 180 0 0))
  (ly:stencil-translate rotated-flag (cons (- (/ stem-width 2)) 0)))))

snippetexamplenotes = { \autoBeamOff c'8 d'16 c'32 d'64 \acciaccatura {c'8} d'64 }■

{
  \override Score.RehearsalMark.self-alignment-X = #LEFT
  \time 1/4
  \mark "Normal flags"
  \snippetexamplenotes

  \mark "Custom flag: inverted"
  \override Flag.stencil = #inverted-flag
  \snippetexamplenotes

  \mark "Custom flag: weight"
  \override Flag.stencil = #weight-flag
  \snippetexamplenotes

  \mark "Revert to normal"
  \revert Flag.stencil
  \snippetexamplenotes
}

```



Glissandi can skip grobs

NoteColumn grobs can be skipped over by glissandi.

```

\relative c' {
  a2 \glissando
  \once \override NoteColumn.glissando-skip = ##t
  f'''4 d,
}

```



Hairpins with different line styles

Hairpins can take any style from `line-interface` - dashed-line, dotted-line, line, trill or zigzag.

```


\relative c' {
  c2\< c\!
  \override Hairpin.style = #'dashed-line
  c2\< c\!
  \override Hairpin.style = #'dotted-line
}

```

```

c2\< c\!
\override Hairpin.style = #'line
c2\< c\!
\override Hairpin.style = #'trill
c2\< c\!
\override Hairpin.style = #'zigzag
c2\< c\!
\revert Hairpin.style
c2\< c\!
}

```



Horizontally aligning custom dynamics (e.g. "sempre pp" "piu f" "subito p")

Some dynamic expressions involve additional text, like “sempre pp”. Since dynamics are usually centered under the note, the \pp would be displayed way after the note it applies to.

To correctly align the “sempre pp” horizontally, so that it is aligned as if it were only the \pp, there are several approaches:

- * Simply use \once\override DynamicText.X-offset = #-9.2 before the note with the dynamics to manually shift it to the correct position. Drawback: This has to be done manually each time you use that dynamic markup...

- * Add some padding (#:hspace 7.1) into the definition of your custom dynamic mark, so that after lilypond center-aligns it, it is already correctly aligned. Drawback: The padding really takes up that space and does not allow any other markup or dynamics to be shown in that position.

- * Shift the dynamic script \once\override ...X-offset = ... Drawback: \once\override is needed for every invocation!

- * Set the dimensions of the additional text to 0 (using #:with-dimensions '(0 . 0) '(0 . 0)). Drawback: To LilyPond “sempre” has no extent, so it might put other stuff there and create collisions (which are not detected by the collision detection!). Also, there seems to be some spacing, so it’s not exactly the same alignment as without the additional text

- * Add an explicit shifting directly inside the scheme function for the dynamic-script.

- * Set an explicit alignment inside the dynamic-script. By default, this won’t have any effect, only if one sets X-offset! Drawback: One needs to set DynamicText #'X-offset, which will apply to all dynamic texts! Also, it is aligned at the right edge of the additional text, not at the center of pp.

```

\header { title = "Horizontally aligning custom dynamics" }

\paper { ragged-right = ##f }

% Solution 1: Using a simple markup with a particular halign value
% Drawback: It's a markup, not a dynamic command, so \dynamicDown
%           etc. will have no effect
semppMarkup = \markup { \halign #1.4 \italic "sempre" \dynamic "pp" }

```

```
% Solution 2: Using a dynamic script & shifting with
%           \once \override ...X-offset = ..
% Drawback: \once \override needed for every invocation
semppK =
#(make-dynamic-script
  (markup #:line
    (#:normal-text
      #:italic "sempre"
      #:dynamic "pp")))

% Solution 3: Padding the dynamic script so the center-alignment
%           puts it at the correct position
% Drawback: the padding really reserves the space, nothing else can be there
semppT =
#(make-dynamic-script
  (markup #:line
    (#:normal-text
      #:italic "sempre"
      #:dynamic "pp"
      #:hspace 7.1)))

% Solution 4: Dynamic, setting the dimensions of the additional text to 0
% Drawback: To lilypond "sempre" has no extent, so it might put
%           other stuff there => collisions
% Drawback: Also, there seems to be some spacing, so it's not exactly the
%           same alignment as without the additional text
semppM =
#(make-dynamic-script
  (markup #:line
    (#:with-dimensions '(0 . 0) '(0 . 0)
      #:right-align
      #:normal-text
      #:italic "sempre"
      #:dynamic "pp")))

% Solution 5: Dynamic with explicit shifting inside the scheme function
semppG =
#(make-dynamic-script
  (markup #:hskip 0
    #:translate '(-18.85 . 0)
    #:line (#:normal-text
      #:italic "sempre"
      #:dynamic "pp")))

% Solution 6: Dynamic with explicit alignment. This has only effect
%           if one sets X-offset!
% Drawback: One needs to set DynamicText.X-offset!
% Drawback: Aligned at the right edge of the additional text,
%           not at the center of pp
semppMII =
#(make-dynamic-script
  (markup #:line (#:right-align
```

```

#:normal-text
#:italic "sempre"
#:dynamic "pp"))

\context StaffGroup <<
\context Staff = "s" <<
  \set Staff.instrumentName = #"Normal"
  \relative c' {
    \key es \major
    c4\pp c\p c c | c\ff c c\pp c
  }
>>
\context Staff = "sMarkup" <<
  \set Staff.instrumentName = \markup \column { Normal markup }
  \relative c' {
    \key es \major
    c4-\semppMarkup c\p c c | c\ff c c-\semppMarkup c
  }
>>
\context Staff = "sK" <<
  \set Staff.instrumentName = \markup \column { Explicit shifting }
  \relative c' {
    \key es \major
    \once \override DynamicText.X-offset = #-9.2
    c4\semppK c\p c c
    c4\ff c
    \once \override DynamicText.X-offset = #-9.2
    c4\semppK c
  }
>>
\context Staff = "sT" <<
  \set Staff.instrumentName = \markup \column { Right padding }
  \relative c' {
    \key es \major
    c4\semppT c\p c c | c\ff c c\semppT c
  }
>>
\context Staff = "sM" <<
  \set Staff.instrumentName = \markup \column { Setting dimension "to zero" }
  \relative c' {
    \key es \major
    c4\semppM c\p c c | c\ff c c\semppM c
  }
>>
\context Staff = "sG" <<
  \set Staff.instrumentName = \markup \column { Shifting inside dynamics }
  \relative c' {
    \key es \major
    c4\semppG c\p c c | c\ff c c\semppG c
  }
>>
\context Staff = "sMII" <<

```

```
\set Staff.instrumentName = \markup \column { Alignment inside dynamics }
\relative c' {
    \key es \major
    % Setting to ##f (false) gives the same result
    \override DynamicText.X-offset = #0
    c4\semppMII c\p c c | c\ff c c\semppMII c
}
>>
>>
```

Horizontally aligning custom dynamics

How to change fret diagram position

If you want to move the position of a fret diagram, for example, to avoid collision, or to place it between two notes, you have various possibilities:


- 1) modify #'padding or #'extra-offset values (as shown in the first snippet)
- 2) you can add an invisible voice and attach the fret diagrams to the invisible notes in that voice (as shown in the second example).

If you need to move the fret according with a rhythmic position inside the bar (in the example, the third beat of the measure) the second example is better, because the fret is aligned with the third beat itself.

```
harmonies = \chordmode
{
  a8:13
```

```
% THE FOLLOWING IS THE COMMAND TO MOVE THE CHORD NAME
\once \override ChordNames.ChordName.extra-offset = #'(10 . 0)
b8:13 s2.
% THIS LINE IS THE SECOND METHOD
s4 s4 b4:13
}

\score
{
  <<
    \context ChordNames \harmonies
    \context Staff
    {a8^\markup { \fret-diagram "#6-x;5-0;4-2;3-0;2-0;1-2;" } }
% THE FOLLOWING IS THE COMMAND TO MOVE THE FRET DIAGRAM
\once \override TextScript.extra-offset = #'(10 . 0)
b4.~^\markup { \fret-diagram "#6-x;5-2;4-4;3-2;2-2;1-4;" } b4. a8\break
% HERE IS THE SECOND METHOD
  <<
    { a8 b4.~ b4. a8}
    { s4 s4 s4^\markup { \fret-diagram "#6-x;5-2;4-4;3-2;2-2;1-4;" } }
  }
  >>
}
>>
}
```



How to print two rehearsal marks above and below the same barline (method 1)

This method prints two 'rehearsal marks', one on top of the other. It shifts the lower rehearsal mark below the staff and then adds padding above it in order to place the upper rehearsal mark above the staff.


By adjusting the extra-offset and baseline-skip values you can increase or decrease the overall space between the rehearsal mark and the staff.

Because nearly every type of glyph or string can be made to behave like a rehearsal mark it is possible to centre those above and below a bar line.

Adding the appropriate 'break visibility' as shown in snippet 1 will allow you to position two marks at the end of a line as well.

Note: Method 1 is less complex than Method 2 but does not really allow for fine tuning of placement of one of the rehearsal marks without affecting the other. It may also give some problems with vertical spacing, since using `extra-offset` does not change the bounding box of the mark from its original value.

```
\relative c'{
  c d e f |
  \once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
  \once \override Score.RehearsalMark.baseline-skip = #9
  \mark \markup \center-column { \circle 1 \box A }
  g f e d |
  \once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
  \once \override Score.RehearsalMark.baseline-skip = #9
  \mark \markup \center-column { \flat { \bold \small \italic Fine. } }
  g f e d |
  \once \override Score.RehearsalMark.extra-offset = #'(0 . -8.5)
  \once \override Score.RehearsalMark.baseline-skip = #9
  \override Score.RehearsalMark.break-visibility = #begin-of-line-invisible
  \mark \markup \center-column { \fermata \box z }
}
```




How to print two rehearsal marks above and below the same barline (method 2)

This method prints two 'rehearsal marks' - one above the stave and one below, by creating two voices, adding the Rehearsal Mark engraver to each voice - without this no rehearsal mark is printed - and then placing each rehearsal mark UP and DOWN in each voice respectively.

This method (as opposed to method 1) is more complex, but allows for more flexibility, should it be needed to tweak each rehearsal mark independently of the other.

```
\score {
  \relative c'
  <<
  \new Staff {
    <<
    \new Voice \with {
      \consists Mark_engraver
      \consists "Staff_collecting_engraver"
    }
    { c4 d e f
      \mark \markup { \box A }
      c4 d e f
    }
  }
}
```

```
\new Voice \with {
    \consists Mark_engraver
    \consists "Staff_collecting_engraver"
    \override RehearsalMark.direction = #DOWN
}
{s4 s s s
\mark \markup { \circle 1 }
s4 s s s
}
>>
}
>>
\layout {
    \context {
        \Score
        \remove "Mark_engraver"
        \remove "Staff_collecting_engraver"
    }
}
}
```



Inserting a caesura

Caesura marks can be created by overriding the 'text' property of the BreathingSign object. A curved caesura mark is also available.

```
\relative c' {
    \override BreathingSign.text = \markup {
        \musicglyph #'scripts.caesura.straight"
    }
c8 e4. \breathe g8. e16 c4

\override BreathingSign.text = \markup {
    \musicglyph #'scripts.caesura.curved"
}
g8 e'4. \breathe g8. e16 c4
}
```



Keep change clefs full sized

When a clef is changed, the clef sign displayed is smaller than the initial clef. This can be overridden with `full-size-change`.

```
\relative c' {
```

```
\clef "treble"
c1
\clef "bass"
c1
\clef "treble"
c1
\override Staff.Clef.full-size-change = ##t
\clef "bass"
c1
\clef "treble"
c1
\revert Staff.Clef.full-size-change
\clef "bass"
c1
\clef "treble"
c1
}
}
```



Line arrows

Arrows can be applied to text-spanners and line-spanners (such as the Glissando).

```
\relative c' {
  \override TextSpanner.bound-padding = #1.0
  \override TextSpanner.style = #'line
  \override TextSpanner.bound-details.right.arrow = ##t
  \override TextSpanner.bound-details.left.text = #"fof"
  \override TextSpanner.bound-details.right.text = #"gag"
  \override TextSpanner.bound-details.right.padding = #0.6

  \override TextSpanner.bound-details.right.stencil-align-dir-y = #CENTER
  \override TextSpanner.bound-details.left.stencil-align-dir-y = #CENTER

  \override Glissando.bound-details.right.arrow = ##t
  \override Glissando.arrow-length = #0.5
  \override Glissando.arrow-width = #0.25

  a8\startTextSpan gis a4 b\glissando b,
  g'4 c\stopTextSpan c2
}
```



Making an object invisible with the 'transparent' property

Setting the `transparent` property will cause an object to be printed in “invisible ink”: the object is not printed, but all its other behavior is retained. The object still takes up space, it takes part in collisions, and slurs, ties and beams can be attached to it.

This snippet demonstrates how to connect different voices using ties. Normally, ties only connect two notes in the same voice. By introducing a tie in a different voice, and blanking the first up-stem in that voice, the tie appears to cross voices.

```
\relative c' {
  \time 2/4
  <<
  {
    \once \hide Stem
    \once \override Stem.length = #8
    b8 ~ b\noBeam
    \once \hide Stem
    \once \override Stem.length = #8
    g8 ~ g\noBeam
  }
  \\
  {
    b8 g g e
  }
  >>
}
```



Making glissandi breakable

Setting the `breakable` property to `#t` in combination with `after-line-breaking` allows a glissando to break if it occurs at a line break:

```
glissandoSkipOn = {
  \override NoteColumn.glissando-skip = ##t
  \hide NoteHead
  \override NoteHead.no-ledgers = ##t
}

\relative c' {
  \override Glissando.breakable = ##t
  \override Glissando.after-line-breaking = ##t
  f1\glissando |
  \break
  a4 r2. |
  f1\glissando
  \once \glissandoSkipOn
  \break
  a2 a4 r4 |
}
```

The image displays three separate musical staves. Staff 1 has a single note on the G-line. Staff 2 has a note on the A-line with a short horizontal bar extending to the right, followed by a blank space and another note on the C-line. Staff 3 has a note on the E-line with a long horizontal bar extending to the right, followed by a blank space and another note on the G-line.

Manually controlling beam positions

Beam positions may be controlled manually, by overriding the `positions` setting of the Beam grob.

```
\relative c' {
    \time 2/4
    % from upper staff-line (position 2) to center (position 0)
    \override Beam.positions = #'(2 . 0)
    c8 c
    % from center to one above center (position 1)
    \override Beam.positions = #'(0 . 1)
    c8 c
}
```




Mensurstriche layout (bar lines between the staves)

The mensurstriche-layout where the bar lines do not show on the staves but between staves can be achieved with a `StaffGroup` instead of a `ChoirStaff`. The bar line on staves is blanked out by setting the `transparent` property.

```
global = {
    \hide Staff.BarLine
    s1 s
    % the final bar line is not interrupted
    \undo \hide Staff.BarLine
    \bar "|."
}

\new StaffGroup \relative c'' {
    <<
        \new Staff { << \global { c1 c } >> }
        \new Staff { << \global { c c } >> }
    >>
}
```



Moving dotted notes in polyphony

When a dotted note in the upper voice is moved to avoid a collision with a note in another voice, the default is to move the upper note to the right. This behaviour can be over-ridden by using the `prefer-dotted-right` property of `NoteCollision`.

```
\new Staff \relative c' <<
  { f2. f4
    \override Staff.NoteCollision.prefer-dotted-right = ##f
    f2. f4
    \override Staff.NoteCollision.prefer-dotted-right = ##t
    f2. f4
  }
  \\
  { e4 e e e e e e e e}
>>
```



Moving slur positions vertically


The vertical position of a slur can be adjusted using the `positions` property of `Slur`. The property has 2 parameters, the first referring to the left end of the slur and the second to the right. The values of the parameters are not used by LilyPond to make an exact movement of the slur - instead it selects what placement of the slur looks best, taking into account the parameter values. Positive values move the slur up, and are appropriate for notes with stems down. Negative values move downward slurs further down.

```
\relative c' {
  \stemDown
  e4( a)
  \override Slur.positions = #'(1 . 1)
  e4( a)
  \override Slur.positions = #'(2 . 2)
  e4( a)
  \override Slur.positions = #'(3 . 3)
  e4( a)
  \override Slur.positions = #'(4 . 4)
  e4( a)
  \override Slur.positions = #'(5 . 5)
  e4( a)
  \override Slur.positions = #'(0 . 5)
  e4( a)
  \override Slur.positions = #'(5 . 0)
  e4( a)
  \stemUp
  \override Slur.positions = #'(-5 . -5)
```

```

e4( a)
\stemDown
\revert Slur.positions
e4( a)
}

```




Nesting staves

The property `systemStartDelimiterHierarchy` can be used to make more complex nested staff groups. The command `\set StaffGroup.systemStartDelimiterHierarchy` takes an alphabetical list of the number of staves produced. Before each staff a system start delimiter can be given. It has to be enclosed in brackets and takes as much staves as the brackets enclose. Elements in the list can be omitted, but the first bracket takes always the complete number of staves. The possibilities are `SystemStartBar`, `SystemStartBracket`, `SystemStartBrace`, and `SystemStartSquare`.

```

\new StaffGroup
\relative c' <<
  \set StaffGroup.systemStartDelimiterHierarchy
    = #'(SystemStartSquare (SystemStartBrace (SystemStartBracket a
                                              (SystemStartSquare b) ) c ) d)
  \new Staff { c1 }
  \new Staff { c1 }
>>

```



Overriding articulations of distinct type

Sometimes you may want to affect a single articulation-type. Although it is always possible to use \tweak, it might become tedious to do so for every single sign of a whole score. The following shows how to tweak articulations with a list of custom-settings. One use-case might be to create a style-sheet.

With 2.16.2 it is possible to put the proposed function, \customScripts, into a \layout-block.

% Code by David Nalesnik and Thomas Morley

```

#define (custom-script-tweaks ls)
(lambda (grob)
  (let* ((type (ly:prob-property
                (assoc-ref (ly:grob-properties grob) 'cause)
                'articulation-type))
         (tweaks (assoc-ref ls type)))
    (if tweaks
        (for-each
         (lambda (x) (ly:grob-set-property! grob (car x) (cdr x)))
         tweaks)))))

customScripts =
#define-music-function (parser location settings)(list?)
#{
  \override Script.before-line-breaking =
  #(custom-script-tweaks settings)
}

revertCustomScripts = { \revert Script.before-line-breaking }

%%%%%%%%%%%%%
% Example:
%%%%%%%%%%%%%

% Predefine a list of desired tweaks.
#define my-settings-1
  (
    ("staccato" . ((color . (1 0 0))(padding . 0.5)))
    ("accent" . ((font-size . 0)(color . (1 0 0))))
    ("tenuto" . ((rotation . (45 0 0)) (padding . 2)(font-size . 10)))
    ("staccatissimo" . ((padding . 1) (color . (1 0 0))))
    ("segno" . ((font-size . 0)(color . (1 0 0))))
  )

#define my-settings-2
  (
    ("staccato" . ((color . (0 1 0))))
    ("accent" . ((font-size . 4)(color . (0 1 0))(padding . 1.5)))
    ("tenuto" . ((font-size . 10)))
    ("staccatissimo" . ((padding . 2) (color . (0 1 0))))
    ("coda" . ((color . (0 1 0)) (padding . 1)))
  )

```


```

one =
\relative c'' {
  f1--
  \customScripts #my-settings-1
  f-. f-! f-> f-- f-!\segno
  \revertCustomScripts
  f-> f-.
}

two =
\relative c' {
  f1--
  \customScripts #my-settings-2
  f-. f-! f-> f---> f-!
  f-> f-. \coda
}

\new Staff <<
  \new Voice { \voiceOne \one }
  \new Voice { \voiceTwo \two }
>>

```




Percent repeat count visibility

Percent repeat counters can be shown at regular intervals by setting the context property `repeatCountVisibility`.

```

\relative c'' {
  \set countPercentRepeats = ##
  \set repeatCountVisibility = #(every-nth-repeat-count-visible 5)
  \repeat percent 10 { c1 } \break
  \set repeatCountVisibility = #(every-nth-repeat-count-visible 2)
  \repeat percent 6 { c1 d1 }
}


```



Positioning arpeggios

If you need to extend or shorten an arpeggio, you can modify the upper and lower start positions independently.

```
\relative c' {
  <c e g b>1\arpeggio
  \once \override Arpeggio.positions = #'(-5 . 0)
  <c e g b>1\arpeggio
  \once \override Arpeggio.positions = #'(0 . 5)
  <c e g b>1\arpeggio
  \once \override Arpeggio.positions = #'(-5 . 5)
  <c e g b>1\arpeggio
}
```



Positioning multi-measure rests

Unlike ordinary rests, there is no predefined command to change the staff position of a multi-measure rest symbol of either form by attaching it to a note. However, in polyphonic music multi-measure rests in odd-numbered and even-numbered voices are vertically separated. The positioning of multi-measure rests can be controlled as follows:

```
\relative c'' {
  % Multi-measure rests by default are set under the fourth line
  R1
  % They can be moved using an override
  \override MultiMeasureRest.staff-position = #-2
  R1
  \override MultiMeasureRest.staff-position = #0
  R1
  \override MultiMeasureRest.staff-position = #2
  R1
  \override MultiMeasureRest.staff-position = #3
  R1
  \override MultiMeasureRest.staff-position = #6
  R1
  \revert MultiMeasureRest.staff-position
  \break

  % In two Voices, odd-numbered voices are under the top line
  << { R1 } \\ { a1 } >>
  % Even-numbered voices are under the bottom line
  << { a1 } \\ { R1 } >>
  % Multi-measure rests in both voices remain separate
  << { R1 } \\ { R1 } >>

  % Separating multi-measure rests in more than two voices
  % requires an override
  << { R1 } \\ { R1 } \\
```

```
\once \override MultiMeasureRest.staff-position = #0
{ R1 }
>>

% Using compressed bars in multiple voices requires another override
% in all voices to avoid multiple instances being printed
\compressFullBarRests
<<
\revert MultiMeasureRest.direction
{ R1*3 }
\\
\revert MultiMeasureRest.direction
{ R1*3 }
>>
}
```

Positioning text markups inside slurs

Text markups need to have the `outside-staff-priority` property set to false in order to be printed inside slurs.

```
\relative c' {
  \override TextScript.avoid-slur = #'inside
  \override TextScript.outside-staff-priority = ##f
  c2(^\markup { \halign #-10 \natural } d4.) c8
}
```

Printing a repeat sign at the beginning of a piece


A `.|:` bar line can be printed at the beginning of a piece, by overriding the relevant property:

```
\relative c' {
\once \override Score.BreakAlignment.break-align-orders =
#(make-vector 3 '(instrument-name
  left-edge
  ambitus
  breathing-sign
  clef
  key-signature
  time-signature
  staff-bar
```

```

        custos))
\once \override Staff.TimeSignature.space-alist =
 #'((first-note . (fixed-space . 2.0))
  (right-edge . (extra-space . 0.5))
  ;; free up some space between time signature
  ;; and repeat bar line
  (staff-bar . (extra-space . 1)))
\bar ".|:"
c1
d1
d4 e f g
}

```



Printing bar numbers inside boxes or circles

Bar numbers can also be printed inside boxes or circles.

```

\relative c' {
  % Prevent bar numbers at the end of a line and permit them elsewhere
  \override Score.BarNumber.break-visibility = #end-of-line-invisible
  \set Score.barNumberVisibility = #(every-nth-bar-number-visible 4)

  % Increase the size of the bar number by 2
  \override Score.BarNumber.font-size = #2

  % Draw a box round the following bar number(s)
  \override Score.BarNumber.stencil
    = #(make-stencil-boxer 0.1 0.25 ly:text-interface::print)
  \repeat unfold 5 { c1 }

  % Draw a circle round the following bar number(s)
  \override Score.BarNumber.stencil
    = #(make-stencil-circler 0.1 0.25 ly:text-interface::print)
  \repeat unfold 4 { c1 } \bar "|."
}

```



Printing metronome and rehearsal marks below the staff

By default, metronome and rehearsal marks are printed above the staff. To place them below the staff simply set the `direction` property of `MetronomeMark` or `RehearsalMark` appropriately.

```


\layout { ragged-right = ##f }

{
  % Metronome marks below the staff

```

```
\override Score.MetronomeMark.direction = #DOWN
\tempo 8. = 120
c''1

% Rehearsal marks below the staff
\override Score.RehearsalMark.direction = #DOWN
\mark \default
c''1
}
```



Printing note names with and without an octave marker

The `NoteNames` context can be used to print the text value of notes. The `printOctaveNames` property turns on or off the representation of the octave of the note.

```
scale = \relative c' {
    a4 b c d
    e4 f g a
}

\new Staff {
  <<
  \scale
  \context NoteNames {
    \set printOctaveNames = ##f
    \scale
  }
  >>
  R1
  <<
  \scale
  \context NoteNames {
    \set printOctaveNames = ##t
    \scale
  }
  >>
}
```



Proportional strict notespacing

If `strict-note-spacing` is set spacing of notes is not influenced by bars or clefs within a system. Rather, they are placed just before the note that occurs at the same time. This may cause collisions.


```
\relative c' <<
  \override Score.SpacingSpanner.strict-note-spacing = ##t
  \set Score.proportionalNotationDuration = #(ly:make-moment 1/16)
  \new Staff {
    c8[ c \clef alto c c \grace { d16 } c8 c] c4
    c2 \grace { c16 c16 } c2
  }
  \new Staff {
    c2 \tuplet 3/2 { c8 \clef bass cis,, c } c4
    c1
  }
>>
```



Removing connecting bar lines on StaffGroup PianoStaff or GrandStaff

By default, bar lines in StaffGroup, PianoStaff, or GrandStaff groups are connected between the staves. This behaviour can be overridden on a staff-by-staff basis.

```
\relative c' {
  \new StaffGroup <<
    \new Staff {
      e1 | e
      \once \override Staff.BarLine.allow-span-bar = ##f
      e1 | e | e
    }
    \new Staff {
      c1 | c | c
      \once \override Staff.BarLine.allow-span-bar = ##f
      c1 | c
    }
    \new Staff {
      a1 | a | a | a | a
    }
  >>
}
```




Removing the first empty line

The first empty staff can also be removed from the score by setting the `VerticalAxisGroup` property `remove-first`. This can be done globally inside the `\layout` block, or locally inside the specific staff that should be removed. In the latter case, you have to specify the context (`Staff` applies only to the current staff) in front of the property.

The lower staff of the second staff group is not removed, because the setting applies only to the specific staff inside of which it is written.

```
\layout {
  \context {
    \Staff \RemoveEmptyStaves
    % To use the setting globally, uncomment the following line:
    % \override VerticalAxisGroup.remove-first = ##t
  }
}
\new StaffGroup <<
  \new Staff \relative c' {
    e4 f g a \break
    c1
  }
  \new Staff {
    % To use the setting globally, comment this line,
    % uncomment the line in the \layout block above
    \override Staff.VerticalAxisGroup.remove-first = ##t
    R1 \break
    R
  }
>>
\new StaffGroup <<
  \new Staff \relative c' {
    e4 f g a \break
    c1
  }
  \new Staff {
    R1 \break
    R
  }
>>
```



Rest styles

Rests may be used in various styles.

```
\layout {
    indent = 0
    \context {
        \Staff
        \remove "Time_signature_engraver"
    }
}

\new Staff \relative c {
    \cadenzaOn
    \override Staff.Rest.style = #'mensural
    r\maxima^\markup \typewriter { mensural }
    r\longa r\breve r1 r2 r4 r8 r16 s32 s64 s128 s128
    \bar ""

    \override Staff.Rest.style = #'neomensural
    r\maxima^\markup \typewriter { neomensural }
    r\longa r\breve r1 r2 r4 r8 r16 s32 s64 s128 s128
    \bar ""

    \override Staff.Rest.style = #'classical
    r\maxima^\markup \typewriter { classical }
    r\longa r\breve r1 r2 r4 r8 r16 r32 r64 r128 s128
    \bar ""

    \override Staff.Rest.style = #'default
    r\maxima^\markup \typewriter { default }
    r\longa r\breve r1 r2 r4 r8 r16 r32 r64 r128 s128
}
```

Rhythmic slashes

In “simple” lead-sheets, sometimes no actual notes are written, instead only “rhythmic patterns” and chords above the measures are notated giving the structure of a song. Such a feature is for example useful while creating/transcribing the structure of a song and also when sharing lead sheets with guitarists or jazz musicians. The standard support for this using `\repeat percent` is unsuitable here since the first beat has to be an ordinary note or rest. This example shows two solutions to this problem, by redefining ordinary rests to be printed as slashes. (If the duration of each beat is not a quarter note, replace the `r4` in the definitions with a rest of the appropriate duration).

```
% Macro to print single slash
rs = {
    \once \override Rest.stencil = #ly:percent-repeat-item-interface::beat-slash
    \once \override Rest.thickness = #0.48
    \once \override Rest.slope = #1.7
    r4
}

% Function to print a specified number of slashes
comp = #(define-music-function (parser location count) (integer?)
  #{
    \override Rest.stencil = #ly:percent-repeat-item-interface::beat-slash
    \override Rest.thickness = #0.48
    \override Rest.slope = #1.7
    \repeat unfold $count { r4 }
    \revert Rest.stencil
  })
)

\score {
  \relative c' {
    c4 d e f |
    \rs \rs \rs \rs |
    \comp #4 |
  }
}
```

Separating key cancellations from key signature changes

By default, the accidentals used for key cancellations are placed adjacent to those for key signature changes. This behavior can be changed by overriding the '`break-align-orders`' property of the `BreakAlignment` grob.

The value of '`break-align-orders`' is a vector of length 3, with quoted lists of breakable items as elements. This example only modifies the second list, moving `key-cancellation` before `staff-bar`; by modifying the second list, break alignment behavior only changes in the middle of a system, not at the beginning or the end.

```
\new Staff {
    \override Score.BreakAlignment.break-align-orders =
        ##((left-edge ambitus breathing-sign clef staff-bar
            key-cancellation key-signature time-signature custos)

        (left-edge ambitus breathing-sign clef key-cancellation
            staff-bar key-signature time-signature custos)

        (left-edge ambitus breathing-sign clef key-cancellation
            key-signature staff-bar time-signature custos))


    \key des \major
    c'1
    \bar "||"
    \key bes \major
    c'1
}
```



Setting hairpin behavior at bar lines

If the note which ends a hairpin falls on a downbeat, the hairpin stops at the bar line immediately preceding. This behavior can be controlled by overriding the '`to-barline`' property.

```
\relative c' {
    e4 < e2.
    e1 !
    \override Hairpin.to-barline = ##f
    e4 < e2.
    e1 !
}
```



Setting system separators

System separators can be inserted between systems. Any markup can be used, but `\slashSeparator` has been provided as a sensible default.

```
\paper {
    system-separator-markup = \slashSeparator
}

notes = \relative c' {
    c1 | c \break
    c1 | c \break
    c1 | c
}

\book {
    \score {
        \new GrandStaff <<
            \new Staff \notes
            \new Staff \notes
        >>
    }
}
```



Showing the same articulation above and below a note or chord


By default, LilyPond does not allow the same articulation (e.g., an accent, a fermata, a flageolet, etc.) to be displayed above and below a note. For example, `c4_\fermata^_\fermata` will only show a fermata below. The fermata above will simply be ignored. However, one can stick scripts (just like fingerings) inside a chord, which means it is possible to have as many articulations as desired. This approach has the advantage that it ignores the stem and positions the articulation relative to the note head. This can be seen in the case of the flageolets in the snippet. To mimic the behaviour of scripts outside a chord, 'add-stem-support' would be required. So, the solution is to write the note as a chord and add the articulations inside the `<...>`. The direction will always be above, but one can tweak this via a `\tweak`:

```
% The same as \flageolet, just a little smaller
smallFlageolet =
#(let ((m (make-articulation "flageolet")))
  (set! (ly:music-property m 'tweaks)
        (acons 'font-size -2
              (ly:music-property m 'tweaks)))
  m)

\relative c' {
  s4^"Wrong:"
  c4_\fermata^_\fermata % The second fermata is ignored!
  <e d'>4^\smallFlageolet_\smallFlageolet

  s4^"Works if written inside a chord:"
  <e_\smallFlageolet d'^\smallFlageolet>4
  <e_\flageolet d'^\flageolet>4
  <e_\smallFlageolet^\smallFlageolet>4
  <e_\fermata^\fermata>4
}
```

Wrong: Works if written inside a chord:




String number extender lines

Make an extender line for string number indications, showing that a series of notes is supposed to be played all on the same string.

```
stringNumberSpanner =
#(define-music-function (parser location StringNumber) (string?))
#{
  \override TextSpanner.style = #'solid
  \override TextSpanner.font-size = #-5
  \override TextSpanner.bound-details.left.stencil-align-dir-y = #CENTER
  \override TextSpanner.bound-details.left.text = \markup { \circle \number #StringNumber
#})
```

```
\relative c {
```

```
\clef "treble_8"
\stringNumberSpanner "5"
\textSpannerDown
a8\startTextSpan
b c d e f\stopTextSpan
\stringNumberSpanner "4"
g\startTextSpan a
bes4 a g2\stopTextSpan
}
```



Suppressing warnings for clashing note columns

If notes from two voices with stems in the same direction are placed at the same position, and both voices have no shift or the same shift specified, the error message ‘warning: ignoring too many clashing note columns’ will appear when compiling the LilyPond file. This message can be suppressed by setting the ‘ignore-collision’ property of the NoteColumn object to #t. Please note that this does not just suppress warnings but stops LilyPond trying to resolve collisions at all and so may have unintended results unless used with care.

```
ignore = \override NoteColumn.ignore-collision = ##t
```

```
\relative c' {
  <<
    \ignore
    { \stemDown f2 g }
  \\
  { c2 c, }
  >>
}
```



Time signature in parentheses - method 3

Another way to put the time signature in parenthesis

```
\relative c'' {
  \override Staff.TimeSignature.stencil = #(lambda (grob)
    (parenthesize-stencil (ly:time-signature::print grob) 0.1 0.4 0.4 0.1 ))
  \time 2/4
  a4 b8 c
}
```



Time signature in parentheses

The time signature can be enclosed within parentheses.

```
\relative c' {
    \override Staff.TimeSignature.stencil = #(lambda (grob)
        (bracketify-stencil (ly:time-signature::print grob) Y 0.1 0.2 0.1))
    \time 2/4
    a4 b8 c
}
```



Time signature printing only the numerator as a number (instead of the fraction)

Sometimes, a time signature should not print the whole fraction (e.g. $7/4$), but only the numerator (7 in this case). This can be easily done by using `\override Staff.TimeSignature.style = #'single-digit` to change the style permanently. By using `\revert Staff.TimeSignature.style`, this setting can be reversed. To apply the single-digit style to only one time signature, use the `\override` command and prefix it with a `\once`.

```
\relative c' {
    \time 3/4
    c4 c c
    % Change the style permanently
    \override Staff.TimeSignature.style = #'single-digit
    \time 2/4
    c4 c
    \time 3/4
    c4 c c
    % Revert to default style:
    \revert Staff.TimeSignature.style
    \time 2/4
    c4 c
    % single-digit style only for the next time signature
    \once \override Staff.TimeSignature.style = #'single-digit
    \time 5/4
    c4 c c c c
    \time 2/4
    c4 c
}
```



Transcription of Ancient music with incipit

As a workaround to get real incipits which are independent from the main score these are included as a markup into the field normally used for the instrument name. As for now lyrics can only be added as a direct markup. It doesn't unfortunately conform with the spacing of the main lyrics.

```
global = {
    \set Score.skipBars = ##t
    \key g \major
    \time 4/4
    %make the staff lines invisible on staves
    \hide Staff.BarLine
    \skip 1*8 % the actual music
    % let finis bar go through all staves
    \override Staff.BarLine.transparent = ##f
    % finis bar
    \bar "|."
}

discantusNotes = {
    \transpose c' c'' {
        \clef treble
        d'2. d'4 |
        b e' d'2 |
        c'4 e'4.( d'8 c' b |
        a4) b a2 |
        b4.( c'8 d'4) c'4 |
        \once \hide NoteHead c'1 |
        b\breve |
    }
}

discantusLyrics = \lyricmode {
    Ju -- bi -- |
    la -- te De -- |
    o, om --
    nis ter -- |
    ra, __ om- |
    "..." |
    -us. |
}

altusNotes = {
    \transpose c' c'' {
        \clef treble
        r2 g2. e4 fis g | % two bars
        a2 g4 e |
        fis g4.( fis16 e fis4) |
        g1 |
        \once \hide NoteHead g1 |
        g\breve |
    }
}

altusLyrics = \lyricmode {
    Ju -- bi -- la -- te | % two bars
    De -- o, om --
    nis ter -- ra, |
```

```
"..." |
-us. |
}

tenorNotes = {
    \transpose c' c' {
        \clef "treble_8"
        R1 |
        R1 |
        R1 |
        r2 d'2. d'4 b e' | % two bars
        \once \hide NoteHead e'1 |
        d'\breve |
    }
}

tenorLyrics = \lyricmode {
    Ju -- bi -- la -- te | % two bars
    "..." |
    -us.
}

bassusNotes = {
    \transpose c' c' {
        \clef bass
        R1 |
        R1 |
        R1 |
        R1 |
        g2. e4 |
        \once \hide NoteHead e1 |
        g\breve |
    }
}

bassusLyrics = \lyricmode {
    Ju -- bi- |
    "..." |
    -us.
}

incipitDiscantus = \markup {
    \score {
        {
            \set Staff.instrumentName = #"Discantus"
            \override NoteHead.style = #'neomensural
            \override Rest.style = #'neomensural
            \override Staff.TimeSignature.style = #'neomensural
            \cadenzaOn
            \clef "neomensural-c1"
            \key f \major
            \time 2/2
        }
    }
}
```

```
c'1._"IV-" s2  %two bars
\skip 1*8 % eight bars
}
\layout {
  \context {
    \Voice
    \remove "Ligature_bracket_engraver"
    \consists "Mensural_ligature_engraver"
  }
  line-width = 4.5\cm
}
}

incipitAltus = \markup {
  \score {
    {
      \set Staff.instrumentName = #"Altus "
      \override NoteHead.style = #'neomensural
      \override Rest.style = #'neomensural
      \override Staff.TimeSignature.style = #'neomensural
      \cadenzaOn
      \clef "neomensural-c3"
      \key f \major
      \time 2/2
      r1          % one bar
      f'1._"IV-" s2  % two bars
      \skip 1*7 % seven bars
    }
    \layout {
      \context {
        \Voice
        \remove "Ligature_bracket_engraver"
        \consists "Mensural_ligature_engraver"
      }
      line-width = 4.5\cm
    }
  }
}

incipitTenor = \markup {
  \score {
    {
      \set Staff.instrumentName = #"Tenor "
      \override NoteHead.style = #'neomensural
      \override Rest.style = #'neomensural
      \override Staff.TimeSignature.style = #'neomensural
      \cadenzaOn
      \clef "neomensural-c4"
      \key f \major
      \time 2/2
      r\longa  % four bars
    }
  }
}
```

```

r\breve % two bars
r1       % one bar
c'1._"IV-" s2   % two bars
\skip 1   % one bar
}
\layout {
  \context {
    \Voice
    \remove "Ligature_bracket_engraver"
    \consists "Mensural_ligature_engraver"
  }
  line-width = 4.5\cm
}
}
}

incipitBassus = \markup {
\score {
{
  \set Staff.instrumentName = #'Bassus
  \override NoteHead.style = #'neomensural
  \override Rest.style = #'neomensural
  \override Staff.TimeSignature.style = #'neomensural
  \cadenzaOn
  \clef "bass"
  \key f \major
  \time 2/2
  % incipit
  r\maxima % eight bars
  f1._"IV-" s2   % two bars
}
\layout {
  \context {
    \Voice
    \remove "Ligature_bracket_engraver"
    \consists "Mensural_ligature_engraver"
  }
  line-width = 4.5\cm
}
}
}

%StaffGroup is used instead of ChoirStaff to get bar lines between systems
\score {
<<
  \new StaffGroup = choirStaff <<
  \new Voice = "discantusNotes" <<
    \global
    \set Staff.instrumentName = \incipitDiscantus
    \discantusNotes
  >>
  \new Lyrics = "discantusLyrics" \lyricsto discantusNotes { \discantusLyrics }■
}

```

```
\new Voice = "altusNotes" <<
    \global
    \set Staff.instrumentName = \incipitAltus
    \altusNotes
>>
\new Lyrics = "altusLyrics" \lyricsto altusNotes { \altusLyrics }


\new Voice = "tenorNotes" <<
    \global
    \set Staff.instrumentName = \incipitTenor
    \tenorNotes
>>
\new Lyrics = "tenorLyrics" \lyricsto tenorNotes { \tenorLyrics }


\new Voice = "bassusNotes" <<
    \global
    \set Staff.instrumentName = \incipitBassus
    \bassusNotes
>>
>>
\new Lyrics = "bassusLyrics" \lyricsto bassusNotes { \bassusLyrics }
%Keep the bass lyrics outside of the staff group to avoid bar lines
%between the lyrics.
>>


\layout {
    \context {
        \Score
        % no bars in staves
        \hide BarLine
    }
    % the next three instructions keep the lyrics between the bar lines
    \context {
        \Lyrics
        \consists "Bar_engraver"
        \hide BarLine
    }
    \context {
        \StaffGroup
        \consists "Separating_line_group_engraver"
    }
    \context {
        \Voice
        % no slurs
        \hide Slur
        % Comment in the below "\remove" command to allow line
        % breaking also at those barlines where a note overlaps
        % into the next bar. The command is commented out in this
        % short example score, but especially for large scores, you
        % will typically yield better line breaking and thus improve
        % overall spacing if you comment in the following command.
    }
}
```

```
%\remove "Forbid_line_break_engraver"
}
indent = 5\cm
}
}
```

Discantus 

Altus 

Tenor 

Bassus 



Tweaking clef properties

The command `\clef "treble_8"` is equivalent to setting `clefGlyph`, `clefPosition` (which controls the vertical position of the clef), `middleCPosition` and `clefTransposition`. A clef is printed when any of the properties except `middleCPosition` are changed.

Note that changing the glyph, the position of the clef, or the octavation does not in itself change the position of subsequent notes on the staff: the position of middle C must also be specified to do this. In order to get key signatures on the correct staff lines, `middleCClefPosition` must also be set. The positional parameters are relative to the staff center line, positive numbers displacing upwards, counting one for each line and space. The `clefTransposition` value would normally be set to 7, -7, 15 or -15, but other values are valid.

When a clef change takes place at a line break the new clef symbol is printed at both the end of the previous line and the beginning of the new line by default. If the warning clef at the end of the previous line is not required it can be suppressed by setting the `Staff` property `explicitClefVisibility` to the value `end-of-line-invisible`. The default behavior can be recovered with `\unset Staff.explicitClefVisibility`.

The following examples show the possibilities when setting these properties manually. On the first line, the manual changes preserve the standard relative positioning of clefs and notes, whereas on the second line, they do not.

```
\layout { ragged-right = ##t }
{
    % The default treble clef
    \key f \major
    c'1
    % The standard bass clef
    \set Staff.clefGlyph = #"clefs.F"
    \set Staff.clefPosition = #2
    \set Staff.middleCPosition = #6
    \set Staff.middleCClefPosition = #6
    \key g \major
    c'1
    % The baritone clef
    \set Staff.clefGlyph = #"clefs.C"
    \set Staff.clefPosition = #4
    \set Staff.middleCPosition = #4
    \set Staff.middleCClefPosition = #4
    \key f \major
    c'1
    % The standard choral tenor clef
    \set Staff.clefGlyph = #"clefs.G"
    \set Staff.clefPosition = #-2
    \set Staff.clefTransposition = #-7
    \set Staff.middleCPosition = #1
    \set Staff.middleCClefPosition = #1
    \key f \major
    c'1
    % A non-standard clef
    \set Staff.clefPosition = #0
    \set Staff.clefTransposition = #0
    \set Staff.middleCPosition = #-4
    \set Staff.middleCClefPosition = #-4
    \key g \major
    c'1 \break

    % The following clef changes do not preserve
    % the normal relationship between notes, key signatures
    % and clefs:

    \set Staff.clefGlyph = #"clefs.F"
    \set Staff.clefPosition = #2
    c'1
    \set Staff.clefGlyph = #"clefs.G"
    c'1
    \set Staff.clefGlyph = #"clefs.C"
    c'1
    \set Staff.clefTransposition = #7
    c'1
```

```
\set Staff.clefTransposition = #0
\set Staff.clefPosition = #0
c'1

% Return to the normal clef:

\set Staff.middleCPosition = #0
c'1
}
```



Tweaking grace layout within music

The layout of grace expressions can be changed throughout the music using the functions `add-grace-property` and `remove-grace-property`. The following example undefines the `Stem` direction for this grace, so that stems do not always point up, and changes the default note heads to crosses.

```
\relative c' {
  \new Staff {
    $(remove-grace-property 'Voice 'Stem 'direction)
    $(add-grace-property 'Voice 'NoteHead 'style 'cross)
    \new Voice {
      \acciaccatura { f16 } g4
      \grace { d16 e } f4
      \appoggiatura { f,,32 g a } e2
    }
  }
}
```



Using alternative flag styles

Alternative styles of flag on eighth and shorter notes can be displayed by overriding the `stencil` property of `Flag`. Valid values are `modern-straight-flag` and `old-straight-flag`.

```
testnotes = {
  \autoBeamOff
  c8 d16 c32 d64 \acciaccatura { c8 } d64 r4
}

\relative c' {
  \time 2/4
```

```
\testnotes

\override Flag.stencil = #modern-straight-flag
\testnotes

\override Flag.stencil = #old-straight-flag
\testnotes

\revert Flag.stencil
\testnotes
}
```



Using ly:grob-object to access grobs with \tweak

Some grobs can be accessed “laterally” from within another grob’s callback. These are usually listed as “layout objects” in the “Internal properties” section of a grob-interface. The function `ly:grob-object` is used to access these grobs.

Demonstrated below are some ways of accessing grobs from within a NoteHead callback, but the technique is not limited to NoteHeads. However, the NoteHead callback is particularly important, since it is the implicit callback used by the `\tweak` command.

The example function defined below ("display-grobs") is probably not that useful, but it demonstrates that the grobs are indeed being accessed.

Example console output:

```
----- #-Grob Accidental - #-Grob Arpeggio - #-Grob Stem -
#(define (notehead-get-accidental notehead)
  ;;= notehead is grob
  (ly:grob-object notehead 'accidental-grob))

#(define (notehead-get-arpeggio notehead)
  ;;= notehead is grob
  (let ((notecolumn (notehead-get-notecolumn notehead)))
    (ly:grob-object notecolumn 'arpeggio)))

#(define (notehead-get-notecolumn notehead)
  ;;= notehead is grob
  (ly:grob-parent notehead X))

#(define (notehead-get-stem notehead)
  ;;= notehead is grob
  (let ((notecolumn (notehead-get-notecolumn notehead)))
    (ly:grob-object notecolumn 'stem)))
```

```

#(define (display-grobs notehead)
  ;; notehead is grob
  (let ((accidental (notehead-get-accidental notehead))
        (arpeggio (notehead-get-arpeggio notehead))
        (stem (notehead-get-stem notehead)))
    (format (current-error-port) "~~2&~a\n" (make-string 20 #\‐))
    (for-each
      (lambda (x) (format (current-error-port) "~~a\n" x))
      (list accidental arpeggio stem)))))

\relative c' {
  %% display grobs for each note head:
  \%override NoteHead.before-line-breaking = #display-grobs
  <c
  %% or just for one:
  \tweak before-line-breaking #display-grobs
  es
  g>1\arpeggio
}

```



Using PostScript to generate special note head shapes

When a note head with a special shape cannot easily be generated with graphic markup, PostScript code can be used to generate the shape. This example shows how a parallelogram-shaped note head is generated.

```

parallelogram =
#(ly:make-stencil (list 'embedded-ps
  "gsave
  currentpoint translate
  newpath
  0 0.25 moveto
  1.3125 0.75 lineto
  1.3125 -0.25 lineto
  0 -0.75 lineto
  closepath
  fill
  grestore" )
  (cons 0 1.3125)
  (cons -.75 .75))

myNoteHeads = \override NoteHead.stencil = \parallelogram
normalNoteHeads = \revert NoteHead.stencil

\relative c' {
  \myNoteHeads
  g4 d'
  \normalNoteHeads
  <f, \tweak stencil \parallelogram b e>4 d
}

```


```
}
```



Using the \tweak command to tweak individual grobs

With the `\tweak` command, every grob can be tuned directly. Here are some examples of available tweaks.

```
\relative c' {
    \time 2/4
    \set fingeringOrientations = #'(right)
    <
        \tweak font-size #3 c
        \tweak color #red d-\tweak font-size #8 -4
        \tweak style #'cross g
        \tweak duration-log #2 a
    >2
}
```



Vertically aligned dynamics and textscripts

All `DynamicLineSpanner` objects (hairpins and dynamic texts) are placed with their reference line at least 'staff-padding from the staff, unless other notation forces them to be farther. Setting 'staff-padding to a sufficiently large value aligns the dynamics.

The same idea, together with `\textLengthOn`, is used to align the text scripts along their baseline.

```
\markup \vspace #1 %avoid LSR-bug

music = \relative c' {
    a'2\p b\f
    e4\p f\f\> g, b\p
    c2^\markup { \huge gorgeous } c^\markup { \huge fantastic }
}

{
    \music
    \break
    \override DynamicLineSpanner.staff-padding = #3
    \textLengthOn
    \override TextScript.staff-padding = #1
    \music
}
```

The image displays two staves of music. The top staff is in common time (indicated by 'c') and the bottom staff is in 4/4 time (indicated by '4'). Both staves begin with a quarter note dynamic 'p'. The second measure has a dynamic 'f'. The third measure has a dynamic 'p'. The fourth measure has a dynamic 'f' followed by a dynamic 'p' on the eighth note. The fifth measure has a dynamic 'p'. The sixth measure has a dynamic 'p'. The lyrics 'gorgeous' and 'fantastic' are placed above the notes in the top staff, and 'gorgeous' and 'fantastic' are placed below the notes in the bottom staff.

Vertically aligning ossias and lyrics

This snippet demonstrates the use of the context properties `alignBelowContext` and `alignAboveContext` to control the positioning of lyrics and ossias.

```
\paper {
    ragged-right = ##t
}

\relative c' <<
    \new Staff = "1" { c4 c s2 }
    \new Staff = "2" { c4 c s2 }
    \new Staff = "3" { c4 c s2 }
    { \skip 2
      <<
        \lyrics {
            \set alignBelowContext = #'1"
            lyrics4 below
        }
        \new Staff \with {
            alignAboveContext = #'3"
            fontSize = #-2
            \override StaffSymbol.staff-space = #(magstep -2)
            \remove "Time_signature_engraver"
        } {
            \tuplet 6/4 {
                \override TextScript.padding = #3
                c8[{"ossia above" d e d e f}]
            }
        }
    >>
}
>>
```



Vertically centering paired figured bass extenders

Where figured bass extender lines are being used by setting `useBassFigureExtenders` to true, pairs of congruent figured bass extender lines are vertically centered if `figuredBassCenterContinuations` is set to true.

```
<<
\relative c' {
  c8 c b b a a c16 c b b
  c8 c b b a a c16 c b b
  c8 c b b a a c c b b
}
\figures {
  \set useBassFigureExtenders = ##t
  <6+ 4 3>4 <6 4 3>8 r
  <6+ 4 3>4 <6 4 3>8 <4 3+>16 r
  \set figuredBassCenterContinuations = ##t
  <6+ 4 3>4 <6 4 3>8 r
  <6+ 4 3>4 <6 4 3>8 <4 3+>16 r
  \set figuredBassCenterContinuations = ##f
  <6+ 4 3>4 <6 4 3>8 r
  <6+ 4 3>4 <6 4 3>8 <4 3+>8
}
>>
```

Paper and layout


Section “Spacing issues” in *Notation Reference*

Aligning and centering instrument names

The horizontal alignment of instrument names is tweaked by changing the `Staff.InstrumentName #'self-alignment-X` property. The `\layout` variables `indent` and `short-indent` define the space in which the instrument names are aligned before the first and the following systems, respectively.

```
\paper {
    left-margin = 3\cm
}

\score {
    \new StaffGroup <<
        \new Staff {
            \override Staff.InstrumentName.self-alignment-X = #LEFT
            \set Staff.instrumentName = \markup \left-column {
                "Left aligned"
                "instrument name"
            }
            \set Staff.shortInstrumentName = #"Left"
            c''1
            \break
            c''1
        }
        \new Staff {
            \override Staff.InstrumentName.self-alignment-X = #CENTER
            \set Staff.instrumentName = \markup \center-column {
                Centered
                "instrument name"
            }
            \set Staff.shortInstrumentName = #"Centered"
            g'1
            g'1
        }
        \new Staff {
            \override Staff.InstrumentName.self-alignment-X = #RIGHT
            \set Staff.instrumentName = \markup \right-column {
                "Right aligned"
                "instrument name"
            }
            \set Staff.shortInstrumentName = #"Right"
            e'1
            e'1
        }
    >>
    \layout {
        ragged-right = ##t
        indent = 4\cm
        short-indent = 2\cm
    }
}
```



Book parts

\bookpart can be used to split a book into several parts. Each part last page can be affected by `ragged-last-bottom`. Header and footer markups can detect a part last page, and make the difference with the book last page.

```
#(set-default-paper-size "a6")
```

```
\book {
  %% book paper, which is inherited by all children bookparts
  \paper {
    ragged-last-bottom = ##t
    %% Page footer: add a different part-tagline at part last page
    oddFooterMarkup = \markup {
      \column {
        \fill-line {
          %% Copyright header field only on book first page.
          \on-the-fly #first-page \fromproperty #'header:copyright
        }
        \fill-line {
          %% Part tagline header field only on each part last page.
          \on-the-fly #part-last-page \fromproperty #'header:parttagline
        }
        \fill-line {
          %% Tagline header field only on book last page.
          \on-the-fly #last-page \fromproperty #'header:tagline
        }
      }
    }
  }
}
```

```
}

}

%% book header, which is inherited by the first bookpart
\header {
    title = "Book title"
    copyright = "Copyright line on book first page"
    parttagline = "Part tagline"
    tagline = "Book tagline"
}

\bookpart {
    %% a different page breaking function may be used on each part
    \paper { page-breaking = #ly:minimal-breaking }
    \header { subtitle = "First part" }
    \markup { The first book part }
    \markup { a page break }
    \pageBreak
    \markup { first part last page }
    \markup \wordwrap { with ragged-last-bottom (see the space below this text) }
}

\bookpart {
    \header { subtitle = "Second part" }
    { c'4 }
}
}
```

Book title

First part

The first book part

a page break

Copyright line on book first page

2
first part last page
with ragged-last-bottom (see the space below this
text)

Part tagline

Book title

Second part




Part tagline
Book tagline

Changing the staff size

Though the simplest way to resize staves is to use `#(set-global-staff-size xx)`, an individual staff's size can be changed by scaling the properties `'staff-space` and `fontSize`.

```
<<
\new Staff {
    \relative c' {
        \dynamicDown
        c8\ff c c c c c c c
    }
}
\new Staff \with {
    fontSize = #-3
    \override StaffSymbol.staff-space = #(magstep -3)
} {
    \clef bass
    c8 c c c c\f c c c
}
>>
```



Clip systems

This code shows how to clip (extract) snippets from a full score.

This file needs to be run separately with `-dclip-systems`; the snippets page may not adequately show the results.

The result will be files named ‘`base-from-start-to-end[-count].eps`’.

If system starts and ends are included, they include extents of the System grob, e.g., instrument names.

Grace notes at the end point of the region are not included.

Regions can span multiple systems. In this case, multiple EPS files are generated.

```
#(ly:set-option 'clip-systems)
#(define output-suffix "1")

origScore = \score {
  \relative c' {
    \set Staff.instrumentName = #"bla"
    c1
    d1
    \grace c16 e1
    \key d \major
    f1 \break
    \clef bass
    g,,1
    fis1
  }
}

\book {
  \score {
    \origScore
    \layout {
      % Each clip-region is a (START . END) pair
      % where both are rhythmic-locations.

      % (make-rhythmic-locations BAR-NUMBER NUM DEN)
      % means NUM/DEN whole-notes into bar numbered BAR-NUMBER

      clip-regions = #(
        (cons
          (make-rhythmic-location 2 0 1)
          (make-rhythmic-location 4 0 1))

        (cons
          (make-rhythmic-location 0 0 1)
          (make-rhythmic-location 4 0 1))
      )
    }
  }
}
```

```
(cons
  (make-rhythmic-location 0 0 1)
  (make-rhythmic-location 6 0 1))
 )
}
}
}

#(ly:set-option 'clip-systems #f)
#(define output-suffix #f)

\book {
  \score { \origScore }
  \markup { \bold \fontsize #6 clips }
  \score {
    \lyrics {
      \markup { from-2.0.1-to-4.0.1-clip.eps }
      \markup {
        \epsfile #X #30.0 #(format #f "~a-1-from-2.0.1-to-4.0.1-clip.eps"
                                     (ly:parser-output-name parser)) }
    }
  }
}
```




Creating blank staves

To create blank staves, generate empty measures then remove the `Bar_number_engraver` from the `Score` context, and the `Time_signature_engraver`, `Clef_engraver` and `Bar_engraver` from the `Staff` context.

```
#(set-global-staff-size 20)

\score {
    {
        \repeat unfold 12 { s1 \break }
    }
    \layout {
        indent = 0\in
        \context {
            \Staff
            \remove "Time_signature_engraver"
            \remove "Clef_engraver"
            \remove "Bar_engraver"
        }
        \context {
            \Score
            \remove "Bar_number_engraver"
        }
    }
}

\paper {
    #(set-paper-size "letter")
    ragged-last-bottom = ##f
    line-width = 7.5\in
    left-margin = 0.5\in
    bottom-margin = 0.25\in
    top-margin = 0.25\in
}
```





Demonstrating all headers

All header fields with special meanings.

```
\header {
    copyright = "copyright"
    title = "title"
    subtitle = "subtitle"
    composer = "composer"
    arranger = "arranger"
    instrument = "instrument"
    metre = "metre"
    opus = "opus"
    piece = "piece"
    poet = "poet"
    texidoc = "All header fields with special meanings."
    copyright = "public domain"
    enteredby = "jcn"
    source = "urtext"
}

\layout {
    ragged-right = ##f
}

\score {
    \relative c' { c1 | c | c | c }
}

\score {
    \relative c' { c1 | c | c | c }
    \header {
        title = "localtitle"
        subtitle = "localsubtitle"
        composer = "localcomposer"
        arranger = "localarranger"
    }
}
```

```

instrument = "localinstrument"
metre = "localmetre"
opus = "localopus"
piece = "localpiece"
poet = "localpoet"
copyright = "localcopyright"
}
}

```

	title	
	subtitle	
poet	instrument	composer
		arranger

piece	opus
-------	------



localpiece	localopus
------------	-----------



Setting system separators

System separators can be inserted between systems. Any markup can be used, but `\slashSeparator` has been provided as a sensible default.

```

\paper {
    system-separator-markup = \slashSeparator
}

notes = \relative c' {
    c1 | c \break
    c1 | c \break
    c1 | c
}

\book {
    \score {
        \new GrandStaff <<
            \new Staff \notes
            \new Staff \notes
        >>
    }
}

```



Table of contents

A table of contents is included using `\markuplist \table-of-contents`. The TOC items are added with the `\tocItem` command.


```
#(set-default-paper-size "a6")

\book {
  \markuplist \table-of-contents
  \pageBreak
  \tocItem \markup { The first score }
  \score {
    {
      c'1 \pageBreak
      \mark "A" \tocItem \markup { Mark A }
      d'1
    }
  }
  \pageBreak
  \tocItem \markup { The second score }
  \score {
    { e'1 }
    \header { piece = "Second score" }
  }
}
```


Table of Contents

The first score	2
Mark A	3
The second score	4


2



3



4
Second score



Music engraving by LilyPond 2.18.2—www.lilypond.org

Vertical aligned StaffGroups without connecting SystemStartBar

This snippet shows how to achieve vertically aligned StaffGroups with a SystemStartBar for each StaffGroup, but without connecting them.

% by Thomas Morley

```
#(set-global-staff-size 18)

\paper {
    indent = 0
    ragged-right = ##f
    print-all-headers = ##t
}

\layout {
    \context {
        \Staff
        \consists "Mark_engraver"
        \override RehearsalMark.self-alignment-X = #LEFT
    }
    \context {
```

```

\StaffGroup
systemStartDelimiterHierarchy =
#'(SystemStartBrace (SystemStartBracket a b))
}

\context {
\Score
\override SystemStartBrace.style = #'bar-line
\omit SystemStartBar
\override SystemStartBrace.padding = #-0.1
\override SystemStartBrace.thickness = #1.6
\remove "Mark_engraver"
\override StaffGrouper.staffgroup-staff-spacing.basic-distance = #15
}
}

%%% EXAMPLE

txt =
\lyricmode {
Wer4 nur den lie -- ben Gott lässt wal2 -- ten4
und4 hof -- fet auf ihn al -- le Zeit2.
}

% First StaffGroup "exercise"

eI =
\relative c' {
\mark \markup {
\bold Teacher:
This is a simple setting of the choral. Please improve it.
}
\key a \minor
\time 4/4
\voiceOne

\partial 4
e4
a b c b
a b gis2
e4\fermata g! g f
e a a gis
a2.\fermata
\bar ":{|."
}

eII =
\relative c' {
\key a \minor
\time 4/4
\voiceTwo
\partial 4
c4
}

```

```
e e e gis
a f e2
b4 b d d
c c d d
c2.
\bar ":{| ."
}

eIII =
\relative c' {
    \key a \minor
    \time 4/4
    \clef bass
    \voiceOne

    \partial 4
    a4
    c b a b
    c d b2
    gis4 g g b
    c a f e
    e2.
}
}

eIV =
\relative c' {
    \key a \minor
    \time 4/4
    \clef bass
    \voiceTwo

    \partial 4
    a,4
    a' gis a e
    a, d e2
    e,4\fermata e' b g
    c f d e
    a,2.\fermata
    \bar ":{| ."
}

exercise =
\new StaffGroup = "exercise"
<<

\new Staff
<<
    \new Voice \eI
    \new Voice \eII
>>

\new Lyrics \txt
```

```
\new Staff
<<
    \new Voice \eIII
    \new Voice \eIV
>>
>>

% Second StaffGroup "simple Bach"

sbI =
\relative c' {
    \markup {\bold Pupil: "Here's my version! "}
    \key a \minor
    \time 4/4
    \voiceOne

    \partial 4
    e4
    a b c b
    a b gis2
    e4\fermata g! g f
    e a a gis
    a2.\fermata
    \bar ":| ."
}

sbII =
\relative c' {
    \key a \minor
    \time 4/4
    \voiceTwo
    \partial 4
    c8 d
    e4 e e8 f g4
    f f e2
    b4 b8 c d4 d
    e8 d c4 b8 c d4
    c2.
    \bar ":| ."
}

sbIII =
\relative c' {
    \key a \minor
    \time 4/4
    \clef bass
    \voiceOne

    \partial 4
    a8 b
    c4 b a b8 c
```

```
d4 d8 c b2
gis4 g g8 a b4
b a8 g f4 e
e2.
}

sbIV =
\relative c' {
    \key a \minor
    \time 4/4
    \clef bass
    \voiceTwo

    \partial 4
    a,4
    a' gis a e
    f8 e d4 e2
    e,4\fermata e' b a8 g
    c4 f8 e d4 e
    a,2.\fermata
    \bar ":"| ."
}

simpleBach =
\new StaffGroup = "simple Bach"
<<

\new Staff
<<
    \new Voice \sbI
    \new Voice \sbII
>>

\new Lyrics \txt

\new Staff
<<
    \new Voice \sbIII
    \new Voice \sbIV
>>
>>

% Third StaffGroup "chromatic Bach"

cbI =
\relative c' {
    \mark \markup {
        \bold "Teacher:"
        \column {
            "Well, you simply copied and transposed a version of J.S.Bach." \blacksquare
            "Do you know this one?"
        }
}
```

```
}

\key a \minor
\time 4/4
\voiceOne

\partial 4
e4
a b c b
a b gis4. fis8
e4\fermata g! g f
e a a8 b gis4
a2.\fermata
\bar ":{| ."
}

cbII =
\relative c' {
    \key a \minor
    \time 4/4
    \voiceTwo
    \partial 4
    c8 d
    e4 e e8 fis gis4
    a8 g! f!4 e2
    b4 e e d
    d8[ cis] d dis e fis e4
    e2.
    \bar ":{| ."
}

cbIII =
\relative c' {
    \key a \minor
    \time 4/4
    \clef bass
    \voiceOne

    \partial 4
    a8 b
    c[ b] a gis8 a4 d,
    e8[ e'] d c b4. a8
    gis4 b c d8 c
    b[ a] a b c b b c16 d
    c2.
}

cbIV =
\relative c' {
    \key a \minor
    \time 4/4
    \clef bass
    \voiceTwo
```

```
\partial 4
a4
c, e a, b
c d e2
e4\fermata e a b8 c
gis[ g] fis f e dis e4
a,2.\fermata
\bar ":{|."
}

chromaticBach =
\new StaffGroup = "chromatic Bach"
<<

\new Staff
<<
  \new Voice \cbI
  \new Voice \cbII
>>

\new Lyrics \txt

\new Staff
<<
  \new Voice \cbIII
  \new Voice \cbIV
>>
>>

% Score

\score {
  <<
  \exercise
  \simpleBach
  \chromaticBach
>>
  \header {
    title = \markup
      \column {
        \combine \null \vspace #1
        "Exercise: Improve the given choral"
        " "
      }
  }
  \layout {
    \context {
      \Lyrics
      \override LyricText.X-offset = #-1
    }
  }
}
```

}

}

Exercise: Improve the given choral

Teacher: This is a simple setting of the choral. Please improve it.

A musical score for two voices (Soprano and Bass) and piano. The key signature is common C. The vocal parts enter at the beginning with quarter notes. The piano accompaniment consists of sustained notes and chords. The lyrics are: Wer nur den lieben Gott lässt walzen.

Pupil: Here's my version!

A musical score for two voices (Soprano and Bass) and piano. The key signature is common C. The vocal parts enter at the beginning with eighth-note patterns. The piano accompaniment consists of eighth-note chords. The lyrics are: Wer nur den lieben Gott lässt walzen.

Teacher: Well, you simply copied and transposed a version of J.S.Bach.
Do you know this one?

A musical score for two voices (Soprano and Bass) and piano. The key signature is common C. The vocal parts enter at the beginning with eighth-note patterns. The piano accompaniment includes eighth-note chords and a melodic line. The lyrics are: Wer nur den lieben Gott lässt walzen.

The image displays three staves of musical notation, likely for a two-part setting (e.g., soprano and basso continuo). The notation is in common time (indicated by '3' at the beginning of each staff) and consists of six measures. The lyrics are written below the notes:

ten und hof - fet auf ihn al - le Zeit

The first staff shows simple quarter note patterns. The second staff adds eighth-note patterns. The third staff adds sixteenth-note patterns, indicating increasing complexity or realization of the harmonic structure.

Titles

Section “Titles and headers” in *Notation Reference*

Adding the current date to a score

With a little Scheme code, the current date can easily be added to a score.

```
% first, define a variable to hold the formatted date:
date = #(strftme "%d-%m-%Y" (localtime (current-time)))

% use it in the title block:
\header {
    title = "Including the date!"
    subtitle = \date
}

\score {
    \relative c' {
        c4 c c c
    }
}
% and use it in a \markup block:
\markup {
    \date
}
```

Including the date!

17-03-2014



17-03-2014

Aligning and centering instrument names

The horizontal alignment of instrument names is tweaked by changing the `Staff.InstrumentName #'self-alignment-X` property. The `\layout` variables `indent` and `short-indent` define the space in which the instrument names are aligned before the first and the following systems, respectively.

```
\paper {
    left-margin = 3\cm
}

\score {
    \new StaffGroup <<
        \new Staff {
            \override Staff.InstrumentName.self-alignment-X = #LEFT
            \set Staff.instrumentName = \markup \left-column {
                "Left aligned"
            }
    >>
}
```

```

    "instrument name"
}
\set Staff.shortInstrumentName = #"Left"
c'1
\break
c'1
}
\new Staff {
\override Staff.InstrumentName.self-alignment-X = #CENTER
\set Staff.instrumentName = \markup \center-column {
    Centered
    "instrument name"
}
\set Staff.shortInstrumentName = #"Centered"
g'1
g'1
}
\new Staff {
\override Staff.InstrumentName.self-alignment-X = #RIGHT
\set Staff.instrumentName = \markup \right-column {
    "Right aligned"
    "instrument name"
}
\set Staff.shortInstrumentName = #"Right"
e'1
e'1
}
>>
\layout {
    ragged-right = ##t
    indent = 4\cm
    short-indent = 2\cm
}
}


```

Left aligned
instrument name

Centered
instrument name

Right aligned
instrument name

The image shows three staves of music. Each staff has a treble clef at the beginning. The first staff, labeled 'Left aligned instrument name', has the word 'Left' above it and 'aligned' below it, with the staff itself containing two notes. The second staff, labeled 'Centered instrument name', has the word 'Centered' above it and 'instrument' below it, with the staff containing two notes. The third staff, labeled 'Right aligned instrument name', has the word 'Right' above it and 'aligned' below it, with the staff containing two notes.



Demonstrating all headers

All header fields with special meanings.

```
\header {
    copyright = "copyright"
    title = "title"
    subtitle = "subtitle"
    composer = "composer"
    arranger = "arranger"
    instrument = "instrument"
    metre = "metre"
    opus = "opus"
    piece = "piece"
    poet = "poet"
    texidoc = "All header fields with special meanings."
    copyright = "public domain"
    enteredby = "jcn"
    source = "urtext"
}

\layout {
    ragged-right = ##f
}

\score {
    \relative c' { c1 | c | c | c }
}

\score {
    \relative c' { c1 | c | c | c }
    \header {
        title = "localtitle"
        subtitle = "localsubtitle"
        composer = "localcomposer"
        arranger = "localarranger"
        instrument = "localinstrument"
        metre = "localmetre"
        opus = "localopus"
        piece = "localpiece"
        poet = "localpoet"
        copyright = "localcopyright"
    }
}
```

	title	
	subtitle	
poet	instrument	composer
		arranger
piece		opus



localpiece localopus



Outputting the version number

By putting the output of `lilypond-version` into a lyric, it is possible to print the version number of LilyPond in a score, or in a document generated with `lilypond-book`. Another possibility is to append the version number to the doc-string, in this manner:

```
\score {
    \new Lyrics {
        \override Score.RehearsalMark.self-alignment-X = #LEFT
        \mark #(string-append "Processed with LilyPond version " (lilypond-version))
        s2
    }
}
```

Processed with LilyPond version 2.18.2

Spacing

Section “Spacing issues” in *Notation Reference*

Adjusting lyrics vertical spacing

This snippet shows how to bring the lyrics line closer to the staff.

% Default layout:

<<

```
\new Staff \new Voice = melody \relative c' {
  c4 d e f
  g4 f e d
  c1
}
\new Lyrics \lyricsto melody { aa aa aa aa aa aa aa aa }
```

```
\new Staff {
  \new Voice = melody \relative c' {
    c4 d e f
    g4 f e d
    c1
  }
}
```

% Reducing the minimum space below the staff and above the lyrics:

```
\new Lyrics \with {
  \override VerticalAxisGroup.nonstaff-relatedstaff-spacing = #'((basic-distance . 1))■
}
\lyricsto melody { aa aa aa aa aa aa aa aa }
```


>>



Allowing fingerings to be printed inside the staff

By default, vertically oriented fingerings are positioned outside the staff. However, this behavior can be canceled. Note: you must use a chord construct <>, even if it is only a single note.

```
\relative c' {
  <c-1 e-2 g-3 b-5>2
  \override Fingering.staff-padding = #'()
  <c-1 e-2 g-3 b-5>4 <g'-0>
}
```



Page label

Page labels may be placed inside music or at top-level, and referred to in markups.

```
#(set-default-paper-size "a6")

#(define-markup-command (toc-line layout props label text)
  (symbol? markup?)
  (interpret-markup layout props
    (markup #:fill-line (text #:page-ref label "8" "?"))))

\book {
  \markup \huge \fill-line { \null Title Page \null }

  \pageBreak

  \label #'toc
  \markup \column {
    \large \fill-line { \null Table of contents \null }
    \toc-line #'toc "Table of contents"
    \toc-line #'firstScore "First Score"
    \toc-line #'markA "Mark A"
    \toc-line #'markB "Mark B"
    \toc-line #'markC "Mark C"
    \toc-line #'unknown "Unknown label"
  }

  \pageBreak

  \label #'firstScore
  \score {
    \new Staff \relative c' {
      c2 c
      \mark \markup {
        A (page \concat { \page-ref #'markA "0" "?" } )
      } \label #'markA
      c2 c
      \pageBreak
      \mark "B" \label #'markB
      d2 d
      d2 d
      \once \override Score.RehearsalMark.break-visibility =
        #begin-of-line-invisible
      \mark "C" \label #'markC
    }
    \header { piece = "First score" }
  }
}
```


2

Table of contents

Table of contents	2
First Score	3
Mark A	3
Mark B	4
Mark C	4
Unknown label	?


3

First score



A (page 3)





Music engraving by LilyPond 2.18.2—www.lilypond.org

Proportional strict notespacing

If `strict-note-spacing` is set spacing of notes is not influenced by bars or clefs within a system. Rather, they are placed just before the note that occurs at the same time. This may cause collisions.

```
\relative c' <<
  \override Score.SpacingSpanner.strict-note-spacing = ##t
  \set Score.proportionalNotationDuration = #(ly:make-moment 1/16)
  \new Staff {
    c8[ c \clef alto c c \grace { d16 } c8 c] c4
    c2 \grace { c16 c16 } c2
  }
  \new Staff {
    c2 \tuplet 3/2 { c8 \clef bass cis,, c } c4
    c1
  }
>>
```



Vertically aligned dynamics and textscripts

All `DynamicLineSpanner` objects (hairpins and dynamic texts) are placed with their reference line at least 'staff-padding' from the staff, unless other notation forces them to be farther. Setting 'staff-padding' to a sufficiently large value aligns the dynamics.

The same idea, together with `\textLengthOn`, is used to align the text scripts along their baseline.

```
\markup \vspace #1 %avoid LSR-bug
```

```
music = \relative c' {
  a'2\p b\f
  e4\p f\f> g, b\p
  c2^\markup { \huge gorgeous } c^\markup { \huge fantastic }
}

{
  \music
  \break
  \override DynamicLineSpanner.staff-padding = #3
  \textLengthOn
  \override TextScript.staff-padding = #1
  \music
}
```

Vertically aligning ossias and lyrics

This snippet demonstrates the use of the context properties `alignBelowContext` and `alignAboveContext` to control the positioning of lyrics and ossias.

```
\paper {
  ragged-right = ##t
}
```

```
\relative c' <<
  \new Staff = "1" { c4 c s2 }
  \new Staff = "2" { c4 c s2 }
  \new Staff = "3" { c4 c s2 }
  { \skip 2
    <<
      \lyrics {
        \set alignBelowContext = #"1"
        lyrics4 below
      }
    \new Staff \with {
      alignAboveContext = #"3"
      fontSize = #-2
      \override StaffSymbol.staff-space = #(magstep -2)
      \remove "Time_signature_engraver"
    } {
      \tuplet 6/4 {
        \override TextScript.padding = #3
        c8[^"ossia above" d e d e f]
      }
    }
  >>
}
>>
```



MIDI

Section “MIDI output” in *Notation Reference*

Changing MIDI output to one channel per voice

When outputting MIDI, the default behavior is for each staff to represent one MIDI channel, with all the voices on a staff amalgamated. This minimizes the risk of running out of MIDI channels, since there are only 16 available per MIDI port, and most devices support only one port.

However, by moving the `Staff_performer` to the `Voice` context, each voice on a staff can have its own MIDI channel, as is demonstrated by the following example: despite being on the same staff, two MIDI channels are created, each with a different `midiInstrument`.

```
\score {
    \new Staff <<
        \new Voice \relative c''' {
            \set midiInstrument = #"flute"
            \voiceOne
            \key g \major
            \time 2/2
            r2 g—"Flute" ~
            g fis ~
            fis4 g8 fis e2 ~
            e4 d8 cis d2
        }
        \new Voice \relative c' {
            \set midiInstrument = #"clarinet"
            \voiceTwo
            b1—"Clarinet"
            a2. b8 a
            g2. fis8 e
            fis2 r
        }
    >>
    \layout { }
    \midi {
        \context {
            \Staff
            \remove "Staff_performer"
        }
        \context {
            \Voice
            \consists "Staff_performer"
        }
        \tempo 2 = 72
    }
}
```



Changing the tempo without a metronome mark

To change the tempo in MIDI output without printing anything, make the metronome mark invisible.

```
\score {
  \new Staff \relative c' {
    \tempo 4 = 160
    c4 e g b
    c4 b d c
    \set Score.tempoHideNote = ##t
    \tempo 4 = 96
    d,4 fis a cis
    d4 cis e d
  }
  \layout { }
  \midi { }
}
}
```



Demo MidiInstruments

Problem: How to know which `midiInstrument` would be best for your composition? Solution: A LilyPond demo file.

```
\header {
  title = "Demo of all midi sounds"
  arranger = "Myself"
}

baseMelody = \relative c' {
  c4.\mf g c16 b' c d
  e16 d e f g4 g'4 r
  R1
}
melody = {
  \tempo 4 = 150
  \baseMelody
}

\score {
  \new Staff <<
    \new Voice \melody
  >>
  \layout { }
}

\score {
  \new Staff <<
    \new Voice {
```

```
r\mf
\set Staff.midiInstrument = #"acoustic grand" \melody
\set Staff.midiInstrument = #"bright acoustic" \melody
\set Staff.midiInstrument = #"electric grand" \melody
\set Staff.midiInstrument = #"honky-tonk" \melody
\set Staff.midiInstrument = #"electric piano 1" \melody
\set Staff.midiInstrument = #"electric piano 2" \melody
\set Staff.midiInstrument = #"harpsichord" \melody
\set Staff.midiInstrument = #"clav" \melody
\set Staff.midiInstrument = #"celesta" \melody
\set Staff.midiInstrument = #"glockenspiel" \melody
\set Staff.midiInstrument = #"music box" \melody
\set Staff.midiInstrument = #"vibraphone" \melody
\set Staff.midiInstrument = #"marimba" \melody
\set Staff.midiInstrument = #"xylophone" \melody
\set Staff.midiInstrument = #"tubular bells" \melody
\set Staff.midiInstrument = #"dulcimer" \melody
\set Staff.midiInstrument = #"drawbar organ" \melody
\set Staff.midiInstrument = #"percussive organ" \melody
\set Staff.midiInstrument = #"rock organ" \melody
\set Staff.midiInstrument = #"church organ" \melody
\set Staff.midiInstrument = #"reed organ" \melody
\set Staff.midiInstrument = #"accordion" \melody
\set Staff.midiInstrument = #"harmonica" \melody
\set Staff.midiInstrument = #"concertina" \melody
\set Staff.midiInstrument = #"acoustic guitar (nylon)" \melody
\set Staff.midiInstrument = #"acoustic guitar (steel)" \melody
\set Staff.midiInstrument = #"electric guitar (jazz)" \melody
\set Staff.midiInstrument = #"electric guitar (clean)" \melody
\set Staff.midiInstrument = #"electric guitar (muted)" \melody
\set Staff.midiInstrument = #"overdriven guitar" \melody
\set Staff.midiInstrument = #"distorted guitar" \melody
\set Staff.midiInstrument = #"acoustic bass" \melody
\set Staff.midiInstrument = #"electric bass (finger)" \melody
\set Staff.midiInstrument = #"electric bass (pick)" \melody
\set Staff.midiInstrument = #"fretless bass" \melody
\set Staff.midiInstrument = #"slap bass 1" \melody
\set Staff.midiInstrument = #"slap bass 2" \melody
\set Staff.midiInstrument = #"synth bass 1" \melody
\set Staff.midiInstrument = #"synth bass 2" \melody
\set Staff.midiInstrument = #"violin" \melody
\set Staff.midiInstrument = #"viola" \melody
\set Staff.midiInstrument = #"cello" \melody
\set Staff.midiInstrument = #"contrabass" \melody
\set Staff.midiInstrument = #"tremolo strings" \melody
\set Staff.midiInstrument = #"pizzicato strings" \melody
\set Staff.midiInstrument = #"orchestral harp" \melody
\set Staff.midiInstrument = #"timpani" \melody
\set Staff.midiInstrument = #"string ensemble 1" \melody
\set Staff.midiInstrument = #"string ensemble 2" \melody
\set Staff.midiInstrument = #"synthstrings 1" \melody
\set Staff.midiInstrument = #"synthstrings 2" \melody
```

```
\set Staff.midiInstrument = #"choir aahs" \melody
\set Staff.midiInstrument = #"voice oohs" \melody
\set Staff.midiInstrument = #"synth voice" \melody
\set Staff.midiInstrument = #"orchestra hit" \melody
\set Staff.midiInstrument = #"trumpet" \melody
\set Staff.midiInstrument = #"trombone" \melody
\set Staff.midiInstrument = #"tuba" \melody
\set Staff.midiInstrument = #"muted trumpet" \melody
\set Staff.midiInstrument = #"french horn" \melody
\set Staff.midiInstrument = #"brass section" \melody
\set Staff.midiInstrument = #"synthbrass 1" \melody
\set Staff.midiInstrument = #"synthbrass 2" \melody
\set Staff.midiInstrument = #"soprano sax" \melody
\set Staff.midiInstrument = #"alto sax" \melody
\set Staff.midiInstrument = #"tenor sax" \melody
\set Staff.midiInstrument = #"baritone sax" \melody
\set Staff.midiInstrument = #"oboe" \melody
\set Staff.midiInstrument = #"english horn" \melody
\set Staff.midiInstrument = #"bassoon" \melody
\set Staff.midiInstrument = #"clarinet" \melody
\set Staff.midiInstrument = #"piccolo" \melody
\set Staff.midiInstrument = #"flute" \melody
\set Staff.midiInstrument = #"recorder" \melody
\set Staff.midiInstrument = #"pan flute" \melody
\set Staff.midiInstrument = #"blown bottle" \melody
\set Staff.midiInstrument = #"shakuhachi" \melody
\set Staff.midiInstrument = #"whistle" \melody
\set Staff.midiInstrument = #"ocarina" \melody
\set Staff.midiInstrument = #"lead 1 (square)" \melody
\set Staff.midiInstrument = #"lead 2 (sawtooth)" \melody
\set Staff.midiInstrument = #"lead 3 (calliope)" \melody
\set Staff.midiInstrument = #"lead 4 (chiff)" \melody
\set Staff.midiInstrument = #"lead 5 (charang)" \melody
\set Staff.midiInstrument = #"lead 6 (voice)" \melody
\set Staff.midiInstrument = #"lead 7 (fifths)" \melody
\set Staff.midiInstrument = #"lead 8 (bass+lead)" \melody
\set Staff.midiInstrument = #"pad 1 (new age)" \melody
\set Staff.midiInstrument = #"pad 2 (warm)" \melody
\set Staff.midiInstrument = #"pad 3 (polysynth)" \melody
\set Staff.midiInstrument = #"pad 4 (choir)" \melody
\set Staff.midiInstrument = #"pad 5 (bowed)" \melody
\set Staff.midiInstrument = #"pad 6 (metallic)" \melody
\set Staff.midiInstrument = #"pad 7 (halo)" \melody
\set Staff.midiInstrument = #"pad 8 (sweep)" \melody
\set Staff.midiInstrument = #"fx 1 (rain)" \melody
\set Staff.midiInstrument = #"fx 2 (soundtrack)" \melody
\set Staff.midiInstrument = #"fx 3 (crystal)" \melody
\set Staff.midiInstrument = #"fx 4 (atmosphere)" \melody
\set Staff.midiInstrument = #"fx 5 (brightness)" \melody
\set Staff.midiInstrument = #"fx 6 (goblins)" \melody
\set Staff.midiInstrument = #"fx 7 (echoes)" \melody
\set Staff.midiInstrument = #"fx 8 (sci-fi)" \melody
```

```

\set Staff.midiInstrument = #"sitar" \melody
\set Staff.midiInstrument = #"banjo" \melody
\set Staff.midiInstrument = #"shamisen" \melody
\set Staff.midiInstrument = #"koto" \melody
\set Staff.midiInstrument = #"kalimba" \melody
\set Staff.midiInstrument = #"bagpipe" \melody
\set Staff.midiInstrument = #"fiddle" \melody
\set Staff.midiInstrument = #"shanai" \melody
\set Staff.midiInstrument = #"tinkle bell" \melody
\set Staff.midiInstrument = #"agogo" \melody
\set Staff.midiInstrument = #"steel drums" \melody
\set Staff.midiInstrument = #"woodblock" \melody
\set Staff.midiInstrument = #"taiko drum" \melody
\set Staff.midiInstrument = #"melodic tom" \melody
\set Staff.midiInstrument = #"synth drum" \melody
\set Staff.midiInstrument = #"reverse cymbal" \melody
\set Staff.midiInstrument = #"guitar fret noise" \melody
\set Staff.midiInstrument = #"breath noise" \melody
\set Staff.midiInstrument = #"seashore" \melody
\set Staff.midiInstrument = #"bird tweet" \melody
\set Staff.midiInstrument = #"telephone ring" \melody
\set Staff.midiInstrument = #"helicopter" \melody
\set Staff.midiInstrument = #"applause" \melody
\set Staff.midiInstrument = #"gunshot" \melody
}
>>
\midi { }
}
```

Demo of all midi sounds

Myself



Templates

Ancient notation template – modern transcription of gregorian music

This example demonstrates how to do modern transcription of Gregorian music. Gregorian music has no measure, no stems; it uses only half and quarter note heads, and special marks, indicating rests of different length.

```
\include "gregorian.ly"

chant = \relative c' {
    \set Score.timing = ##f
    f4 a2 \divisioMinima
    g4 b a2 f2 \divisioMaior
    g4( f) f( g) a2 \finalis
}

verba = \lyricmode {
    Lo -- rem ip -- sum do -- lor sit a -- met
}

\score {
    \new Staff <<
        \new Voice = "melody" \chant
        \new Lyrics = "one" \lyricsTo melody \verba
    >>
    \layout {
        \context {
            \Staff
            \remove "Time_signature_engraver"
            \remove "Bar_engraver"
            \hide Stem
        }
        \context {
            \Voice
            \override Stem.length = #0
        }
        \context {
            \Score
            barAlways = ##t
        }
    }
}
```



Ancient notation template – modern transcription of mensural music

When transcribing mensural music, an incipit at the beginning of the piece is useful to indicate the original key and tempo. While today musicians are used to bar lines in order to faster recognize rhythmic patterns, bar lines were not yet invented during the period of mensural music; in fact, the meter often changed after every few notes. As a compromise, bar lines are often printed between the staves rather than on the staves.

```
global = {
    \set Score.skipBars = ##t

    % incipit
    \once \hide Score.SystemStartBracket
    % Set tight spacing
    \override Score.SpacingSpanner.spacing-increment = #1.0
    \key f \major
    \time 2/2
    \once \override Staff.TimeSignature.style = #'neomensural
    \override Voice.NoteHead.style = #'neomensural
    \override Voice.Rest.style = #'neomensural
    \set Staff.printKeyCancellation = ##f
    \codaOn % turn off bar lines
    \skip 1*10
    \once \override Staff.BarLine.transparent = ##f
    \bar "||"
    \skip 1*1 % need this extra \skip such that clef change comes
              % after bar line
    \bar ""

    % main
    \codaOff % turn bar lines on again
    \once \override Staff.Clef.full-size-change = ##t
    \set Staff.forceClef = ##t
    \key g \major
    \time 4/4
    \override Voice.NoteHead.style = #'default
    \override Voice.Rest.style = #'default

    % Setting printKeyCancellation back to #t must not
    % occur in the first bar after the incipit. Dto. for forceClef.
    % Therefore, we need an extra \skip.
    \skip 1*1
    \set Staff.printKeyCancellation = ##t
    \set Staff.forceClef = ##f

    \skip 1*7 % the actual music

    % let finis bar go through all staves
    \override Staff.BarLine.transparent = ##f

    % finis bar
    \bar "|."
}
```

```
discantusNotes = {
    \transpose c' c'' {
        \set Staff.instrumentName = #"Discantus"

        % incipit
        \clef "neomensural-c1"
        c'1. s2    % two bars
        \skip 1*8 % eight bars
        \skip 1*1 % one bar

        % main
        \clef "treble"
        d'2. d'4 |
        b e' d'2 |
        c'4 e'4.( d'8 c' b |
        a4) b a2 |
        b4.( c'8 d'4) c'4 |
        \once \hide NoteHead c'1 |
        b\breve |

    }
}

discantusLyrics = \lyricmode {
    % incipit
    IV-

    % main
    Ju -- bi -- |
    la -- te De -- |
    o, om --
    nis ter -- |
    ra, __ om- |
    "..." |
    -us. |

}

altusNotes = {
    \transpose c' c'' {
        \set Staff.instrumentName = #"Altus"

        % incipit
        \clef "neomensural-c3"
        r1          % one bar
        f1. s2      % two bars
        \skip 1*7 % seven bars
        \skip 1*1 % one bar

        % main
        \clef "treble"
        r2 g2. e4 fis g | % two bars
        a2 g4 e |
    }
}
```

```
fis g4.( fis16 e fis4) |
g1 |
\once \hide NoteHead g1 |
g\breve |
}
}

altusLyrics = \lyricmode {
% incipit
IV-

% main
Ju -- bi -- la -- te | % two bars
De -- o, om -- |
nis ter -- ra, |
"..." |
-us. |
}

tenorNotes = {
\transpose c' c' {
\set Staff.instrumentName = #"Tenor"

% incipit
\clef "neomensural-c4"
r\longa    % four bars
r\breve    % two bars
r1         % one bar
c'1. s2    % two bars
\skip 1*1 % one bar
\skip 1*1 % one bar

% main
\clef "treble_8"
R1 |
R1 |
R1 |
r2 d'2. d'4 b e' | % two bars
\once \hide NoteHead e'1 |
d'\breve |
}
}

tenorLyrics = \lyricmode {
% incipit
IV-

% main
Ju -- bi -- la -- te | % two bars
"..." |
-us. |
}
```

```
bassusNotes = {  
    \transpose c' c' {  
        \set Staff.instrumentName = #"Bassus"  
  
        % incipit  
        \clef "bass"  
        r\maxima % eight bars  
        f1. s2 % two bars  
        \skip 1*1 % one bar  
  
        % main  
        \clef "bass"  
        R1 |  
        R1 |  
        R1 |  
        R1 |  
        g2. e4 |  
        \once \hide NoteHead e1 |  
        g\breve |  
    }  
}  
  
bassusLyrics = \lyricmode {  
    % incipit  
    IV-  
  
    % main  
    Ju -- bi- |  
    "... |  
    -us. |  
}  
  
\score {  
    \new StaffGroup = choirStaff <<  
        \new Voice =  
            "discantusNotes" << \global \discantusNotes >>  
        \new Lyrics =  
            "discantusLyrics" \lyricsto discantusNotes { \discantusLyrics }  
    \new Voice =  
        "altusNotes" << \global \altusNotes >>  
    \new Lyrics =  
        "altusLyrics" \lyricsto altusNotes { \altusLyrics }  
    \new Voice =  
        "tenorNotes" << \global \tenorNotes >>  
    \new Lyrics =  
        "tenorLyrics" \lyricsto tenorNotes { \tenorLyrics }  
    \new Voice =  
        "bassusNotes" << \global \bassusNotes >>  
    \new Lyrics =  
        "bassusLyrics" \lyricsto bassusNotes { \bassusLyrics }  
    >>  
}
```

```
\layout {
  \context {
    \Score

    % no bars in staves
    \hide BarLine

    % incipit should not start with a start delimiter
    \remove "System_start_delimiter_engraver"
  }
  \context {
    \Voice

    % no slurs
    \hide Slur

    % The command below can be commented out in
    % short scores, but especially for large scores you
    % will typically yield better line breaking and improve
    % overall spacing if you do not comment the command out.

    \remove "Forbid_line_break_engraver"
  }
}
}
```

Discantus  IV-

Altus  IV-

Tenor  IV-

Bassus  IV-

Ju - bi - la - te De -
Ju - bi - la - te
- - - -



The score shows three systems of music. The first system starts with 'o, om - nis ter - ra, om- ... -us.' The second system starts with 'De - o, om - nis ter - ra, ... -us.' The third system starts with 'Ju - bi - la - te ... -us.' The fourth system starts with 'Ju - bi - ... -us.' The music is set in common time (indicated by '8' on the bass staff).

Anglican psalm template

This template shows one way of setting out an Anglican psalm chant. It also shows how the verses may be added as stand-alone text under the music. The two verses are coded in different styles to demonstrate more possibilities.

```

SopranoMusic = \relative g' {
  g1 | c2 b | a1 | \bar "||"
  a1 | d2 c | c b | c1 | \bar "||"
}

AltoMusic = \relative c' {
  e1 | g2 g | f1 |
  f1 | f2 e | d d | e1 |
}

TenorMusic = \relative a {
  c1 | c2 c | c1 |
  d1 | g,2 g | g g | g1 |
}

BassMusic = \relative c {
  c1 | e2 e | f1 |
  d1 | b2 c | g' g | c,1 |
}

global = {
  \time 2/2
}

dot = \markup {
  \raise #0.7 \musicglyph #'dots.dot"
}

tick = \markup {
  \raise #1 \fontsize #-5 \musicglyph #'scripts.rvarcomma"
}

% Use markup to center the chant on the page
\markup {

```

```
\fill-line {
  \score { % centered
    <>
    \new ChoirStaff <<
      \new Staff <<
        \global
        \clef "treble"
        \new Voice = "Soprano" <<
          \voiceOne
          \SopranoMusic
        >>
        \new Voice = "Alto" <<
          \voiceTwo
          \AltoMusic
        >>
      >>
      \new Staff <<
        \clef "bass"
        \global
        \new Voice = "Tenor" <<
          \voiceOne
          \TenorMusic
        >>
        \new Voice = "Bass" <<
          \voiceTwo
          \BassMusic
        >>
      >>
    >>
  >>
  \layout {
    \context {
      \Score
      \override SpacingSpanner.base-shortest-duration = #(ly:make-moment 1/2)
    }
    \context {
      \Staff
      \remove "Time_signature_engraver"
    }
  }
  } % End score
}
} % End markup

\markup {
  \fill-line {
    \column {
      \left-align {
        \null \null \null
        \line {
          \fontsize #5 0
          \fontsize #3 come
        }
      }
    }
  }
}
```

```
    let us \bold sing | unto \dot the | Lord : let
}
\line {
    us heartily
    \concat { re \bold joyce }
    in the | strength of | our
}
\line {
    sal | vation.
}
\null
\line {
    \hspace #2.5 8. Today if ye will hear his voice *
}
\line {
    \concat { \bold hard en }
    \tick not your \tick hearts : as in the pro-
}
\line {
    vocation * and as in the \bold day of tempt- \tick
}
\line {
    -ation \tick in the \tick wilderness.
}
}
}
}
```

O come let us sing | unto the | Lord : let
us heartily rejoice in the | strength of | our
sal | vation.

8. Today if ye will hear his voice *
harden' not your' hearts : as in the pro-
vocation * and as in the **day** of tempt-'
-ation' in the' wilderness.

Hymn template

This code shows one way of setting out a hymn tune when each line starts and ends with a partial measure. It also shows how to add the verses as stand-alone text under the music.

```

Timeline = {
    \time 4/4
    \tempo 4=96
    \partial 2
    s2 | s1 | s2 \breathe s2 | s1 | s2 \bar "||" \break
    s2 | s1 | s2 \breathe s2 | s1 | s2 \bar "||"
}

SopranoMusic = \relative g' {
    g4 g | g g g g | g g g g | g g g g | g2
    g4 g | g g g g | g g g g | g g g g | g2
}

AltoMusic = \relative c' {
    d4 d | d d d d | d d d d | d d d d | d2
    d4 d | d d d d | d d d d | d d d d | d2
}

TenorMusic = \relative a {
    b4 b | b b b b | b b b b | b b b b | b2
    b4 b | b b b b | b b b b | b b b b | b2
}

BassMusic = \relative g {
    g4 g | g g g g | g g g g | g g g g | g2
    g4 g | g g g g | g g g g | g g g g | g2
}

global = {
    \key g \major
}

\score { % Start score
    <<
        \new PianoStaff << % Start pianostaff
        \new Staff << % Start Staff = RH
        \global
        \clef "treble"
        \new Voice = "Soprano" << % Start Voice = "Soprano"
        \Timeline
        \voiceOne
        \SopranoMusic
    >> % End Voice = "Soprano"
    \new Voice = "Alto" << % Start Voice = "Alto"
        \Timeline
        \voiceTwo
        \AltoMusic
    >> % End Voice = "Alto"
}

```

```


>> % End Staff = RH
\new Staff << % Start Staff = LH
  \global
  \clef "bass"
  \new Voice = "Tenor" << % Start Voice = "Tenor"
    \Timeline
    \voiceOne
    \TenorMusic
  >> % End Voice = "Tenor"
  \new Voice = "Bass" << % Start Voice = "Bass"
    \Timeline
    \voiceTwo
    \BassMusic
  >> % End Voice = "Bass"
  >> % End Staff = LH
  >> % End pianostaff
>>
}
} % End score

\markup {
  \fill-line {
    ""
    {
      \column {
        \left-align {
          "This is line one of the first verse"
          "This is line two of the same"
          "And here's line three of the first verse"
          "And the last line of the same"
        }
      }
    }
    ""
  }
}

\paper { % Start paper block
  indent = 0      % don't indent first system
  line-width = 130 % shorten line length to suit music
} % End paper block

```





This is line one of the first verse
 This is line two of the same
 And here's line three of the first verse
 And the last line of the same

Jazz combo template

This is quite an advanced template, for a jazz ensemble. Note that all instruments are notated in \key c \major. This refers to the key in concert pitch; the key will be automatically transposed if the music is within a \transpose section.

```
\header {
    title = "Song"
    subtitle = "(tune)"
    composer = "Me"
    meter = "moderato"
    piece = "Swing"
    tagline = \markup {
        \column {
            "LilyPond example file by Amelie Zapf,"
            "Berlin 07/07/2003"
        }
    }
}

%#(set-global-staff-size 16)
\include "english.ly"

%%%%%% Some macros %%%%%%
sl = {
    \override NoteHead.style = #'slash
    \hide Stem
}
nsl = {
    \revert NoteHead.style
    \undo \hide Stem
}
crOn = \override NoteHead.style = #'cross
crOff = \revert NoteHead.style

% insert chord name style stuff here.

jazzChords = { }

%%%%% Keys 'n' thangs %%%%%%
global = { \time 4/4 }
```

```
Key = { \key c \major }

% ##### Horns #####
% ----- Trumpet -----
trpt = \transpose c d \relative c' {
  \Key
  c1 | c | c |
}
trpHarmony = \transpose c' d {
  \jazzChords
}
trumpet = {
  \global
  \set Staff.instrumentName = #"Trumpet"
  \clef treble
  <<
    \trpt
  >>
}

% ----- Alto Saxophone -----
alto = \transpose c a \relative c' {
  \Key
  c1 | c | c |
}
altoHarmony = \transpose c' a {
  \jazzChords
}
altoSax = {
  \global
  \set Staff.instrumentName = #"Alto Sax"
  \clef treble
  <<
    \alto
  >>
}

% ----- Baritone Saxophone -----
bari = \transpose c a' \relative c {
  \Key
  c1
  c1
  \sl
  d4^"Solo" d d d
  \nsl
}
bariHarmony = \transpose c' a \chordmode {
  \jazzChords s1 s d2:maj e:m7
}
bariSax = {
```

```
\global
\set Staff.instrumentName = #"Bari Sax"
\clef treble
<<
  \bari
>>
}

% ----- Trombone -----
tbone = \relative c {
  \Key
  c1 | c | c
}
tboneHarmony = \chordmode {
  \jazzChords
}
trombone = {
  \global
  \set Staff.instrumentName = #"Trombone"
  \clef bass
  <<
    \tbone
  >>
}

% ##### Rhythm Section #####
% ----- Guitar -----
gtr = \relative c' {
  \Key
  c1
  \sl
  b4 b b b
  \nsl
  c1
}
gtrHarmony = \chordmode {
  \jazzChords
  s1 c2:min7+ d2:maj9
}
guitar = {
  \global
  \set Staff.instrumentName = #"Guitar"
  \clef treble
  <<
    \gtr
  >>
}

%% ----- Piano -----
rhUpper = \relative c' {
  \voiceOne
```

```
\Key
c1 | c | c
}
rhLower = \relative c' {
  \voiceTwo
  \Key
  e1 | e | e
}

lhUpper = \relative c' {
  \voiceOne
  \Key
  g1 | g | g
}
lhLower = \relative c {
  \voiceTwo
  \Key
  c1 | c | c
}

PianoRH = {
  \clef treble
  \global
  \set Staff.midiInstrument = #"acoustic grand"
<<
  \new Voice = "one" \rhUpper
  \new Voice = "two" \rhLower
>>
}
PianoLH = {
  \clef bass
  \global
  \set Staff.midiInstrument = #"acoustic grand"
<<
  \new Voice = "one" \lhUpper
  \new Voice = "two" \lhLower
>>
}

piano = {
<<
  \set PianoStaff.instrumentName = #"Piano"
  \new Staff = "upper" \PianoRH
  \new Staff = "lower" \PianoLH
>>
}

% ----- Bass Guitar -----
Bass = \relative c {
  \Key
  c1 | c | c
}
```

```
bass = {
    \global
    \set Staff.instrumentName = #"Bass"
    \clef bass
    <<
        \Bass
    >>
}

% ----- Drums -----
up = \drummode {
    \voiceOne
    hh4 <hh sn> hh <hh sn>
    hh4 <hh sn> hh <hh sn>
    hh4 <hh sn> hh <hh sn>
}
down = \drummode {
    \voiceTwo
    bd4 s bd s
    bd4 s bd s
    bd4 s bd s
}

drumContents = {
    \global
    <<
        \set DrumStaff.instrumentName = #"Drums"
        \new DrumVoice \up
        \new DrumVoice \down
    >>
}
%% It All Goes Together Here %%%%%%%

\score {
    <<
        \new StaffGroup = "horns" <<
            \new Staff = "trumpet" \trumpet
            \new Staff = "altosax" \altoSax
            \new ChordNames = "barichords" \bariHarmony
            \new Staff = "barisax" \bariSax
            \new Staff = "trombone" \trombone
        >>
        \new StaffGroup = "rhythm" <<
            \new ChordNames = "chords" \gtrHarmony
            \new Staff = "guitar" \guitar
            \new PianoStaff = "piano" \piano
            \new Staff = "bass" \bass
            \new DrumStaff \drumContents
        >>
    >>
}
```

```
\layout {
  \context { \Staff \RemoveEmptyStaves }
  \context {
    \Score
    \override BarNumber.padding = #3
    \override RehearsalMark.padding = #2
    skipBars = ##t
  }
}
\midi { }
```

Song
(tune)

moderato

Me

Swing

Orchestra choir and piano template

This template demonstrates the use of nested `StaffGroup` and `GrandStaff` contexts to subgroup instruments of the same type together, and a way to use `\transpose` so that variables hold music for transposing instruments at concert pitch.

```
#(set-global-staff-size 17)
\paper {
    indent = 3.0\cm % space for instrumentName
    short-indent = 1.5\cm % space for shortInstrumentName
}

fluteMusic = \relative c' { \key g \major g'1 b }
% Pitches as written on a manuscript for Clarinet in A
% are transposed to concert pitch.
clarinetMusic = \transpose c' a
    \relative c'' { \key bes \major bes1 d }
trumpetMusic = \relative c { \key g \major g''1 b }
% Key signature is often omitted for horns
hornMusic = \transpose c' f
    \relative c { d'1 fis }
```

```
percussionMusic = \relative c { \key g \major g1 b }
sopranoMusic = \relative c' { \key g \major g'1 b }
sopranoLyrics = \lyricmode { Lyr -- ics }
altoIMusic = \relative c' { \key g \major g'1 b }
altoIIMusic = \relative c' { \key g \major g'1 b }
altoILyrics = \sopranoLyrics
altoIIILyrics = \lyricmode { Ah -- ah }
tenorMusic = \relative c' { \clef "treble_8" \key g \major g1 b }
tenorLyrics = \sopranoLyrics
pianoRHMUSIC = \relative c { \key g \major g''1 b }
pianoLHMusic = \relative c { \clef bass \key g \major g1 b }
violinIMusic = \relative c' { \key g \major g'1 b }
violinIIMusic = \relative c' { \key g \major g'1 b }
violaMusic = \relative c { \clef alto \key g \major g'1 b }
celloMusic = \relative c { \clef bass \key g \major g1 b }
bassMusic = \relative c { \clef "bass_8" \key g \major g,1 b }

\score {
  <<
  \new StaffGroup = "StaffGroup_woodwinds" <<
    \new Staff = "Staff_flute" {
      \set Staff.instrumentName = #"Flute"
      % shortInstrumentName, midiInstrument, etc.
      % may be set here as well
      \fluteMusic
    }
    \new Staff = "Staff_clarinet" {
      \set Staff.instrumentName =
      \markup { \concat { "Clarinet in B" \flat } }
      % Declare that written Middle C in the music
      % to follow sounds a concert B flat, for
      % output using sounded pitches such as MIDI.
      \transposition bes
      % Print music for a B-flat clarinet
      \transpose bes c' \clarinetMusic
    }
  >>
  \new StaffGroup = "StaffGroup_brass" <<
    \new Staff = "Staff_hornI" {
      \set Staff.instrumentName = #"Horn in F"
      \transposition f
      \transpose f c' \hornMusic
    }
    \new Staff = "Staff_trumpet" {
      \set Staff.instrumentName = #"Trumpet in C"
      \trumpetMusic
    }
  >>
  \new RhythmicStaff = "RhythmicStaff_percussion" <<
    \set RhythmicStaff.instrumentName = #"Percussion"
    \percussionMusic
  >>
}
```

```
\new PianoStaff <<
  \set PianoStaff.instrumentName = #"Piano"
  \new Staff { \pianoRHMUSIC }
  \new Staff { \pianoLHMUSIC }
>>
\new ChoirStaff = "ChoirStaff_choir" <<
  \new Staff = "Staff_soprano" {
    \set Staff.instrumentName = #"Soprano"
    \new Voice = "soprano"
    \sopranoMusic
  }
  \new Lyrics \lyricsto "soprano" { \sopranoLyrics }
  \new GrandStaff = "GrandStaff_altos"
  \with { \accepts Lyrics } <<
    \new Staff = "Staff_altoI" {
      \set Staff.instrumentName = #"Alto I"
      \new Voice = "altoI"
      \altoIMusic
    }
    \new Lyrics \lyricsto "altoI" { \altoILyrics }
    \new Staff = "Staff_altoII" {
      \set Staff.instrumentName = #"Alto II"
      \new Voice = "altoII"
      \altoIIMusic
    }
    \new Lyrics \lyricsto "altoII" { \altoIILyrics }
  >>
  \new Staff = "Staff_tenor" {
    \set Staff.instrumentName = #"Tenor"
    \new Voice = "tenor"
    \tenorMusic
  }
  \new Lyrics \lyricsto "tenor" { \tenorLyrics }
>>
\new StaffGroup = "StaffGroup_strings" <<
  \new GrandStaff = "GrandStaff_violins" <<
    \new Staff = "Staff_violinI" {
      \set Staff.instrumentName = #"Violin I"
      \violinIMusic
    }
    \new Staff = "Staff_violinII" {
      \set Staff.instrumentName = #"Violin II"
      \violinIIMusic
    }
  >>
  \new Staff = "Staff_viola" {
    \set Staff.instrumentName = #"Viola"
    \violaMusic
  }
  \new Staff = "Staff_cello" {
    \set Staff.instrumentName = #"Cello"
    \celloMusic
```

```

}
\new Staff = "Staff_bass" {
    \set Staff.instrumentName = #"Double Bass"
    \bassMusic
}
>>
>>
\layout { }
}

```

The musical score consists of 15 staves, each representing a different instrument. The instruments are listed on the left side of the staves. The score is in common time (4/4) and has a key signature of one sharp (F#). The notes are placed on the first two lines of each staff. Measures 1 and 2 are identical for all instruments.

Instrument	Measure 1 Notes	Measure 2 Notes
Flute	C, E	C, E
Clarinet in B _{flat}	C, D, E, G	C, D, E, G
Horn in F	C, D, E, G	C, D, E, G
Trumpet in C	C, D, E, G	C, D, E, G
Percussion	C, E	C, E
Piano (Upper Octave)	C, E	C, E
Piano (Lower Octave)	C, E	C, E
Soprano	C	C
Alto I	C, E	C, E
Alto II	C, E	C, E
Tenor	C, E	C, E
Violin I	C, E	C, E
Violin II	C, E	C, E
Viola	C, D, E, G	C, D, E, G
Cello	C, D, E, G	C, D, E, G
Double Bass	C, D, E, G	C, D, E, G

Piano template (simple)

Here is a simple piano staff with some notes.

```

upper = \relative c' {
    \clef treble
    \key c \major
    \time 4/4
}

```

```


    a4 b c d
}

lower = \relative c {
  \clef bass
  \key c \major
  \time 4/4

  a2 c
}

\score {
  \new PianoStaff <-
    \set PianoStaff.instrumentName = #"Piano"
    \new Staff = "upper" \upper
    \new Staff = "lower" \lower
  >>
  \layout { }
  \midi { }
}

```



Piano template with centered lyrics

Instead of having a full staff for the melody and lyrics, lyrics can be centered between the staves of a piano staff.

```

upper = \relative c' {
  \clef treble
  \key c \major
  \time 4/4

  a4 b c d
}


lower = \relative c {
  \clef bass
  \key c \major
  \time 4/4

  a2 c
}

text = \lyricmode {
  Aaa Bee Cee Dee
}

```

```
\score {
    \new GrandStaff <<
        \new Staff = upper { \new Voice = "singer" \upper }
        \new Lyrics \lyricsto "singer" \text
        \new Staff = lower { \lower }
    >>
    \layout {
        \context {
            \GrandStaff
            \accepts "Lyrics"
        }
        \context {
            \Lyrics
            \consists "Bar_engraver"
        }
    }
    \midi { }
}
```



Piano template with melody and lyrics

Here is a typical song format: one staff with the melody and lyrics, with piano accompaniment underneath.

```
melody = \relative c' {
    \clef treble
    \key c \major
    \time 4/4

    a b c d
}

text = \lyricmode {
    Aaa Bee Cee Dee
}

upper = \relative c' {
    \clef treble
    \key c \major
    \time 4/4

    a4 b c d
}

lower = \relative c {
    \clef bass
```


```

\key c \major
\time 4/4

a2 c
}

\score {
  <<
  \new Voice = "mel" { \autoBeamOff \melody }
  \new Lyrics \lyricsto mel \text
  \new PianoStaff <<
    \new Staff = "upper" \upper
    \new Staff = "lower" \lower
  >>
  >>
  \layout {
    \context { \Staff \RemoveEmptyStaves }
  }
  \midi { }
}

```



SATB Choir template - four staves

SATB choir template (four staves)

```

global = {
  \key c \major
  \time 4/4
  \dynamicUp
}
sopranonotes = \relative c' {
  c2 \p \< d c d \f
}
sopranowords = \lyricmode { do do do do }
altonotes = \relative c' {
  c2\p d c d
}
altowords = \lyricmode { re re re re }
tenornotes = {
  \clef "G_8"
  c2\mp d c d
}

```

```
tenorwords = \lyricmode { mi mi mi mi }
bassnotes = {
    \clef bass
    c2\mf d c d
}
basswords = \lyricmode { mi mi mi mi }

\score {
    \new ChoirStaff <<
        \new Staff <<
            \new Voice = "soprano" <<
                \global
                \sopranonotes
            >>
            \lyricsto "soprano" \new Lyrics \sopranowords
        >>
        \new Staff <<
            \new Voice = "alto" <<
                \global
                \altonotes
            >>
            \lyricsto "alto" \new Lyrics \altowords
        >>
        \new Staff <<
            \new Voice = "tenor" <<
                \global
                \tenornotes
            >>
            \lyricsto "tenor" \new Lyrics \tenorwords
        >>
        \new Staff <<
            \new Voice = "bass" <<
                \global
                \bassnotes
            >>
            \lyricsto "bass" \new Lyrics \basswords
        >>
    >>
}
```



Score for diatonic accordion

A template to write a score for a diatonic accordion.

- There is a horizontal staff indicating if the accordion must be pushed (thick line) or pulled (thin line)
- There is a small rhythmic staff with lyrics that describes the bass buttons to press. The bar lines are made from gridlines
- The tabulator staff for diatonic accordions shows the geographic position of the buttons and not (as for every other instrument) the pitch of the notes; the keys on the melody-side of the accordion are placed in three columns and about 12 rows

In the tabulator staff notation the outermost column is described with notes between lines, the innermost column is described with notes between lines and a cross as accidental, and the middle column is described with notes on a line, whereby the row in the middle is represented on the middle line in the staff.

Some words to transpose piano notes to the diatonic accordion:

1. Every diatonic accordion is built for some keys only (for example, for the keys of C major and F major), so it is important to transpose a piano melody to match one of these keys. Transpose the source code, not only the output because this code is required later on to translate it once more to the tabulator staff. This can be done with the command `displayLilyMusic`.
2. You have to alternate the push- and pull-direction of the accordion regularly. If the player has a too long part to pull the accordion gets broken. On the other hand, some harmonies are only available in one direction. Considering this, decide which parts of the melody are the push-parts and which the pull-parts.
3. For each pull- or push-part translate the piano notes to the according tabulature representation.

This snippet comes with a useful optional macro for the jEdit text editor.

```
verse = \lyricmode { Wie gross bist du! Wie gross bist du! }
```

```
harmonies = \new ChordNames \chordmode {
  \germanChords
  \set chordChanges = ##t
  bes8 bes8 bes8
  es2 f
  bes1
```

```
}
```

```
NoStem = { \hide Stem }
NoNoteHead = \hide NoteHead
ZeroBeam = \override Beam.positions = #'(0 . 0)

staffTabLine = \new Staff \with {
  \remove "Time_signature_engraver"
  \remove "Clef_engraver"
} {
  \override Staff.StaffSymbol.line-positions = #'(0)
  % Shows one horizontal line. The vertical line (simulating a bar-line) is simulated with a
  \set Staff.midiInstrument = #"choir aahs"
  \key c \major
  \relative c' {
    % disable the following line to see the noteheads while writing the song
    \NoNoteHead
    \override NoteHead.no-ledgers = ##t

    % The beam between 8th-notes is used to draw the push-line
    % How to fast write the push-lines:
    % 1. write repeatedly 'c c c c c c c c |' for the whole length of the song
    % 2. uncomment the line \NoNoteHead
    % 3. compile
    % 4. Mark the positions on which push/pull changes.
    %     In the score-picture click on the position the push- or pull-part starts■
    %         (on the noteHead, the cursor will change to a hand-icon).
    %     The cursor in the source code will jump just at this position.
    %     a) If a push-part starts there, replace the 'c' by an 'e['
    %     b) If a pull-part starts there, replace the 'c' by an 's'
    % 5. Switch into 'overwrite-mode' by pressing the 'ins' key.
    % 6. For the pull-parts overwrite the 'c' with 's'
    % 7. For every push-part replace the last 'c' with 'e]'
    %     8. Switch into 'insert-mode' again
    % 9. At last it should look like e.g. (s s e[ c | c c c c c c c | c c c c c e] s s)■
    % 10. re-enable the line \NoNoteHead
    \autoBeamOff
    \ZeroBeam
    s8 s s e[ c c c c c e] | s s s s s
  }
}

%{
%}

% Accordion melody in tabulator score
% 1. Place a copy of the piano melody below
% 2. Separate piano melody into pull- and push-parts according to the staffTabLine you've al
% 3. For each line: Double the line. Remark the 1st one (Keeps unchanged as reference) and t
%     or the macros 'conv2diaton push.bsh' and 'conv2diaton pull.bsh'
% Tips:
```

% - In jEdit Search & Replace mark the Option 'Keep Dialog'

```
AccordionTabTwoCBesDur = {
    % pull 1
    %<f' bes'>8 <f' a'>8 <d' bes'>8 |
    <g' a''>8 <g' b''>8 <e' a''>8 |
    % push 2
    %<g' c''>4 <f' d''> <g' ees''> <f' a'> |
    <g' a''>4 <d' eisis''> <g' bisis''> <d' f''> |
    % pull 3
    % <f' bes'>2 r8 }
    <g' a''>2 r8 }

AccordionTab= { \dynamicUp
    % 1. Place a copy of the piano melody above
    % 2. Separate piano melody into pull- and push-parts according to the staffTabLine you've
    % 3. For each line: Double the line. Remark the 1st one (Keeps unchanged as reference) and
    %     change the second line using the transformation paper
    % Tips:
    % - In jEdit Search & Replace mark the Option 'Keep Dialog'
    % -
    \AccordionTabTwoCBesDur
}
```

```
\layout {
    \context {
        \Score
        % The vertical line (simulating a bar-line) in
        % the staffBassRhytm is a gridline
        \consists "Grid_line_span_engraver"
    }
    \context {
        \Staff
        \consists "Grid_point_engraver"
        gridInterval = #(ly:make-moment 4/4) % 4/4 - tact. How many beats per bar
        % The following line has to be adjusted O-F-T-E-N.
        \override GridPoint.Y-extent = #'(-2 . -21)
    }
    \context {
        \ChoirStaff
        \remove "System_start_delimiter_engraver"
    }
}

staffVoice = \new Staff = astaffvoice {
    \time 4/4
    \set Staff.instrumentName = "Voice"
    \set Staff.midiInstrument = "voice oohs"
    \key bes \major
    \partial 8*3
```

```

\clef treble
{
  \context Voice = "melodyVoi"
  { <f' bes'>8 <f' a'>8 <d' bes'>8 | <g' c''>4 <f' d''> <g' es''> <f' a'> | <f' bes'>2 r8
    \bar "|."
}
}

staffAccordionMel =
\new Staff \with { \remove "Clef_engraver" } {
  \accidentalStyle forget %Set the accidentals (Vorzeichen) for each note,
  %do not remember them for the rest of the measure.
  \time 4/4
  \set Staff.instrumentName="Accordion"
  \set Staff.midiInstrument="voice oohs"
  \key c \major
  \clef treble
  { \AccordionTab \bar "|." }
}

AltOn =
#define-music-function (parser location mag) (number?)
#{ \override Stem.length = #(* 7.0 mag)
  \override NoteHead.font-size =
#(inexact->exact (* (/ 6.0 (log 2.0)) (log mag))) #}

AltOff = {
  \revert Stem.length
  \revert NoteHead.font-size
}

BassRhytm = {s4 s8 | c2 c2 | c2 s8 }
LyricBassRhythmI= \lyricmode { c b | c }

staffBassRhytm =
\new Staff = staffbass \with { \remove "Clef_engraver" } {
  % This is not a RhythmicStaff because it must be possible to append lyrics.

  \override Score.GridLine.extra-offset = #'( 13.0 . 0.0 ) % x.y
  \override Staff.StaffSymbol.line-positions = #'( 0 )
  % Shows one horizontal line. The vertical line (simulating a bar-line) is simulated by a g
  % Search for 'grid' in this page to find all related functions
  \time 4/4
{
  \context Voice = "VoiceBassRhytm"
  \stemDown \AltOn #0.6
  \relative c'
  {
    \BassRhytm
  }
  \AltOff
  \bar "|."
}

```

```

        }
    }

\score {
    \new ChoirStaff <<
        \harmonies
        \staffVoice
        \context Lyrics = "lmelodyVoi"
            \with { alignBelowContext = astaffvoice }
            \lyricsto melodyVoi \verse
        \staffAccordionMel
        \staffTabLine
        \staffBassRhytm
        \context Lyrics = "lBassRhytmAboveI"
            \with { alignAboveContext = staffbass }
            \lyricsto VoiceBassRhytm \LyricBassRhythml
    >>
}
%}

```

The musical score consists of three staves. The top staff is for the Voice, starting with a G clef. It contains five measures: the first measure has a C note, the second has a B chord, the third has an E-flat chord, the fourth has an F note, and the fifth has a B chord. Below the voice lyrics 'Wie gross bist du! Wie gross bist du!' are written. The middle staff is for the Accordion, starting with a C note. It contains four measures: the first has a C note, the second has a B chord, the third has an E-flat chord, and the fourth has a B chord. The bottom staff is a bass staff, also starting with a C note. It contains three measures: the first has a C note, the second has a B note, and the third has a C note. The entire score is in 4/4 time.

Single staff template with notes lyrics and chords

This template allows the preparation of a song with melody, words, and chords.

```

melody = \relative c' {
    \clef treble
    \key c \major
    \time 4/4

    a4 b c d
}

```

```

text = \lyricmode {
    Aaa Bee Cee Dee
}

```

```

harmonies = \chordmode {


```

```

    a2 c
}

\score {
  <<
  \new ChordNames {
    \set chordChanges = ##t
    \harmonies
  }
  \new Voice = "one" { \autoBeamOff \melody }
  \new Lyrics \lyricsto "one" \text
  >>
  \layout { }
  \midi { }
}

```



Single staff template with notes lyrics chords and frets

Here is a simple lead sheet template with melody, lyrics, chords and fret diagrams.

```

verseI = \lyricmode {
  \set stanza = #"1."
  This is the first verse
}

verseII = \lyricmode {
  \set stanza = #"2."
  This is the second verse.
}

theChords = \chordmode {
  % insert chords for chordnames and fretboards here
  c2 g4 c
}

staffMelody = \relative c' {
  \key c \major
  \clef treble
  % Type notes for melody here
  c4 d8 e f4 g
  \bar "|."
}


\score {
  <<
  \context ChordNames { \theChords }
  \context FretBoards { \theChords }
  \new Staff {

```

```

\context Voice = "voiceMelody" { \staffMelody }
}
\new Lyrics = "lyricsI" {
  \lyricsto "voiceMelody" \verseI
}
\new Lyrics = "lyricsII" {
  \lyricsto "voiceMelody" \verseII
}
>>
\layout { }
\midi { }
}

```



1. This is the first verse
2. This is the second verse.

Single staff template with notes and chords

Want to prepare a lead sheet with a melody and chords? Look no further!

```

melody = \relative c' {
  \clef treble
  \key c \major
  \time 4/4

  f4 e8[ c] d4 g
  a2 ~ a
}

harmonies = \chordmode {
  c4:m f:min7 g:maj c:aug
  d2:dim b:sus
}

\score {
  <<
  \new ChordNames {
    \set chordChanges = ##t
    \harmonies
  }
  \new Staff \melody
  >>
  \layout{ }
  \midi { }
}

```

Cm Fm⁷ G[△] C+ D[°] B

Single staff template with notes and lyrics

This small template demonstrates a simple melody with lyrics. Cut and paste, add notes, then words for the lyrics. This example turns off automatic beaming, which is common for vocal parts. To use automatic beaming, change or comment out the relevant line.

```
melody = \relative c' {
    \clef treble
    \key c \major
    \time 4/4

    a4 b c d
}

text = \lyricmode {
    Aaa Bee Cee Dee
}

\score{
    <<
        \new Voice = "one" {
            \autoBeamOff
            \melody
        }
        \new Lyrics \lyricsto "one" \text
    >>
    \layout { }
    \midi { }
}
```

a4 b c d

Aaa Bee Cee Dee

Single staff template with only notes

This very simple template gives you a staff with notes, suitable for a solo instrument or a melodic fragment. Cut and paste this into a file, add notes, and you're finished!

```
melody = \relative c' {
    \clef treble
    \key c \major
    \time 4/4

    a4 b c d
}
```

```
\score {
    \new Staff \melody
    \layout { }
```

```
\midi { }
```



String quartet template (simple)

This template demonstrates a simple string quartet. It also uses a \global section for time and key signatures

```
global = {
    \time 4/4
    \key c \major
}

violinOne = \new Voice \relative c' {
    \set Staff.instrumentName = #"Violin 1"

    c2 d
    e1

    \bar "|."
}

violinTwo = \new Voice \relative c' {
    \set Staff.instrumentName = #"Violin 2"

    g2 f
    e1

    \bar "|."
}

viola = \new Voice \relative c' {
    \set Staff.instrumentName = #"Viola"
    \clef alto

    e2 d
    c1

    \bar "|."
}

cello = \new Voice \relative c' {
    \set Staff.instrumentName = #"Cello"
    \clef bass

    c2 b
    a1

    \bar "|."
}
```

```
}
```

```
\score {
    \new StaffGroup <<
        \new Staff << \global \violinOne >>
        \new Staff << \global \violinTwo >>
        \new Staff << \global \viola >>
        \new Staff << \global \cello >>
    >>
    \layout { }
    \midi { }
}
```

String quartet template with separate parts

The “String quartet template” snippet produces a nice string quartet, but what if you needed to print parts? This new template demonstrates how to use the `\tag` feature to easily split a piece into individual parts.

You need to split this template into separate files; the filenames are contained in comments at the beginning of each file. `piece.ly` contains all the music definitions. The other files – `score.ly`, `vn1.ly`, `vn2.ly`, `vla.ly`, and `vlc.ly` – produce the appropriate part.

Do not forget to remove specified comments when using separate files!

```
%%%%% piece.ly
%%%%% (This is the global definitions file)
```

```
global= {
    \time 4/4
    \key c \major
}

Violinone = \new Voice { \relative c' {
    \set Staff.instrumentName = #"Violin 1 "
    c2 d e1
}
\bar "|." } %*****Violinone*****
```

```
Violintwo = \new Voice { \relative c' {
    \set Staff.instrumentName = #"Violin 2 "
}
```

```
g2 f e1

\bar "|." }} %*****  
Viola = \new Voice { \relative c' {  
    \set Staff.instrumentName = #"Viola"  
    \clef alto

e2 d c1

\bar "|." }} %*****  
Cello = \new Voice { \relative c' {  
    \set Staff.instrumentName = #"Cello"  
    \clef bass

c2 b a1

\bar "|." }} %*****  
  
music = {  
    <<  
        \tag #'score \tag #'vn1 \new Staff { << \global \Violinone >> }  
        \tag #'score \tag #'vn2 \new Staff { << \global \Violintwo >> }  
        \tag #'score \tag #'vla \new Staff { << \global \Viola >> }  
        \tag #'score \tag #'vlc \new Staff { << \global \Cello >> }  
    >>  
}  
  
%%% These are the other files you need to save on your computer  
  
%%%%% score.ly  
%%%%% (This is the main file)  
  
%%% uncomment the line below when using a separate file  
\include "piece.ly"  
#(set-global-staff-size 14)  
\score {  
    \new StaffGroup \keepWithTag #'score \music  
    \layout { }  
    \midi { }  
}  
  
%{ Uncomment this block when using separate files  
  
%%%%% vn1.ly  
%%%%% (This is the Violin 1 part file)  
  
\include "piece.ly"  
\score {  
    \keepWithTag #'vn1 \music  
    \layout { }
```

```
}
```

```
%%%%% vn2.ly
```

```
%%%%% (This is the Violin 2 part file)
```

```
\include "piece.ly"
\score {
  \keepWithTag #'vn2 \music
  \layout { }
}
```

```
%%%%% vla.ly
```

```
%%%%% (This is the Viola part file)
```

```
\include "piece.ly"
\score {
  \keepWithTag #'vla \music
  \layout { }
}
```

```
%%%%% vlc.ly
```

```
%%%%% (This is the Cello part file)
```

```
\include "piece.ly"
\score {
  \keepWithTag #'vlc \music
  \layout { }
}
```

```
%}
```

The musical score shows four staves for Violin 1, Violin 2, Viola, and Cello. The key signature for all instruments is C major (one sharp). The time signature is common time (indicated by 'C'). The first measure for each instrument contains one note: Violin 1 has a quarter note followed by a half note; Violin 2 has a half note followed by a quarter note; Viola has a half note followed by a quarter note; and Cello has a half note followed by a quarter note.

Vocal ensemble template with automatic piano reduction

This template adds an automatic piano reduction to the standard SATB vocal score demonstrated in “Vocal ensemble template”. This demonstrates one of the strengths of LilyPond – you can use a music definition more than once. If any changes are made to the vocal notes (say, `tenorMusic`), then the changes will also apply to the piano reduction.

```
\paper {
  top-system-spacing #'basic-distance = #10
```

```
score-system-spacing #'basic-distance = #20
system-system-spacing #'basic-distance = #20
last-bottom-spacing #'basic-distance = #10
}

global = {
    \key c \major
    \time 4/4
}

sopMusic = \relative c' {
    c4 c c8[( b)] c4
}
sopWords = \lyricmode {
    hi hi hi hi
}

altoMusic = \relative c' {
    e4 f d e
}
altoWords =\lyricmode {
    ha ha ha ha
}

tenorMusic = \relative c' {
    g4 a f g
}
tenorWords = \lyricmode {
    hu hu hu hu
}

bassMusic = \relative c {
    c4 c g c
}
bassWords = \lyricmode {
    ho ho ho ho
}


\score {
    <<
    \new ChoirStaff <<
        \new Lyrics = "sopranos" \with {
            % This is needed for lyrics above a staff
            \override VerticalAxisGroup.staff-affinity = #DOWN
        }
        \new Staff = "women" <<
            \new Voice = "sopranos" { \voiceOne << \global \sopMusic >> }
            \new Voice = "altos" { \voiceTwo << \global \altoMusic >> }
        >>
        \new Lyrics = "altos"
        \new Lyrics = "tenors" \with {
            % This is needed for lyrics above a staff
        }
    >>
}
```

```

\override VerticalAxisGroup.staff-affinity = #DOWN
}

\new Staff = "men" <<
  \clef bass
  \new Voice = "tenors" { \voiceOne << \global \tenorMusic >> }
  \new Voice = "basses" { \voiceTwo << \global \bassMusic >> }
>>
\new Lyrics = "basses"
\context Lyrics = "sopranos" \lyricsto "sopranos" \sopWords
\context Lyrics = "altos" \lyricsto "altos" \altoWords
\context Lyrics = "tenors" \lyricsto "tenors" \tenorWords
\context Lyrics = "basses" \lyricsto "basses" \bassWords
>>
\new PianoStaff <<
  \new Staff <<
    \set Staff.printPartCombineTexts = ##f
    \partcombine
    << \global \sopMusic >>
    << \global \altoMusic >>
>>
\new Staff <<
  \clef bass
  \set Staff.printPartCombineTexts = ##f
  \partcombine
  << \global \tenorMusic >>
  << \global \bassMusic >>
>>
>>
>>
}

```



Vocal ensemble template with lyrics aligned below and above the staves

This template is basically the same as the simple “Vocal ensemble” template, with the exception that here all the lyrics lines are placed using `alignAboveContext` and `alignBelowContext`.

```
global = {
    \key c \major
    \time 4/4
}

sopMusic = \relative c' {
    c4 c c8[( b)] c4
}
sopWords = \lyricmode {
    hi hi hi hi
}

altoMusic = \relative c' {
    e4 f d e
}
altoWords = \lyricmode {
    ha ha ha ha
}

tenorMusic = \relative c' {
    g4 a f g
}
tenorWords = \lyricmode {
    hu hu hu hu
}

bassMusic = \relative c {
    c4 c g c
}
bassWords = \lyricmode {
    ho ho ho ho
}

\score {
    \new ChoirStaff <<
        \new Staff = "women" <<
            \new Voice = "sopranos" { \voiceOne << \global \sopMusic >> }
            \new Voice = "altos" { \voiceTwo << \global \altoMusic >> }
        >>
        \new Lyrics \with { alignAboveContext = #"women" }
            \lyricsto "sopranos" \sopWords
        \new Lyrics \with { alignBelowContext = #"women" }
            \lyricsto "altos" \altoWords
    % we could remove the line about this with the line below, since
    % we want the alto lyrics to be below the alto Voice anyway.
    % \new Lyrics \lyricsto "altos" \altoWords

    \new Staff = "men" <<
```

```
\clef bass
\new Voice = "tenors" { \voiceOne << \global \tenorMusic >> }
\new Voice = "basses" { \voiceTwo << \global \bassMusic >> }
>>
\new Lyrics \with { alignAboveContext = #"men" }
  \lyricsto "tenors" \tenorWords
\new Lyrics \with { alignBelowContext = #"men" }
  \lyricsto "basses" \bassWords
% again, we could replace the line above this with the line below.
% \new Lyrics \lyricsto "basses" \bassWords
>>
}
```



Vocal ensemble template with verse and refrain

This template creates a score which starts with a solo verse and continues into a refrain for two voices. It also demonstrates the use of spacer rests within the \global variable to define meter changes (and other elements common to all parts) throughout the entire score.

```
global = {
  \key g \major

  % verse
  \time 3/4
  s2.*2
  \break

  % refrain
  \time 2/4
  s2*2
  \bar "| ."

}

SoloNotes = \relative g' {
  \clef "treble"

  % verse
  g4 g g |
  b4 b b |

  % refrain
}
```

```
R2*2 |  
}  
  
SoloLyrics = \lyricmode {  
    One two three |  
    four five six |  
}  
  
SopranoNotes = \relative c' {  
    \clef "treble"  
  
    % verse  
    R2.*2 |  
  
    % refrain  
    c4 c |  
    g4 g |  
}  
  
SopranoLyrics = \lyricmode {  
    la la |  
    la la |  
}  
  
BassNotes = \relative c {  
    \clef "bass"  
  
    % verse  
    R2.*2 |  
  
    % refrain  
    c4 e |  
    d4 d |  
}  
  
BassLyrics = \lyricmode {  
    dum dum |  
    dum dum |  
}  
  
\score {  
    <<  
        \new Voice = "SoloVoice" << \global \SoloNotes >>  
        \new Lyrics \lyricsto "SoloVoice" \SoloLyrics  
  
        \new ChoirStaff <<  
            \new Voice = "SopranoVoice" << \global \SopranoNotes >>  
            \new Lyrics \lyricsto "SopranoVoice" \SopranoLyrics  
  
            \new Voice = "BassVoice" << \global \BassNotes >>  
            \new Lyrics \lyricsto "BassVoice" \BassLyrics  
        >>  
}
```

```
>>
\layout {
  ragged-right = ##t
  \context { \Staff
    % these lines prevent empty staves from being printed
    \RemoveEmptyStaves
    \override VerticalAxisGroup.remove-first = ##t
  }
}
}
```



Vocal ensemble template

Here is a standard four-part SATB vocal score. With larger ensembles, it is often useful to include a section which is included in all parts. For example, the time signature and key signature are almost always the same for all parts. Like in the “Hymn” template, the four voices are regrouped on only two staves.

```
\paper {
  top-system-spacing #'basic-distance = #10
  score-system-spacing #'basic-distance = #20
  system-system-spacing #'basic-distance = #20
  last-bottom-spacing #'basic-distance = #10
}

global = {
  \key c \major
  \time 4/4
}

sopMusic = \relative c' {
  c4 c c8[( b)] c4
}
sopWords = \lyricmode {
  hi hi hi hi
}

altoMusic = \relative c' {
  e4 f d e
}
```

```
}

altoWords = \lyricmode {
    ha ha ha ha
}

tenorMusic = \relative c' {
    g4 a f g
}
tenorWords = \lyricmode {
    hu hu hu hu
}

bassMusic = \relative c {
    c4 c g c
}
bassWords = \lyricmode {
    ho ho ho ho
}

\score {

    \new ChoirStaff <<
        \new Lyrics = "sopranos" \with {
            % this is needed for lyrics above a staff
            \override VerticalAxisGroup.staff-affinity = #DOWN
        }
        \new Staff = "women" <<
            \new Voice = "sopranos" {
                \voiceOne
                << \global \sopMusic >>
            }
            \new Voice = "altos" {
                \voiceTwo
                << \global \altoMusic >>
            }
        >>
        \new Lyrics = "altos"
        \new Lyrics = "tenors" \with {
            % this is needed for lyrics above a staff
            \override VerticalAxisGroup.staff-affinity = #DOWN
        }
        \new Staff = "men" <<
            \clef bass
            \new Voice = "tenors" {
                \voiceOne
                << \global \tenorMusic >>
            }
            \new Voice = "basses" {
                \voiceTwo << \global \bassMusic >>
            }
        >>
        \new Lyrics = "basses"
        \context Lyrics = "sopranos" \lyricsto "sopranos" \sopWords
}
```

```
\context Lyrics = "altos" \lyricsto "altos" \altoWords
\context Lyrics = "tenors" \lyricsto "tenors" \tenorWords
\context Lyrics = "basses" \lyricsto "basses" \bassWords
>>
}
```

A musical score for three voices: Alto, Tenor, and Bass. The Alto voice (top) sings "hi" four times, with the fourth note having a fermata. The Tenor voice (middle) sings "ha" four times. The Bass voice (bottom) sings "hu" four times. The Alto part also sings "ho" four times. The music is in common time, with a key signature of C. The vocal parts are separated by vertical bar lines.